



ORDER/NERC/276/2021

**BEFORE THE NIGERIAN ELECTRICITY REGULATORY COMMISSION
IN THE MATTER OF THE EXTRAORDINARY REVIEW OF MULTI-YEAR TARIFF ORDER FOR
KADUNA ELECTRICITY DISTRIBUTION PLC**

1.1. Title

This regulatory instrument may be cited as NERC Order on Performance Improvement Plan (PIP) and Extraordinary Tariff Review Application for Kaduna Electricity Distribution Plc ("KAEDC").

1.2. Commencement

The approved PIP and Capital Expenditure ("CAPEX") programme of KAEDC shall take effect from 1st July 2021 and shall remain effective until 30th June 2026 unless amended by the Commission.

1.3. Context

KAEDC applied to the Commission in November 2019 for a review of the provisions for CAPEX in its Multi-Year Tariff Order ("MYTO") tariffs to support the implementation of its Performance Improvement Plan ("PIP") over the next 5 years. Under the Power Sector Recovery Program (PSRP), it is envisaged that the Commission would implement a robust tariff review process aiming at improving the performance of the Nigerian Electricity Supply Industry ("NESI"). This process involved a review of the capital expenditure allowances in the MYTO model to align with the Performance Improvement Plans (PIPs) of the Distribution Companies (DisCos). The approved PIP and Extraordinary Tariff Application shall form the basis for KAEDC to prioritise the implementation of the proposed CAPEX initiatives. The approved PIPs shall also form the basis for defining KPIs for KAEDC for the next 5 years by the Commission with emphasis on improvement in energy throughput and improved service delivery to the customers.

As part of the Stakeholder Consultation Process for Extra Ordinary Tariff Review, the Commission held public hearings to consider the applications filed by KAEDC in February 2020 and monitored the stakeholders' engagements by KAEDC at different locations within

its franchise. Based on the feedback received during the consultations and subsequent deliberations with various stakeholders, the Commission approved the Serviced-Based Tariff (SBT) effective from the 1st of September 2020 to ensure that rates paid by customers align with the quality of service as measured by the daily average availability of power supply over a 60-day reference period. Further updates to KAEDC's initial PIP submission have been considered as part of this review to align the PIPs with customer expectations of service commitment by KAEDC.

1.4. Summary and Overview of KAEDC's Network/Current State

KAEDC is one of the successor distribution companies ("DisCos") created following the unbundling and privatization of the state-owned Power Utility, the Power Holding Company of Nigeria Plc. The current Board and Management of KAEDC took over the operation of the company on the 4th of December 2014, 13 months after the privatization of other DisCos. The Company is responsible for distributing electricity within the areas of Kaduna, Kebbi, Sokoto, and the Zamfara States in the North-Western part of Nigeria. KAEDC covers approximately 148,588 km² area, with a total population of 16.23 million (based on the 2006 Census) and a customer population of around 560,000. KAEDC consists of 143 Service Centres, covered under 19 Area Offices, supplied via 11 transmission in-feeds. KAEDC is responsible for the offtake of 8% of the total National grid load allocation in accordance with the vesting contract executed with the Nigerian Bulk Electricity Trading Plc ("NBET").

KAEDC, like other distribution companies, is faced with several challenges such as electricity theft, vandalism of distribution equipment, poor maintenance regimen aggravated by lack of a centralized and automated control system, inadequate funding, inadequate metering, meter bypass, poor quality customer database, inadequate IT infrastructure, and low customer willingness to pay, distribution and transmission interface issues, inefficient revenue collection, among others leading to high ATC&C loss levels. Some of these challenges have been addressed, albeit marginally.

Based on the Load Flow Report of 2020, KAEDC has a lot of overloaded 33KV lines, 11KV lines, and injection substations. Furthermore, due to the rapid increase in infrastructural development across its franchise area, the existing injection substations and distribution transformers (DTs) are far below the required number to cover the rapidly developing areas like Millennium City, Kamazo, Morabar Rido, Rigachikun, and Gonin Gora. Similarly, due to potential demand within the industrial areas, there is a need to expand capacity, particularly in locations such as Kalambaina, Olam area (along Abuja-Kaduna express way), and Kudenda.

2


1.5. Stakeholder Consultation

KAEDC had followed a process for stakeholder consultation as directed by the Commission. Several focused group discussions to harness stakeholder's views on the service delivery, future expectations, and preferences were conducted with various customer groups such as the Premium Customers, Manufacturers Association of Nigeria (MAN), and Non-Maximum Demand customers.

Key discussion areas for the stakeholder sessions were:

- Quality and reliability of supply
- Quality of the metering, billing, and payment process
- Consumers perception of the processes
- Consumers relationship management
- Quality of fault complaint and repairs process

Table – 1: KAEDC's Customer Segmentation

<p>1. Premium Customer Group (PCG)</p> <ul style="list-style-type: none"> • High energy consuming group, some of which are potentially eligible customers, usually contribute a large share of the revenue collection • Quality and reliability of supply is currently not good enough, and consequently, all of them use diesel/gas captive generation • Customer service challenges exist • Collection efficiency is less than 100% 	<p>2. Manageable Urban & Rural Areas (MU&RAs)</p> <ul style="list-style-type: none"> • The large concentration of R2 and C1 customers • Network reliability is poor and captive generation is high • More than 65% of customers unmetered • Technical and commercial losses quite uncertain or wrongly accounted for due to the high number of estimated billing • Collection efficiency is generally low
<p>3. Difficult to Manage Rural Areas (DMRAs)</p> <ul style="list-style-type: none"> • Vast geographical area and many customers dispersed in a few thousand communities/villages • Network reliability is very bad • DisCo presence is low and customer service is deficient • Most of the customers are unmetered • Collection efficiency is extremely low 	<p>4. Informal Settlement in Peri-Urban Areas</p> <ul style="list-style-type: none"> • Huge concentration of low-income families • High concentration of unknown customers • High level of ATC&C losses • Network reliability is poor and unsafe • Collection efficiency is extremely low


1.6. Outputs proposed with interventions:

KAEDC proposes to undertake numerous interventions to improve service delivery to the customers. Over the next five years, the proposed interventions will allow KAEDC to achieve but not limited to the following:

- Reduce ATC&C losses from the current level of 58% to 25% in 2025
- Achieve 100% metering of customers by installing 508,000 meters over 5 years
- Improve customer safety and reduce inadvertent accidents
- Increase number of new customers from the current level of 560,000 to 931,723 over 5 years

Table – 2 below provides a snapshot of KAEDC's proposal

Item	Unit	Current	Service Improvement	Year-5 Target	Variance
Customers	#	560,000	371,723	931,723	66.38%
Current ATC&C Loss	%	58%	-33%	25%	-56.90%
Energy Delivered	GWh	1,968	7,030	8,998	357.22%
Average Duration of Supply	(Hrs/Day)	13	7	20	53.85%
Average Frequency of Interruptions	#/day	2	-1	1	-50.00%
Average Duration of Interruptions	Hrs/day	5.96	-3	3.33	-44.06%

4


1.7. Investment Strategies:

Key strategies proposed by KAEDC to attain the targeted service levels over the next 5 years include the following:

1. Implementation of investments and other initiatives in distribution network rehabilitation and upgrade aimed at resolving existing constraints limiting availability and quality of energy supply.
2. Identification of eventual constraints to meeting electricity demand arising from issues affecting high and medium voltage network infrastructure.
3. TCN-DisCo interface projects are required in resolving existing constraints and meeting electricity demand.
4. Installation of metering systems to capture all electrical parameters involved in commercial transactions with NBET and TCN and amounts of energy injected into the network operated by the DisCo.
5. Incorporation of an Incidents Recording and Management System (IRMS) to identify the location and analyze the extent of an interruption in electricity supply and to enable fast resolution and service restoration.
6. Regularization of consumers not registered as customers.
7. Installation of appropriate meters for all the ministries, departments, and agencies at federal, state, and local levels.
8. Incorporation of a Commercial Management System (CMS) to manage all commercial processes: revenue cycle, attending to customers, etc.
9. Incorporation of an Enterprise Resource Planning (ERP) information system to support corporate planning and management of shared services (accounting, finance, human resources, procurement, logistics & information technology).
10. Implementation of a Revenue Protection Project (RPP) supported by Advanced Metering Infrastructure (AMI) to systematically record and monitor consumption of large and medium customers.
11. Incorporation of a Supervisory Control and Data Acquisition System (SCADA) to operate and control HV & MV infrastructure.

Table - 3: Proposed Investment Programme (Amount)

Investment Plan	2021	2022	2023	2024	2025	Total
	N000,000	N000,000	N000,000	N000,000	N000,000	N000,000
Distribution Management Plan	14,076	21,114	17,515	10,557	7,038	70,300
ATC&C Loss Reduction Plan	5,824	8,736	7,280	4,368	2,912	29,120
Customer Service Improvement Plan	994	1,492	1,243	746	497	4,972
Management Improvement Plan	2,692	4,036	3,363	2,018	1,345	13,454
Total	23,586	35,378	29,401	17,689	11,792	117,846

Table – 4: Proposed Investment (Technical)

Item	Unit	Current	Additions/ Construction	Year-5 Target	Variance	PIP Rehabilitation	% of Rehabilitation
Network Length 33 kV	Km	9,110	100	9,210	1.10%	3,644	40%
Network Length 11 kV	Km	2,872	340	3,212	11.84%	1,436	50%
Network Length 0.4 kV	Km	27,772	3,836	31,608	13.81%		
MVA distributions transformers	MVA	2911.7	1,990	4,902	68.35%		
# distributions transformers	#	10,054	5,531	15,585	55.01%		
MVA Substations transformers	MVA	946	533	1,479	56.29%		
# Substations transformers	#	100	44	144	44.00%	-	

2.0 Commission's Review

2.1. The Commission's Guideline for PIP Application established criteria for KAEDC to prepare an output-based plan that sets out the service improvement output targets over the planning horizon of 5 years. This plan includes the programs and activities that will lead to the realisation of those outputs, the human and material resources required, the projected costs and analysis of the risk factors, and the proposed mitigation measures. KAEDC's PIP and Extraordinary tariff review application was exposed to a Public Hearing and consultation presided over by a panel of three commissioners in line with the Business Rules of the Commission and the "Regulations on Procedure for Electricity Tariff Reviews in the Nigerian Electricity Supply Industry" in February 2020. The Hearing provided an avenue for customers, interested parties, and expert intervenors to critically examine KAEDC's proposal and the associated expected improvement in service levels. KAEDC was further directed to conduct stakeholders' (customers') engagements at various locations within its franchise area which were attended to and monitored by the staff of the Commission.

2.2. Following the outcome of the public consultation, the Commission had vide Order NERC/198/2020 required KAEDC to update its PIP and Extraordinary Tariff Review Application by disaggregating its respective service areas and/or customers per quality of service in order to align rates payable by customers with the quality of supply ("service-based tariffs"). A further review of KAEDC's updated submission was considered using the following criteria:

- i. completeness and consistency of the description of each component of the PIP;
- ii. compliance of each component with the Guidelines for preparation of PIPs issued by the Commission;
- iii. analysis of expected results/outcomes from the implementation of each component including the mitigants provided for addressing identified challenges that may hinder the achievement of target;
- iv. thorough price benchmarking and other relevant approaches to the estimation of resources (physical amounts and related OpEx and CapEx) for each component;
- v. determining if the cost and timeline for delivering the output is efficient;
- vi. assessing the efficiency of the proposed financing arrangement;
- vii. analysing the level of technology/modernization leap proposed going forward;
- viii. determining and analysing the overall level of efficiency improvement proposed.

3.0 Results of the Review

The Commission, having considered KAEDC's PIP and Extraordinary Tariff Review Application in line with the provision of EPSRA and relevant regulations, approved the PIP and CAPEX programme over 5 years as provided in Table – 5 and Table – 6 below. Summary of approved projects for Year-1 and Year-2 are also provided in Table – 7, while a detailed list of approved projects for Year-1 and Year-2 are provided in Appendices 1 and 2 respectively.

Table – 5: Approved 5-year PIP and CAPEX Programme

Year	2021	2022	2023	2024	2025	Total
	Period - 1	Period - 2	Period - 3	Period - 4	Period - 5	Period 1 – 5
	₦000,000	₦000,000	₦000,000	₦000,000	₦000,000	₦000,000
Annual Approved CAPEX	22,805.11	22,805.11	22,805.11	22,805.11	22,805.11	114,025.54

7



Table – 6: KAEDC's Approved 5-year PIP and CAPEX Programme

5-Year Approved PIP	
	<i>A000,000</i>
Total CAPEX	<u>114,025.5</u>
Distribution Network Capex	85,705.7
Construction of 33kV Feeder	2,632.0
Rehabilitation of 33kV Feeder	14,745.0
Construction of 11kV Feeder	4,262.5
Rehabilitation of 11kV Feeder	9,076.3
Construction of 0.400kV Feeder	16,493.8
Distributions transformers (plan)	18,266.4
MVA Substations transformers (plan)	20,229.7
ATC&C Loss Reduction Plan (total)	10,765.8
Customer Service Improvement Plan	513.1
IT Investments (SCADA+GIS+ERP+HSE)	11,060.6
SCADA Initiatives	7869.3
Other IT projects	
GIS Improvement	516.7
ERP System Infrastructure	995.2
HSE Initiatives	747.0
AMI Network Metering	932.4
Customer Metering Capex	-
Network Metering Capex	5,056.6
Others	923.7

Handwritten signatures and initials in blue ink.

Table – 7: KAEDC's Approved PIP and CAPEX Programme for 2021 and 2022

Approved PIP	2021	2022
	<i>N000,000</i>	<i>N000,000</i>
Total CAPEX	<u>22,805.1</u>	<u>22,805.1</u>
Distribution Network Capex	14,847.1	18,915.6
Construction of 33kV Feeder	632.8	420.0
Rehabilitation of 33kV Feeder	1,693.3	1,465.3
Construction of 11kV Feeder	465.0	1,240.0
Rehabilitation of 11kV Feeder	1,078.3	2,552.3
Construction of 0.400kV Feeder	2,336.0	2,982.4
Distributions transformers (plan)	3,590.8	3,715.8
MVA Substations transformers (plan)	5,050.9	6,539.8
ATC&C Loss Reduction Plan (total)	391.5	211.9
Customer Service Improvement Plan	326.2	186.9
IT Investments (SCADA+GIS+ERP+HSE)	2,894.3	2,410.8
SCADA Initiatives	-	-
Other IT projects	1,098.3	1,033.2
GIS Improvement	249.5	249.5
ERP System Infrastructure	426.5	568.7
HSE Initiatives	747.0	-
AMI Network Metering	373.0	559.4
Customer Metering Capex	-	-
Network Metering Capex	3,976.6	1,080.0
Others	369.5	-

9


4.0 Annual Update of PIPs

KAEDC shall be required to provide an annual update to the PIP to reflect the proposed investment programme as part of the Minor Review of Tariffs on a continuous basis. The Commission recognizes this PIP as a dynamic roadmap of where KAEDC envisions to be in the next five (5) years and will continue to evolve in alignment with market development and changes to the operating environment. KAEDC may invest more than the indicated annual CAPEX figure in any particular year on account of front-loading proposed future investments or due to the unanticipated critical investment needs subject to the approval of the Commission.

5.0 Front-loading of CAPEX

KAEDC is at liberty to front-load its CAPEX programmes to attain accelerated service improvements. Front-loading of CAPEX programme in any year shall not exceed annual CAPEX for the following year in line with the framework for continuous update of the PIPs.

6.0 CAPEX Clawback

Annual CAPEX provisions that are unutilized or imprudently expended shall be clawed back during Minor Reviews of Tariffs in line with the requirements of Section 7(a) of Regulations on Procedure for Electricity Tariff Reviews in the NESL.

7.0 Commencement and Effectiveness

The approved PIP and CAPEX programme of KAEDC shall take effect on the 1st day of July 2021 and shall remain effective until the 30th day of June 2026.

8.0 Signature

Dated this 29th day of April 2021



Sanusi Garba
Chairman



Dafe C. Akpeneye
Commissioner

Appendices

Appendix - 1: Details of Planned 2021 Investments for Kaduna Electricity Distribution Company

<i>Distribution Network: lines</i>						
<i>Project Type: Construction of 33kV Feeder</i>						
#	Project Description	Location	Route Length (km)	Project Completion Date (MM - YY)	Expected Impact in MW)	
1	Construction of new 33kv lines	KALAMBAINA	10	Nov-21	8	
2	Construction of new 33kv lines	ZURU	20	Nov-21	4	
3	Construction of new 33kv lines	GIDAN DARE (UNMANNED)	10	Nov-21	5	
4	Construction of new 33kv lines	TAMAJE	20	Nov-21	8	
5	Construction of new 33kv lines	HAYIN DANMANI	20	Nov-21	20	
6	Construction of new 33kv lines	33KV ABU CBN Center Excellence	3	Nov-21	2	
7	Construction of new 33kv lines	ARGUNGU	10	Nov-21	4	
8	Construction of new 33kv lines	MILLENIUM CITY	20	Nov-21	15	
Total			113			



<i>Distribution Network: lines</i>						
<i>Project Type: Rehabilitation of 33kV Feeder</i>						
#	Project Description	Type of Rehabilitation	Location	Route Length (km)	Project Completion Date (MM - YY)	Expected Impact in MW
1	33KV UNGUWAN BORO	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Barnawa	60	September 2021	2.7
2	33KV ABAKPA	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Doka	7	July 2021	0.8
3	33KV DOKA	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Doka	7	July 2021	0.1
4	33KV NAF	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Doka	5	July 2021	2.0
5	33KV WATER WORKS	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Doka	9	July 2021	1.4
6	33KV AREWA	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Makera	7	July 2021	0.8
7	33KV GONIN GORA	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Makera	51	September 2021	0.8
8	33KV KINKINAU	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Rigasa	10	July 2021	1.2
9	33KV MOGADISHU	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Rigasa	6	December 2021	1.4
10	33KV KWARE/UNIVERSITY	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Sokoto	97	September 2021	0.7
11	33KV POWER STATION	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Sokoto	10	July 2021	2.1
12	33KV MAGAMI	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Zamfara	36	September 2021	1.1
13	33KV NNPC GUSAU	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Zamfara	51	July 2021	1.5

14	33KV HANWA	Reconducing, Replacement of Poles, Replacement of Poles accessories	Zaria	2	July 2021	0.5
15	33KV PZ	Reconducing, Replacement of Poles, Replacement of Poles accessories	Zaria	8	July 2021	0.4
Total				366		

Distribution Network: lines

Project Type: Construction of 11KV Feeder

#	Project Description	Location	Route Length (km)	Project Completion Date (MM - YY)	Expected Impact in MW
1	Construction of new 11KV lines with HVDS configuration	KALAMBAINA	16	Nov-21	8
2	Construction of new 11KV lines with HVDS configuration	ZURU	8	Nov-21	4
3	Construction of new 11KV lines with HVDS configuration	GIDAN DARE (JUNMANNED)	8	Nov-21	5
4	Construction of new 11KV lines with HVDS configuration	TAMAJE	16	Nov-21	8
5	Construction of new 11KV lines with HVDS configuration	HAYIN DANMANI	16	Nov-21	20
6	Construction of new 11KV lines	11KV Costain	9	June 2021	1
7	Construction of new 11KV lines	ARGUNGU	5	Jun-21	4.3
8	Construction of new 11KV lines	MILLENIUM CITY	15	Jun-21	15
Total			93		



<i>Distribution Network: lines</i>						
<i>Project Type: Rehabilitation of 11kV Feeder</i>						
#	Project Description	Type of Rehabilitation	Location	Route Length (km)	Project Completion Date (MM - YY)	Expected Impact in MW
1	11KV HIGH COST	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Barnawa	20	July 2021	0.8
2	11KV AHMADU BELLO WAY	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Doka	8	June 2021	11.3
3	11KV CONSTITUTION ROAD	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Doka	23	July 2021	1.4
4	11KV DAWAKI	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Doka	8	June 2021	1.0
5	11KV ISA KAITA	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Doka	13	June 2021	3.5
6	11KV LEGISLATIVE QUARTERS	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Doka	13	June 2021	2.8
7	11KV LUGGARD HALL	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Doka	6	June 2021	1.8
8	11KV NACB	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Doka	13	June 2021	0.3
9	11KV TEACHING HOSPITAL DKA	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Doka	19	July 2021	0.4
10	11KV UNGUWAN RIMI	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Doka	10	June 2021	2.3

11	11KV BULASA	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Kebbi	49	September 2021	0.9
12	11KV GRA KBI	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Kebbi	22	July 2021	0.2
13	11KV GWADANGWAI	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Kebbi	38	July 2021	3.6
14	11KV GWARI AVENUE	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Makera	20	July 2021	8.4
15	11KV NASSARAWA MKR	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Makera	20	July 2021	11.7
16	11KV GOVERNMENT HOUSE KADUNA	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Rigasa	13	June 2021	5.6
17	11KV LEVENTIS	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Rigasa	11	June 2021	1.2
18	11KV POLY ROAD	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Rigasa	20	July 2021	5.1
19	11KV YANTUKWANE	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Rigasa	9	June 2021	1.2
20	11KV KADUNA ROAD	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Sokoto	41	July 2021	0.5
21	11KV LODGE ROAD	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Sokoto	15	July 2021	4.1
22	11KV ABU	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Zaria	30	July 2021	1.4
23	11KV CANTEEN	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Zaria	16	July 2021	2.6
24	11KV GRA ZAR	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Zaria	13	June 2021	0.7
Total				450		



Distribution Network: lines

Project Type: Construction and Rehabilitation of 0-400kV Feeder

#	Project Description	Location	Route Length (km)	Project Completion Date (MM - YY)	Expected Impact in (MW)
1	Rehabilitation of 415KV lines	11KV HIGH COST	17	Aug-21	6
2	Rehabilitation of 415KV lines	11KV AHMADU BELLO WAY	15	Aug-21	6
3	Rehabilitation of 415KV lines	11KV CONSTITUTION ROAD	15	Aug-21	6
4	Rehabilitation of 415KV lines	11KV DAWWAKI	15	Aug-21	6
5	Rehabilitation of 415KV lines	11KV ISA KAITA	15	Aug-21	6
6	Rehabilitation of 415KV lines	11KV LEGISLATIVE QUARTERS	15	Aug-21	6
7	Rehabilitation of 415KV lines	11KV LUGGARD HALL	15	Aug-21	6
8	Rehabilitation of 415KV lines	11KV NACB	15	Aug-21	6
9	Rehabilitation of 415KV lines	11KV TEACHING HOSPITAL DKA	15	Aug-21	6
10	Rehabilitation of 415KV lines	11KV UNGUWAN RIMI	17	Aug-21	6
11	Rehabilitation of 415KV lines	11KV BULASA	16	Aug-21	6
12	Rehabilitation of 415KV lines	11KV GRA KBI	15	Aug-21	6
13	Rehabilitation of 415KV lines	11KV GWADANGWALI	16	Aug-21	6
14	Rehabilitation of 415KV lines	11KV GWARI AVENUE	12	Aug-21	6
15	Rehabilitation of 415KV lines	11KV NASSARAWA MKR	15	Aug-21	6
16	Rehabilitation of 415KV lines	11KV GOVERNMENT HOUSE KADUNA	15	Aug-21	6
17	Rehabilitation of 415KV lines	11KV LEVENTIS	17	Aug-21	6
18	Rehabilitation of 415KV lines	11KV POLY ROAD	15	Aug-21	6
19	Rehabilitation of 415KV lines	11KV YANTUKWANE	17	Aug-21	6
20	Rehabilitation of 415KV lines	11KV KADUNA ROAD	15	Aug-21	6
21	Rehabilitation of 415KV lines	11KV LODGE ROAD	15	Aug-21	6
22	Rehabilitation of 415KV lines	11KV ABU	15	Aug-21	6
23	Rehabilitation of 415KV lines	11KV CANTEEN	17	Aug-21	6
24	Rehabilitation of 415KV lines	11KV GRA ZAR	15	Aug-21	6
25	Construction of new 415 lines	KALAMBAINA	32	Dec-21	6

26	Construction of new 415 lines	ZURU	16	Dec-21
27	Construction of new 415 lines	GIDAN DARE (UNMANNED)	16	Dec-21
28	Construction of new 415 lines	TAMAE	32	Dec-21
29	Construction of new 415 lines	HAYIN DANMANI	32	Dec-21
30	Construction of new 415 lines	11KV Costain	16	Dec-21
31	Construction of new 415 lines	ARGUNGU	8	Dec-21
32	Construction of new 415 lines	MILLENIUM CITY	28	Dec-21
Total			541	

Distribution Network: stations

Project Type: New Construction, Reinforcement and Standardisation of Distribution Sub-station

#	Name of Substation	Transformation Voltage (kV)	Rating - KVA	Type of work (New Construction or Replacement)	Location	Quantity	Project Completion Date (MM - YY)
1	ABDULKADIR	11/0.415	500	Replacement	11KV HIGH COST	1	Sep-21
2	BOTSWANA	11/0.415	300	Replacement	11KV HIGH COST	1	Sep-21
3	BOUNMEDINE	11/0.415	500	Standardisation	11KV HIGH COST	1	Sep-21
4	C. C. 1	11/0.415	500	Replacement	11KV HIGH COST	1	Sep-21
5	CHIROMA	11/0.415	500	New Construction	11KV HIGH COST	1	Sep-21
6	COMPLEX	11/0.415	500	Replacement	11KV HIGH COST	1	Sep-21
7	DANKATO	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
8	ENL HOME 1	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
9	ENL HOME 2	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
10	ENL HOME 3	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
11	GABON	11/0.415	500	Standardisation	11KV HIGH COST	1	Sep-21
12	KUJAMA/MAGANA	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
13	MAKARFI ESTATE	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
14	MALAWI	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
15	MEYERE	11/0.415	500	Standardisation	11KV HIGH COST	1	Sep-21
16	PAN AFRICA	11/0.415	500	Standardisation	11KV HIGH COST	1	Sep-21



17	POST OFFICE	11/0.415	500	Standardisation	11KV HIGH COST	1	Sep-21
18	RWANDA	11/0.415	500	Standardisation	11KV HIGH COST	1	Sep-21
19	SS 1	11/0.415	500	Standardisation	11KV HIGH COST	1	Sep-21
20	SS 2	11/0.415	500	Standardisation	11KV HIGH COST	1	Sep-21
21	SS 3	11/0.415	500	Standardisation	11KV HIGH COST	1	Sep-21
22	SS 4	11/0.415	500	Standardisation	11KV HIGH COST	1	Sep-21
23	TANZANIA	11/0.415	500	Standardisation	11KV HIGH COST	1	Sep-21
24	UGUWAR SUNDAY 4	11/0.415	500	Standardisation	11KV HIGH COST	1	Sep-21
#	UGANDA	11/0.415	500	Standardisation	11KV HIGH COST	1	Sep-21
#	UNT 1	11/0.415	500	Standardisation	11KV HIGH COST	1	Sep-21
	UNT 2	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	YAKWO	11/0.415	500	Standardisation	11KV HIGH COST	1	Sep-21
	ZAIRE	11/0.415	500	Standardisation	11KV HIGH COST	1	Sep-21
	ZAMBIA CRESCENT	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	RWANDA 2	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	ENI HOMES 4	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	AHMADU AHIDJO ROAD, Pole No. 3	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	AHMADU AHIDJO ROAD, Pole No. 5	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	AHMADU AHIDJO ROAD, Pole No. 10	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	AHMADU AHIDJO ROAD, Pole No. 13	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	AHMADU AHIDJO ROAD, Pole No. 15	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	GARBA LANE ROAD, Pole No. 18	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	BOUMIDINE ROAD, Pole No. 20	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	BOUMIDINE ROAD, Pole No. 22	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	BOUMIDINE ROAD, Pole No. 24	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	BOUMIDINE ROAD, Pole No. 25	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	BOUMIDINE ROAD, Pole No. 28	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	BOUMIDINE ROAD, Pole No. 29	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	BOUMIDINE ROAD, Pole No. 31	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21

	BOUMIDINE ROAD, Pole No. 32	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	KING HASSAN ROAD, Pole No. 35	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	KING HASSAN ROAD, Pole No. 37	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	MUBOTU ROAD, Pole No. 41	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	MUBOTU ROAD, Pole No. 43	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	AUGUSTINE ADO ROAD, Pole No. 58	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	AUGUSTINE ADO ROAD, Pole No. 60	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	BARRE CLOSE, Pole No. 67	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	ABUBAKAR LADAN ROAD, Pole No. 71	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	ABUBAKAR LADAN ROAD, Pole No. 72	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	ABUBAKAR LADAN ROAD, Pole No. 73	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	UMAR LAWAL MAIYERE ROAD, Pole No. 79	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	UMAR LAWAL MAIYERE ROAD, Pole No. 78	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	UMAR LAWAL MAIYERE ROAD, Pole No. 77	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	BARRE ROAD, Pole No. 82	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	UNITY LINK ROAD, Pole No. 86	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	UNITY LINK ROAD, Pole No. 87	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	UNITY LINK ROAD, Pole No. 88	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	LIVING WATER AVENUE, Pole No. 90	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	LIVING WATER AVENUE, Pole No. 91	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	LIVING WATER AVENUE, Pole No. 92	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	WINNER AVENUE, Pole No. 98	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
	MUBOTU ROAD, Pole No. 101	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21

MUBOTU ROAD, Pole No. 103	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
MUBOTU ROAD, Pole No. 104	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
MUBOTU ROAD, Pole No. 106	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
KADUNA STATE WATERBOARD BARNAWA	11/0.415	300	Standardisation	11KV HIGH COST	1	Sep-21
Ahman Palegi	11/0.415	300	Standardisation	11KV Iso Kaita	1	Sep-21
Alkali Road	11/0.415	300	Standardisation	11KV Iso Kaita	1	Sep-21
Emir of Zazzau	11/0.415	300	Standardisation	11KV Iso Kaita	1	Sep-21
Goro Road	11/0.415	300	Standardisation	11KV Iso Kaita	1	Sep-21
Ibrahim Biu Crescent	11/0.415	300	Standardisation	11KV Iso Kaita	1	Sep-21
Kankio 1	11/0.415	500	Standardisation	11KV Iso Kaita	1	Sep-21
Kankio 2	11/0.415	300	Standardisation	11KV Iso Kaita	1	Sep-21
Katunu/Marrona	11/0.415	500	Standardisation	11KV Iso Kaita	1	Sep-21
Makarfi	11/0.415	500	Standardisation	11KV Iso Kaita	1	Sep-21
New Dawaki	11/0.415	300	Standardisation	11KV Iso Kaita	1	Sep-21
River Close/Jobi	11/0.415	300	Standardisation	11KV Iso Kaita	1	Sep-21
Sand Bath	11/0.415	300	Standardisation	11KV Iso Kaita	1	Sep-21
Sultan /Jobi	11/0.415	500	Standardisation	11KV Iso Kaita	1	Sep-21
Sultan/ Taro	11/0.415	500	Standardisation	11KV Iso Kaita	1	Sep-21
Aliyu Turaki	11/0.415	300	Standardisation	11KV Iso Kaita	1	Sep-21
Kainji/Boyojidda	11/0.415	300	Standardisation	11KV Iso Kaita	1	Sep-21
Kainji/Idoma	11/0.415	500	Standardisation	11KV Iso Kaita	1	Sep-21
Kainji/Yahoya	11/0.415	300	Standardisation	11KV Iso Kaita	1	Sep-21
Sarkin Musulmi	11/0.415	300	Standardisation	11KV Iso Kaita	1	Sep-21
DANJA/MARNONA	11/0.415	300	Standardisation	11KV Iso Kaita	1	Sep-21
Jobi/Idoma	11/0.415	300	Standardisation	11KV Iso Kaita	1	Sep-21
Kashim Ibrahim Road	11/0.415	300	Standardisation	11KV Iso Kaita	1	Sep-21
Kinkio Road	11/0.415	300	Standardisation	11KV Iso Kaita	1	Sep-21
SULTAN/LAMIDO	11/0.415	300	Standardisation	11KV Iso Kaita	1	Sep-21
YARADUA	11/0.415	300	Standardisation	11KV Iso Kaita	1	Sep-21
IBRAHIM BIU ROAD	11/0.415	300	Standardisation	11KV Iso Kaita	1	Sep-21
Raboh by Marrona Road	11/0.415	300	Standardisation	11KV Iso Kaita	1	Sep-21



Abdulhameed road	11/0.415	300	Standardisation	11KV LEGISLATIVE QUARTERS	1	Sep-21
Ashiru road 1	11/0.415	300	Standardisation	11KV LEGISLATIVE QUARTERS	1	Sep-21
Famak School 1	11/0.415	500	Standardisation	11KV LEGISLATIVE QUARTERS	1	Sep-21
Famak School 2	11/0.415	500	Standardisation	11KV LEGISLATIVE QUARTERS	1	Sep-21
Guova road 2	11/0.415	300	Standardisation	11KV LEGISLATIVE QUARTERS	1	Sep-21
Guova road 1	11/0.415	500	Standardisation	11KV LEGISLATIVE QUARTERS	1	Sep-21
Gwaronji road	11/0.415	500	Standardisation	11KV LEGISLATIVE QUARTERS	1	Sep-21
Kamba close	11/0.415	300	Standardisation	11KV LEGISLATIVE QUARTERS	1	Sep-21
Kudan/Danfodio	11/0.415	500	Standardisation	11KV LEGISLATIVE QUARTERS	1	Sep-21
Kudan/Estu Nupe	11/0.415	500	Standardisation	11KV LEGISLATIVE QUARTERS	1	Sep-21
Legislative Ctrs building	11/0.415	500	Standardisation	11KV LEGISLATIVE QUARTERS	1	Sep-21
Pawa road	11/0.415	500	Standardisation	11KV LEGISLATIVE QUARTERS	1	Sep-21
School road	11/0.415	500	Standardisation	11KV LEGISLATIVE QUARTERS	1	Sep-21
auwal aliyu	11/0.415	500	Standardisation	11KV LEGISLATIVE QUARTERS	1	Sep-21
SILVER BELL 1	11/0.415	300	Standardisation	11KV LEGISLATIVE QUARTERS	1	Sep-21
Silver bell 2	11/0.415	300	Standardisation	11KV LEGISLATIVE QUARTERS	1	Sep-21
Damagun	11/0.415	300	Standardisation	11KV Ahmodu Bello Way	1	Sep-21
DITV Sokoto Road	11/0.415	300	Standardisation	11KV Ahmodu Bello Way	1	Sep-21
North Road	11/0.415	500	Standardisation	11KV Ahmodu Bello Way	1	Sep-21
Road Safety	11/0.415	300	Standardisation	11KV Ahmodu Bello Way	1	Sep-21

Savannah Bank	11/0.415	300	Standardisation	11KV Ahmadu Bello Way	1	Sep-21
Siemens Public	11/0.415	300	Standardisation	11KV Ahmadu Bello Way	1	Sep-21
Tolly Wood Row	11/0.415	300	Standardisation	11KV Ahmadu Bello Way	1	Sep-21
TOTAL ABAKPA (DOKA CRESCENT)	11/0.415	500	Standardisation	11KV Ahmadu Bello Way	1	Sep-21
MUFTAU (YUSUF ABOI ROAD)	11/0.415	300	Standardisation	11KV Ahmadu Bello Way	1	Sep-21
NAGWAMATSE 1	11/0.415	300	Standardisation	11KV Ahmadu Bello Way	1	Sep-21
Durba Junction	11/0.415	300	Standardisation	11KV LUGGARD HALL	1	Sep-21
Galadima Road	11/0.415	500	Standardisation	11KV LUGGARD HALL	1	Sep-21
Hamdola Public	11/0.415	300	Standardisation	11KV LUGGARD HALL	1	Sep-21
Kanta Road	11/0.415	300	Standardisation	11KV LUGGARD HALL	1	Sep-21
Kashim Ibrahim Road	11/0.415	300	Standardisation	11KV LUGGARD HALL	1	Sep-21
Kufena Road 1	11/0.415	500	Standardisation	11KV LUGGARD HALL	1	Sep-21
Kufena Road 2	11/0.415	500	Standardisation	11KV LUGGARD HALL	1	Sep-21
State Secretariat 1	11/0.415	300	Standardisation	11KV LUGGARD HALL	1	Sep-21
Suleiman Crescent	11/0.415	500	Standardisation	11KV LUGGARD HALL	1	Sep-21
Swimming Pool	11/0.415	300	Standardisation	11KV LUGGARD HALL	1	Sep-21
TAFAWA BALEWA STEPHEN SHEKARI	11/0.415	300	Standardisation	11KV LUGGARD HALL	1	Sep-21
EGYPTIAN CONSULATE	11/0.415	300	Standardisation	11KV LUGGARD HALL	1	Sep-21
Iso Korfa/Gwadobe	11/0.415	500	Standardisation	11KV DAWAKI	1	Sep-21
Waziri Maccido	11/0.415	500	Standardisation	11KV DAWAKI	1	Sep-21
Altahiru Rabah	11/0.415	300	Standardisation	11KV DAWAKI	1	Sep-21
Bissau Street	11/0.415	500	Standardisation	11KV DAWAKI	1	Sep-21
Corakry	11/0.415	500	Standardisation	11KV DAWAKI	1	Sep-21
Gwani Muklar road	11/0.415	300	Standardisation	11KV DAWAKI	1	Sep-21
Gwanja road	11/0.415	300	Standardisation	11KV DAWAKI	1	Sep-21
Hamada Carpet	11/0.415	300	Standardisation	11KV DAWAKI	1	Sep-21
Ishaku close	11/0.415	500	Standardisation	11KV DAWAKI	1	Sep-21
Ishaku/Ogbadu road	11/0.415	500	Standardisation	11KV DAWAKI	1	Sep-21
Kamsalem road	11/0.415	500	Standardisation	11KV DAWAKI	1	Sep-21
Lata Tambai road	11/0.415	500	Standardisation	11KV DAWAKI	1	Sep-21
Police Station Malali	11/0.415	500	Standardisation	11KV DAWAKI	1	Sep-21



RABAH CLOSE	11/0.415	300	Standardisation	11KV DAWAKI	1	Sep-21
Rock Road	11/0.415	500	Standardisation	11KV DAWAKI	1	Sep-21
Sarkin Birnin Gwari	11/0.415	500	Standardisation	11KV DAWAKI	1	Sep-21
Technical School	11/0.415	300	Standardisation	11KV DAWAKI	1	Sep-21
Yano Lodge	11/0.415	300	Standardisation	11KV DAWAKI	1	Sep-21
FTC	11/0.415	300	Standardisation	11KV DAWAKI	1	Sep-21
ALTHAJI GARBA/AHMED DAN TANKO	11/0.415	500	Standardisation	11KV DAWAKI	1	Sep-21
OGBADU/UMARU GWANDU	11/0.415	300	Standardisation	11KV DAWAKI	1	Sep-21
Katuru/wurno road	11/0.415	500	Standardisation	11KV DAWAKI	1	Sep-21
Aisha International School	11/0.415	300	Standardisation	11KV DAWAKI	1	Sep-21
Lamido	11/0.415	300	Standardisation	11KV NACB	1	Sep-21
NACB Quarters	11/0.415	300	Standardisation	11KV NACB	1	Sep-21
NITR Public	11/0.415	300	Standardisation	11KV NACB	1	Sep-21
Queen Amino	11/0.415	300	Standardisation	11KV NACB	1	Sep-21
NITR Quarters	11/0.415	300	Standardisation	11KV NACB	1	Sep-21
BamangaTukur	11/0.415	300	Standardisation	11KV NACB	1	Sep-21
Dan Buram	11/0.415	300	Standardisation	11KV NACB	1	Sep-21
Eisu Road	11/0.415	500	Standardisation	11KV NACB	1	Sep-21
Gwadabe Road	11/0.415	500	Standardisation	11KV NACB	1	Sep-21
Ibrahim Zaki	11/0.415	300	Standardisation	11KV NACB	1	Sep-21
Kabir Road	11/0.415	300	Standardisation	11KV NACB	1	Sep-21
Kinshasa Road	11/0.415	300	Standardisation	11KV NACB	1	Sep-21
land Mark Shopping Complex	11/0.415	300	Standardisation	11KV NACB	1	Sep-21
Lapai Road	11/0.415	500	Standardisation	11KV NACB	1	Sep-21
Mutallab	11/0.415	300	Standardisation	11KV NACB	1	Sep-21
Song Road	11/0.415	300	Standardisation	11KV NACB	1	Sep-21
Yahaya Road	11/0.415	300	Standardisation	11KV NACB	1	Sep-21
Zanna Dujuma	11/0.415	300	Standardisation	11KV NACB	1	Sep-21
KWATO ROAD	11/0.415	300	Standardisation	11KV NACB	1	Sep-21
NITR LAYOUT 1	11/0.415	500	Standardisation	11KV NACB	1	Sep-21
NITR LAYOUT 2	11/0.415	300	Standardisation	11KV NACB	1	Sep-21
Alhaji Shehu Ahmed	11/0.415	300	Standardisation	11KV NACB	1	Sep-21

POLY QUARTERS	11/0.415	300	Standardisation	11KV NACB	1	Sep-21
ETSU/KINSHASA	11/0.415	300	Standardisation	11KV NACB	1	Sep-21
Diklo Road	11/0.415	300	Standardisation	11KV NACB	1	Sep-21
Diklo Road/Shehulaminu	11/0.415	300	Standardisation	11KV NACB	1	Sep-21
Imam Close	11/0.415	300	Standardisation	11KV NACB	1	Sep-21
NEPA Close	11/0.415	300	Standardisation	11KV NACB	1	Sep-21
Bissau	11/0.415	500	Standardisation	11KV Unguwan Rimi	1	Sep-21
Durba Camp	11/0.415	300	Standardisation	11KV Unguwan Rimi	1	Sep-21
Monrovia	11/0.415	300	Standardisation	11KV Unguwan Rimi	1	Sep-21
NTA Station	11/0.415	300	Standardisation	11KV Unguwan Rimi	1	Sep-21
Charles Bonet	11/0.415	300	Standardisation	11KV Unguwan Rimi	1	Sep-21
Rimi/Queen Amlina	11/0.415	300	Standardisation	11KV Unguwan Rimi	1	Sep-21
Sewage	11/0.415	300	Standardisation	11KV Unguwan Rimi	1	Sep-21
Shehulaminu/Accro	11/0.415	300	Standardisation	11KV Unguwan Rimi	1	Sep-21
Accro Road	11/0.415	500	Standardisation	11KV Unguwan Rimi	1	Sep-21
Bamako 1	11/0.415	500	Standardisation	11KV Unguwan Rimi	1	Sep-21
Bamako 2	11/0.415	500	Standardisation	11KV Unguwan Rimi	1	Sep-21
Bus - Stop 1	11/0.415	500	Standardisation	11KV Unguwan Rimi	1	Sep-21
Bus - Stop 2	11/0.415	500	Standardisation	11KV Unguwan Rimi	1	Nov-21
Ishaku Gwamna	11/0.415	500	Standardisation	11KV Unguwan Rimi	1	Sep-21
Jo' Abdulkadir/Rimi Drive	11/0.415	500	Standardisation	11KV Unguwan Rimi	1	Sep-21
Kubako	11/0.415	500	Standardisation	11KV Unguwan Rimi	1	Sep-21
Emir Road/Primary	11/0.415	300	Standardisation	11KV Unguwan Rimi	1	Sep-21
Jo' Abdulkadir Close	11/0.415	300	Standardisation	11KV Unguwan Rimi	1	Sep-21
SULEIMAN BARAU	11/0.415	300	Standardisation	11KV Unguwan Rimi	1	Sep-21
SABON GIDA	11/0.415	300	Standardisation	11KV Unguwan Rimi	1	Sep-21
DAN HONO	11/0.415	500	Standardisation	11KV Unguwan Rimi	1	Sep-21
KADAGE	11/0.415	500	Standardisation	11KV Unguwan Rimi	1	Sep-21
DAN BUSHIYA	11/0.415	300	Standardisation	11KV Unguwan Rimi	1	Sep-21
MORTGAGE 1	11/0.415	500	Standardisation	11KV Unguwan Rimi	1	Sep-21
MORTGAGE 2	11/0.415	500	Standardisation	11KV Unguwan Rimi	1	Sep-21
WATER BOARD U/RIMI RELIEF	11/0.415	300	Standardisation	11KV Unguwan Rimi	1	Sep-21
DAN BUSHIYA 1	11/0.415	300	Standardisation	11KV Unguwan Rimi	1	Sep-21



KYAUTA VILLAGE	11/0.415	500	Standardisation	11KV Unguwan Rimi	1	Sep-21
LINGUWAR MA'AJI	11/0.415	300	Standardisation	11KV Unguwan Rimi	1	Sep-21
CABS (BIMA ROAD)	11/0.415	300	Standardisation	11KV Teaching Hospital DKA	1	Sep-21
Camp Road	11/0.415	500	Standardisation	11KV Teaching Hospital DKA	1	Sep-21
Custom 1	11/0.415	500	Standardisation	11KV Teaching Hospital DKA	1	Sep-21
Custom 2	11/0.415	300	Standardisation	11KV Teaching Hospital DKA	1	Sep-21
Degel II 1	11/0.415	500	Standardisation	11KV Teaching Hospital DKA	1	Sep-21
Degel II 2	11/0.415	500	Standardisation	11KV Teaching Hospital DKA	1	Sep-21
EDI	11/0.415	300	Standardisation	11KV Teaching Hospital DKA	1	Sep-21
Link Road	11/0.415	300	Standardisation	11KV Teaching Hospital DKA	1	Sep-21
Maryam	11/0.415	300	Standardisation	11KV Teaching Hospital DKA	1	Sep-21
Old MTD	11/0.415	500	Standardisation	11KV Teaching Hospital DKA	1	Sep-21
Pole Road	11/0.415	300	Standardisation	11KV Teaching Hospital DKA	1	Sep-21
Prof. Abubakar Sambo	11/0.415	300	Standardisation	11KV Teaching Hospital DKA	1	Sep-21
Ras Raj	11/0.415	300	Standardisation	11KV Teaching Hospital DKA	1	Sep-21
Sarki Ilorin	11/0.415	300	Standardisation	11KV Teaching Hospital DKA	1	Sep-21
Shooting Range I	11/0.415	500	Standardisation	11KV Teaching Hospital DKA	1	Sep-21
Shooting Range II	11/0.415	500	Standardisation	11KV Teaching Hospital DKA	1	Sep-21
Kabala/Geborau	11/0.415	300	Standardisation	11KV Teaching Hospital DKA	1	Sep-21
HARUNA D	11/0.415	300	Standardisation	11KV Teaching Hospital DKA	1	Sep-21
POICE HOTS	11/0.415	300	Standardisation	11KV Teaching Hospital DKA	1	Sep-21
BLUE VELVET	11/0.415	500	Standardisation	11KV Teaching Hospital DKA	1	Sep-21
MD ABUBAKAR ESTATE, BABBAN SAURA	11/0.415	500	Standardisation	11KV Teaching Hospital DKA	1	Sep-21
BABBAN SAURA	11/0.415	300	Standardisation	11KV Teaching Hospital DKA	1	Sep-21
LIAMAN CROMA	11/0.415	500	Standardisation	11KV Teaching Hospital DKA	1	Sep-21
BABAN SAURA 3	11/0.415	300	Standardisation	11KV Teaching Hospital DKA	1	Sep-21
Bola Mile 2	11/0.415	500	Standardisation	11KV Constitution Road	1	Sep-21
Dahiru	11/0.415	500	Standardisation	11KV Constitution Road	1	Sep-21
Immigration	11/0.415	500	Standardisation	11KV Constitution Road	1	Sep-21
Kwararrafa 1	11/0.415	500	Standardisation	11KV Constitution Road	1	Sep-21
Kwararrafa 2	11/0.415	300	Standardisation	11KV Constitution Road	1	Sep-21
Luchia	11/0.415	500	Standardisation	11KV Constitution Road	1	Sep-21

Naddabo	11/0.415	500	Standardisation	11KV Constitution Road	1	Sep-21
Police College Public	11/0.415	500	Standardisation	11KV Constitution Road	1	Sep-21
Sam Nwosu	11/0.415	300	Standardisation	11KV Constitution Road	1	Sep-21
Seo Breeze	11/0.415	300	Standardisation	11KV Constitution Road	1	Sep-21
Alba Public	11/0.415	500	Standardisation	11KV Constitution Road	1	Sep-21
Arochukuwu	11/0.415	500	Standardisation	11KV Constitution Road	1	Sep-21
Borno Road	11/0.415	500	Standardisation	11KV Constitution Road	1	Sep-21
Daily Times	11/0.415	500	Standardisation	11KV Constitution Road	1	Sep-21
Daura Road	11/0.415	300	Standardisation	11KV Constitution Road	1	Sep-21
Gwarri/Miri	11/0.415	300	Standardisation	11KV Constitution Road	1	Sep-21
Jamaa Road	11/0.415	500	Standardisation	11KV Constitution Road	1	Sep-21
Keffi	11/0.415	300	Standardisation	11KV Constitution Road	1	Sep-21
Bonny	11/0.415	500	Standardisation	11KV Constitution Road	1	Sep-21
ABUBAKAR KIGO	11/0.415	300	Standardisation	11KV Constitution Road	1	Sep-21
Maiduguri Road	11/0.415	500	Standardisation	11KV Constitution Road	1	Sep-21
Timber Shed by Power Station	11/0.415	300	Standardisation	11KV Constitution Road	1	Sep-21
Aboki	11/0.415	500	Standardisation	11KV GRA KBI	1	Sep-21
Aboki Relieve	11/0.415	500	Standardisation	11KV GRA KBI	1	Sep-21
Almu Yari Farm	11/0.415	300	Standardisation	11KV GRA KBI	1	Sep-21
Alu Zaki	11/0.415	300	Standardisation	11KV GRA KBI	1	Sep-21
Block of School of Nurse	11/0.415	500	Standardisation	11KV GRA KBI	1	Sep-21
Block of School of Nurse relieve	11/0.415	500	Standardisation	11KV GRA KBI	1	Sep-21
Basoura	11/0.415	500	Standardisation	11KV GRA KBI	1	Sep-21
Basoura Relieve	11/0.415	300	Standardisation	11KV GRA KBI	1	Sep-21
Dan Alho Blocks	11/0.415	300	Standardisation	11KV GRA KBI	1	Sep-21
DSTV	11/0.415	300	Standardisation	11KV GRA KBI	1	Sep-21
Filin Moriyu	11/0.415	300	Standardisation	11KV GRA KBI	1	Sep-21
Filin Moriyu 2	11/0.415	300	Standardisation	11KV GRA KBI	1	Sep-21
Gesse Phase 1	11/0.415	500	Standardisation	11KV GRA KBI	1	Sep-21
Gesse Phase 2	11/0.415	500	Standardisation	11KV GRA KBI	1	Sep-21
Gesse Primary	11/0.415	500	Standardisation	11KV GRA KBI	1	Sep-21
Gesse Primary Relieve	11/0.415	500	Standardisation	11KV GRA KBI	1	Sep-21
GM	11/0.415	500	Standardisation	11KV GRA KBI	1	Sep-21

GESSE GATE	11/0.415	500	Standardisation	11KV GRA KBI	1	Sep-21
PROPOSE MUTTAKA	11/0.415	300	Standardisation	11KV GRA KBI	1	Sep-21
PROPOSE FILIN MARIYA	11/0.415	300	Standardisation	11KV GRA KBI	1	Sep-21
Alhaji Kabiru Kamba	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Aliero Estate NO. 1 Relief 1	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Aliero Estate NO. 1 Relief 2	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Aliero Estate NO. 1 Relief 3	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Aliero Estate NO. 2 Relief 1	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Aliero Estate NO. 2 Relief 2	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Aliero Estate NO. 2 Relief 3	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Aliero Estate NO. 2 Relief 4	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Aliero Estate NO. 2 Relief 5	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Aliero Quarter 1 (sakaba pure water)	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
Aliero Quarter 2 (main gate)	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
Aliero Quarter 3 (police station)	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
Amah I Relief 1	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Amah I Relief 2	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Amah II Relief 1	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Amah II Relief 3	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Amah II Relief 4	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Amah 1	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
Amah 2 Borehole	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
Amah 3 Garden Road	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
Argungu Roud>About 1	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
Argungu Roud>About 2 (Bello suru)	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
Argungu Roud>About Relief 1	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Argungu Roud>About Relief 2	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Argungu Roud>About Relief 3	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Block of Presidential Lodge 1	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
Block of Presidential Lodge 2	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
Bello Kusu Relief 1	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Bello Kusu Relief 2	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21



BM Sub-Station	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
BM Sub-station Relief 1	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
D.G Quarters	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
Dangiwa	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
Fadama 1	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
Fadama 2	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
Federal Radio Corporation	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
First Lady	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Gazo Village	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Gwadangaji 1	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
Gwadangaji 2	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
Gwadangaji 3	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Gwadangaji 4	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
Gwadangaji NO.1 Relief 1	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Gwadangaji NO.1V Relief 2	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Gwadangaji NO.1V Relief 1	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Gwadangaji Quarters 1	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
Gwadangaji Quarters New Layout	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
Habib Engineering	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
Haruna Rashheed	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
Haruna Shoyau	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
Immigration	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Immigration Relief 1	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Innuwa Petrol Station	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Kawara	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Kusu Bello	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
Larix 1	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
Larix 1 Relief 1	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Larix 2	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
Larix 2 Relief 1	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Larix 2 Relief 2	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
Mogaji Relief 1	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Minister	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21

Police Station Relief	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
CJ	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
OFFICE	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
NIPP SHARIA COURT	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
NIPP SAMBAWA	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
DR AMINA LAYOUT 1	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
DR AMINA LAYOUT 2	11/0.415	500	Standardisation	11KV GWADANGWAI	1	Sep-21
MECHANICAL WORKSHOP	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
STREET LIGHT OPP ASAJJA	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
STREET LIGHT OPP AREA D	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
WANGARAWA GAS STATION	11/0.415	300	Standardisation	11KV GWADANGWAI	1	Sep-21
Abi 1	11/0.415	500	Standardisation	11KV BULASA	1	Sep-21
Abi 2	11/0.415	500	Standardisation	11KV BULASA	1	Sep-21
Ali Bogudo Junction	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
Ali Bogudo 1	11/0.415	500	Standardisation	11KV BULASA	1	Sep-21
Ali Bogudo 2	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
Ali Bogudo 3	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
Aliero Yard	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
AP2 1 Sub-Station	11/0.415	500	Standardisation	11KV BULASA	1	Sep-21
AP2 2 Sub-Station	11/0.415	500	Standardisation	11KV BULASA	1	Sep-21
Badarhya Police Station	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
Buba Mai Nama 2	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
Capture House	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
Capture 2	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
Fab-International	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
Girls Hostel 1	11/0.415	500	Standardisation	11KV BULASA	1	Sep-21
Girls Hostel 2	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
Jogwoddaji	11/0.415	500	Standardisation	11KV BULASA	1	Sep-21
Jodu Village	11/0.415	500	Standardisation	11KV BULASA	1	Sep-21
Kelbi Store	11/0.415	500	Standardisation	11KV BULASA	1	Sep-21
Kola 1	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
Kola 2	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
Kola Road 1	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21



Kala Road Relive	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
LVS Sub-Station	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
Maivaka Sub-Station	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
Mapol 1	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
Mapol 2	11/0.415	500	Standardisation	11KV BULASA	1	Sep-21
Nasiru Custom	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
Near Buba Mai Nama Sub-Station	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
Near Mr. Ferni House Sub-Station	11/0.415	500	Standardisation	11KV BULASA	1	Sep-21
Old Sefari Sub-Station	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
Perm. Sec. Sub-Station	11/0.415	500	Standardisation	11KV BULASA	1	Sep-21
Primary Board	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
Prison Yard Sub-Station	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
R. Corn Jega 2	11/0.415	500	Standardisation	11KV BULASA	1	Sep-21
R. Corn Jega Road	11/0.415	500	Standardisation	11KV BULASA	1	Sep-21
S/Goru Sub-Station	11/0.415	500	Standardisation	11KV BULASA	1	Sep-21
Tanki 2	11/0.415	500	Standardisation	11KV BULASA	1	Sep-21
Tanki Sub-Station	11/0.415	500	Standardisation	11KV BULASA	1	Sep-21
Unguwar Donbo Sub-Station	11/0.415	500	Standardisation	11KV BULASA	1	Sep-21
Wurimdeki Sub-Station	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
Zakiru Sub-Station	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
Zuguru Village	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
RUGGA	11/0.415	500	Standardisation	11KV BULASA	1	Sep-21
Dan Atto	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
BACK OF NEW PRISON	11/0.415	500	Standardisation	11KV BULASA	1	Sep-21
BALA RANO	11/0.415	500	Standardisation	11KV BULASA	1	Sep-21
NIPP ATAB GLOBAL	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
NIPP BULASA OFFICE	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
NIPP JAGWADEI	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
NIPP BELLO SOKOTO	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
NIPP MALAM KIRLIWA	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
KOLA 3	11/0.415	300	Standardisation	11KV BULASA	1	Sep-21
ZAZZALI ROAD	11/0.415	500	Standardisation	11KV GWARI AVENUE	1	Sep-21
PRISON STAFF COLLEGE	11/0.415	500	Standardisation	11KV GWARI AVENUE	1	Sep-21

SHAGARI 2	11/0.415	300	Standardisation	11KV GWARI AVENUE	1	Sep-21
SHAGARI 3	11/0.415	300	Standardisation	11KV GWARI AVENUE	1	Sep-21
ABYOLO HOTEL	11/0.415	300	Standardisation	11KV GWARI AVENUE	1	Sep-21
DAMAGUN	11/0.415	300	Standardisation	11KV GWARI AVENUE	1	Sep-21
EDE	11/0.415	300	Standardisation	11KV GWARI AVENUE	1	Sep-21
GWARI AVENUE	11/0.415	300	Standardisation	11KV GWARI AVENUE	1	Sep-21
KUJAMA	11/0.415	500	Standardisation	11KV GWARI AVENUE	1	Sep-21
MAI MASA	11/0.415	300	Standardisation	11KV GWARI AVENUE	1	Sep-21
SHAGARI 1	11/0.415	300	Standardisation	11KV GWARI AVENUE	1	Sep-21
TANKO TETE	11/0.415	300	Standardisation	11KV GWARI AVENUE	1	Sep-21
TELEVISION GARAGE	11/0.415	300	Standardisation	11KV GWARI AVENUE	1	Sep-21
AUDU JAGWAN	33/0.415	300	Standardisation	33KV GONIN GORA	1	Sep-21
BUWAYA 1	33/0.415	500	Standardisation	33KV GONIN GORA	1	Sep-21
BUWAYA 2	33/0.415	500	Standardisation	33KV GONIN GORA	1	Sep-21
DOKA VILLAGE	33/0.415	300	Standardisation	33KV GONIN GORA	1	Sep-21
DUTSE	33/0.415	300	Standardisation	33KV GONIN GORA	1	Sep-21
GADDAN MALLAM MAMMAN	33/0.415	300	Standardisation	33KV GONIN GORA	1	Sep-21
GOVERNMENT LAND 1	33/0.415	300	Standardisation	33KV GONIN GORA	1	Sep-21
GWAGWADA 1	33/0.415	300	Standardisation	33KV GONIN GORA	1	Sep-21
GWAGWADA 2	33/0.415	300	Standardisation	33KV GONIN GORA	1	Sep-21
JOY INTERNATIONAL SCHOOL (TOIL GATE)	33/0.415	300	Standardisation	33KV GONIN GORA	1	Sep-21
JUBILEE	33/0.415	500	Standardisation	33KV GONIN GORA	1	Sep-21
KAKAU 1	33/0.415	500	Standardisation	33KV GONIN GORA	1	Sep-21
KAKAU 2	33/0.415	300	Standardisation	33KV GONIN GORA	1	Sep-21
KASARAMI 1	33/0.415	300	Standardisation	33KV GONIN GORA	1	Sep-21
KASARAMI 2	33/0.415	300	Standardisation	33KV GONIN GORA	1	Sep-21
KONAN - BATURE	33/0.415	300	Standardisation	33KV GONIN GORA	1	Sep-21
LAMIGYI 1	33/0.415	300	Standardisation	33KV GONIN GORA	1	Sep-21
LAMIGYI 2	33/0.415	300	Standardisation	33KV GONIN GORA	1	Sep-21
NASARAWA DOKA	33/0.415	300	Standardisation	33KV GONIN GORA	1	Sep-21
RILANA	33/0.415	300	Standardisation	33KV GONIN GORA	1	Sep-21
SABON GARI 1	33/0.415	500	Standardisation	33KV GONIN GORA	1	Sep-21



SABON GARI 2	33/0.415	500	Standardisation	33KV GONJIN GORA	1	Sep-21
SABON GAYAN 1	33/0.415	300	Standardisation	33KV GONJIN GORA	1	Sep-21
SABON GAYAN 2	33/0.415	300	Standardisation	33KV GONJIN GORA	1	Sep-21
SABON GAYAN 3	33/0.415	300	Standardisation	33KV GONJIN GORA	1	Sep-21
SABON GIDA TOLLGATE	33/0.415	300	Standardisation	33KV GONJIN GORA	1	Sep-21
SABON MARO	33/0.415	300	Standardisation	33KV GONJIN GORA	1	Sep-21
UNGUWAR MISSION GWAZUNU	33/0.415	300	Standardisation	33KV GONJIN GORA	1	Sep-21
UNGUWAR BARDE	33/0.415	300	Standardisation	33KV GONJIN GORA	1	Sep-21
UNGUWAR BIE 1	33/0.415	500	Standardisation	33KV GONJIN GORA	1	Sep-21
UNGUWAR BIE 2	33/0.415	500	Standardisation	33KV GONJIN GORA	1	Sep-21
UNGUWAR DOMA	33/0.415	500	Standardisation	33KV GONJIN GORA	1	Sep-21
UNGUWAR ZWAHUI	33/0.415	300	Standardisation	33KV GONJIN GORA	1	Sep-21
SABON GARI 3	33/0.415	500	Standardisation	33KV GONJIN GORA	1	Sep-21
AGYAITA VILLAGE	33/0.415	300	Standardisation	33KV GONJIN GORA	1	Sep-21
JULI 1	33/0.415	300	Standardisation	33KV GONJIN GORA	1	Sep-21
JULI 2	33/0.415	300	Standardisation	33KV GONJIN GORA	1	Sep-21
1ST CONER ROAD	11/0.415	500	Standardisation	11KV NASSARAWA MKR	1	Sep-21
2ND CONER ROAD	11/0.415	500	Standardisation	11KV NASSARAWA MKR	1	Sep-21
3RD CONER ROAD	11/0.415	500	Standardisation	11KV NASSARAWA MKR	1	Sep-21
ABULUCO	11/0.415	300	Standardisation	11KV NASSARAWA MKR	1	Sep-21
AKWANGA 1	11/0.415	500	Standardisation	11KV NASSARAWA MKR	1	Sep-21
AKWANGA 2	11/0.415	500	Standardisation	11KV NASSARAWA MKR	1	Sep-21
BIBLE SOCIETY	11/0.415	500	Standardisation	11KV NASSARAWA MKR	1	Sep-21
COROLLA	11/0.415	300	Standardisation	11KV NASSARAWA MKR	1	Sep-21
CUBIC	11/0.415	300	Standardisation	11KV NASSARAWA MKR	1	Sep-21
DOWN QUARTER 1	11/0.415	500	Standardisation	11KV NASSARAWA MKR	1	Sep-21
DOWN QUARTER 2	11/0.415	500	Standardisation	11KV NASSARAWA MKR	1	Sep-21
DOWN QUARTER 3	11/0.415	300	Standardisation	11KV NASSARAWA MKR	1	Sep-21
FIRST BANK 1	11/0.415	500	Standardisation	11KV NASSARAWA MKR	1	Sep-21
GASHASH ROAD	11/0.415	300	Standardisation	11KV NASSARAWA MKR	1	Sep-21
GEOLOGICAL SURVEY	11/0.415	300	Standardisation	11KV NASSARAWA MKR	1	Sep-21
KEFI ROAD	11/0.415	300	Standardisation	11KV NASSARAWA MKR	1	Sep-21
RAILWAY MARKET 1	11/0.415	500	Standardisation	11KV NASSARAWA MKR	1	Sep-21

RAILWAY MARKET 2	11/0.415	300	Standardisation	11KV NASSARAWA MKR	1	Sep-21
UNGUJWAR JOHN	11/0.415	500	Standardisation	11KV NASSARAWA MKR	1	Sep-21
WATER BOARD	11/0.415	300	Standardisation	11KV NASSARAWA MKR	1	Sep-21
DABO 1	11/0.415	500	Standardisation	11KV NASSARAWA MKR	1	Sep-21
DABO 2	11/0.415	300	Standardisation	11KV NASSARAWA MKR	1	Sep-21
KOTANGORA ESTATE	33/0.415	300	Standardisation	33KV AREWA	1	Sep-21
AHMED BULASA RD. 13	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
AHMED BULASA RD. 14	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
AHMED BULASA RD. 15	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
AHMED BULASA RD. 16	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
AHMED BURUKU	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
AMINA NAMADI	11/0.415	500	Standardisation	11KV YANTUKWANE	1	Sep-21
AT:TATBIO NO10	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
AT:TATBIO NO11	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
AT:TATBIO RD. NO12	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
AT:TATBIO RD. NO9	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
BARRISTER	11/0.415	500	Standardisation	11KV YANTUKWANE	1	Sep-21
DANDALI	11/0.415	500	Standardisation	11KV YANTUKWANE	1	Sep-21
GOMBE RD. NO. 7	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
GOMBE RD. NO. 8	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
GRA 1	11/0.415	500	Standardisation	11KV YANTUKWANE	1	Sep-21
IRAO	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
IYA ABDULLAHI AVE. 20	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
KVAI 1	11/0.415	500	Standardisation	11KV YANTUKWANE	1	Sep-21
MUSABAKA	11/0.415	500	Standardisation	11KV YANTUKWANE	1	Sep-21
PRIMARY	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
SAMBO RD. NO.17	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
SAMBO RD. NO.18	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
SAMBO RD. NO.19	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
SAYAYA	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
SOBA RD. NO.6	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
SOBA ROAD NO. 1	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
SOBA ROAD NO. 2	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21



SOBA ROAD NO. 3	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
SOBA ROAD NO. 4	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
SOBA ROAD NO. 5	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
WAZIRI KAURI	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
YANTUKWANE 1	11/0.415	500	Standardisation	11KV YANTUKWANE	1	Sep-21
YANTUKWANE 2	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
YANTUKWANE 3	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
ZAMFARA 1	11/0.415	500	Standardisation	11KV YANTUKWANE	1	Sep-21
ZAMFARA 2	11/0.415	500	Standardisation	11KV YANTUKWANE	1	Sep-21
ZANGO 1	11/0.415	500	Standardisation	11KV YANTUKWANE	1	Sep-21
ZANGO 2	11/0.415	500	Standardisation	11KV YANTUKWANE	1	Sep-21
ZANGO 3	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
ZANGO 4	11/0.415	500	Standardisation	11KV YANTUKWANE	1	Sep-21
ZANGO 5	11/0.415	500	Standardisation	11KV YANTUKWANE	1	Sep-21
JARMA	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
Danjuma Toro 1	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
Danjuma Toro 2	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
DANIADI UMAR	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
ZANGO 6	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
DANIUMA TORO 3	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
DANIUMA TORO 4	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
YARIMA SAAD	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
AHMAD BURUKU/ALGARGAWI	11/0.415	500	Standardisation	11KV YANTUKWANE	1	Sep-21
YANTUKWANE/ASIBITI	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
AMINA NAMADI SAMBO 2	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
HAYIN DANMANI 1	33/0.415	500	Standardisation	33KV KINKINAU	1	Sep-21
HAYIN DANMANI 2	33/0.415	500	Standardisation	33KV KINKINAU	1	Sep-21
HAYIN DANMANI 3, RIMAYE	33/0.415	500	Standardisation	33KV KINKINAU	1	Sep-21
HAYIN DANMANI 4	33/0.415	500	Standardisation	33KV KINKINAU	1	Sep-21
ALIYU ABBAS	33/0.415	500	Standardisation	33KV KINKINAU	1	Sep-21
RAHMA ROAD	33/0.415	300	Standardisation	33KV KINKINAU	1	Sep-21
OFF SARKIN DILLALAI 2	33/0.415	300	Standardisation	33KV KINKINAU	1	Sep-21
BOKON DALLI 1	33/0.415	500	Standardisation	33KV KINKINAU	1	Sep-21

KANO ROAD, HAYIN DANMANI	33/0.415	500	Standardisation	33KV KINKINAU	1	Sep-21
BOKON DAI 2	33/0.415	500	Standardisation	33KV KINKINAU	1	Sep-21
BOKON DAI 3	33/0.415	500	Standardisation	33KV KINKINAU	1	Sep-21
DANMANI 5	33/0.415	500	Standardisation	33KV KINKINAU	1	Sep-21
ADAMAWA/ABEKUTA STR	11/0.415	500	Standardisation	11KV LEVENTIS	1	Sep-21
ADAMAWA/ABEKUTA STR	11/0.415	300	Standardisation	11KV LEVENTIS	1	Sep-21
BENUÉ/BENIN STREET	11/0.415	500	Standardisation	11KV LEVENTIS	1	Sep-21
BIDA/ABEKUTA STREET	11/0.415	300	Standardisation	11KV LEVENTIS	1	Sep-21
CLUB 69	11/0.415	500	Standardisation	11KV LEVENTIS	1	Sep-21
DAN MUSA/ORIAPAKTA	11/0.415	300	Standardisation	11KV LEVENTIS	1	Sep-21
JOS/ABEKUTA STREET	11/0.415	500	Standardisation	11KV LEVENTIS	1	Sep-21
JOS/AHMADU BELLO WAY	11/0.415	500	Standardisation	11KV LEVENTIS	1	Sep-21
KANO/BAYAJIDA STREET	11/0.415	500	Standardisation	11KV LEVENTIS	1	Sep-21
KANO/BININ STREET	11/0.415	300	Standardisation	11KV LEVENTIS	1	Sep-21
KASTINA/BAYIJIDA STREET	11/0.415	500	Standardisation	11KV LEVENTIS	1	Sep-21
KATSINA/ABEKUTA	11/0.415	300	Standardisation	11KV LEVENTIS	1	Sep-21
N B C	11/0.415	500	Standardisation	11KV LEVENTIS	1	Sep-21
OGORI ROAD	11/0.415	500	Standardisation	11KV LEVENTIS	1	Sep-21
WUSHISHI/DANMUSA	11/0.415	500	Standardisation	11KV LEVENTIS	1	Sep-21
YORUBA ROAD	11/0.415	500	Standardisation	11KV LEVENTIS	1	Sep-21
ZARIA ROAD/ABEKUTA STREET	11/0.415	300	Standardisation	11KV LEVENTIS	1	Sep-21
ARGUNGU ROAD	11/0.415	300	Standardisation	11KV LEVENTIS	1	Sep-21
TIM UNITY	11/0.415	500	Standardisation	11KV LEVENTIS	1	Sep-21
BAYAJIDA BY KANO ROAD	11/0.415	500	Standardisation	11KV LEVENTIS	1	Sep-21
ZARIA ROAD RELIEF	11/0.415	300	Standardisation	11KV LEVENTIS	1	Sep-21
ZARIA BY ABEOKUTA RELIEF	11/0.415	300	Standardisation	11KV LEVENTIS	1	Sep-21
BARAKA	11/0.415	300	Standardisation	11KV POLY ROAD	1	Sep-21
M&K	11/0.415	300	Standardisation	11KV POLY ROAD	1	Sep-21
AHMED BULASA RD. 13	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
AHMED BULASA RD. 14	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
AHMED BULASA RD. 15	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
AHMED BULASA RD. 16	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
AHMED BURUKU	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21



AMINA NAMADI	11/0.415	500	Standardisation	11KV YANTUKWANE	1	Sep-21
AI-TAIBIQ NO10	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
AI-TAIBIQ NO11	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
AI-TAIBIQ RD. NO12	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
AI-TAIBIQ RD. NO9	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
BARRISTER	11/0.415	500	Standardisation	11KV YANTUKWANE	1	Sep-21
DANDALI	11/0.415	500	Standardisation	11KV YANTUKWANE	1	Sep-21
GOMBE RD. NO. 7	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
GOMBE RD. NO. 8	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
GRA 1	11/0.415	500	Standardisation	11KV YANTUKWANE	1	Sep-21
IRAO	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
IYA ABDULLAHI AVE. 20	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
KWAI 1	11/0.415	500	Standardisation	11KV YANTUKWANE	1	Sep-21
MUSABAKA	11/0.415	500	Standardisation	11KV YANTUKWANE	1	Sep-21
PRIMARY	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
SAMBO RD. NO 17	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
SAMBO RD. NO 18	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
SAMBO RD. NO 19	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
SAYAYA	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
SOBA RD. NO 6	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
SOBA ROAD NO. 1	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
SOBA ROAD NO. 2	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
SOBA ROAD NO. 3	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
SOBA ROAD NO. 4	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
SOBA ROAD NO. 5	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
WAZIRI KAURU	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
YANTUKWANE 1	11/0.415	500	Standardisation	11KV YANTUKWANE	1	Sep-21
YANTUKWANE 2	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
YANTUKWANE 3	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
ZAMFARA 1	11/0.415	500	Standardisation	11KV YANTUKWANE	1	Sep-21
ZAMFARA 2	11/0.415	500	Standardisation	11KV YANTUKWANE	1	Sep-21
ZANGO 1	11/0.415	500	Standardisation	11KV YANTUKWANE	1	Sep-21
ZANGO 2	11/0.415	500	Standardisation	11KV YANTUKWANE	1	Sep-21

ZANGO 3	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
ZANGO 4	11/0.415	500	Standardisation	11KV YANTUKWANE	1	Sep-21
ZANGO 5	11/0.415	500	Standardisation	11KV YANTUKWANE	1	Sep-21
JARMA	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
Danjuma Toro 1	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
Danjuma Toro 2	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
DANIADI UMAR	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
ZANGO 6	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
DANIUMA TORO 3	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
DANIUMA TORO 4	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
YARIIMA SAAD	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
AHMAD BURUKU/ALGARGAWI	11/0.415	500	Standardisation	11KV YANTUKWANE	1	Sep-21
YANTUKWANE/ASIBITI	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
AMINA NAMADI SAMBO 2	11/0.415	300	Standardisation	11KV YANTUKWANE	1	Sep-21
HAYIN DANMANI 1	33/0.415	500	Standardisation	33KV KINKINAU	1	Sep-21
HAYIN DANMANI 2	33/0.415	500	Standardisation	33KV KINKINAU	1	Sep-21
HAYIN DANMANI 3, RIMAYE	33/0.415	500	Standardisation	33KV KINKINAU	1	Sep-21
HAYIN DANMANI 4	33/0.415	500	Standardisation	33KV KINKINAU	1	Sep-21
AUYU ABBAS	33/0.415	500	Standardisation	33KV KINKINAU	1	Sep-21
RAHMA ROAD	33/0.415	300	Standardisation	33KV KINKINAU	1	Sep-21
OFF SARKIN DILLALAI 2	33/0.415	300	Standardisation	33KV KINKINAU	1	Sep-21
BOKON DAI 1	33/0.415	500	Standardisation	33KV KINKINAU	1	Sep-21
KANO ROAD,HAYIN DANMANI	33/0.415	500	Standardisation	33KV KINKINAU	1	Sep-21
BOKON DAI 2	33/0.415	500	Standardisation	33KV KINKINAU	1	Sep-21
BOKON DAI 3	33/0.415	500	Standardisation	33KV KINKINAU	1	Sep-21
DANMANI 5	33/0.415	500	Standardisation	33KV KINKINAU	1	Sep-21
ADAMAWA/ABEKUTA STR	11/0.415	500	Standardisation	11KV EVENTS	1	Sep-21
ADAMAWA/ABEKUTA STR	11/0.415	300	Standardisation	11KV EVENTS	1	Sep-21
BENUUE/BENIN STREET	11/0.415	500	Standardisation	11KV EVENTS	1	Sep-21
BIDA/ABEKUTA STREET	11/0.415	300	Standardisation	11KV EVENTS	1	Sep-21
CLUB 69	11/0.415	500	Standardisation	11KV EVENTS	1	Sep-21
DAN MUSA/ORIAPAKTA	11/0.415	300	Standardisation	11KV EVENTS	1	Sep-21
JOS/ABEKUTA STREET	11/0.415	500	Standardisation	11KV EVENTS	1	Sep-21



JOS/AHMADU BELLO WAY	11/0.415	500	Standardisation	11KV LEVENTIS	1	Sep-21
KANO/BAVAJIDA STREET	11/0.415	500	Standardisation	11KV LEVENTIS	1	Sep-21
KANO/BININ STREET	11/0.415	300	Standardisation	11KV LEVENTIS	1	Sep-21
KASTINA/BAVJIDA STREET	11/0.415	500	Standardisation	11KV LEVENTIS	1	Sep-21
KATSINA/ABEKUTA	11/0.415	300	Standardisation	11KV LEVENTIS	1	Sep-21
N B C	11/0.415	500	Standardisation	11KV LEVENTIS	1	Sep-21
OGORI ROAD	11/0.415	500	Standardisation	11KV LEVENTIS	1	Sep-21
WUSHISHI/DANMUSA	11/0.415	500	Standardisation	11KV LEVENTIS	1	Sep-21
YORUBA ROAD	11/0.415	500	Standardisation	11KV LEVENTIS	1	Sep-21
ZARIA ROAD/ABEKUTA STREET	11/0.415	300	Standardisation	11KV LEVENTIS	1	Sep-21
ARGUNGU ROAD	11/0.415	300	Standardisation	11KV LEVENTIS	1	Sep-21
TIM UNITY	11/0.415	500	Standardisation	11KV LEVENTIS	1	Sep-21
BAVAJIDA BY KANO ROAD	11/0.415	500	Standardisation	11KV LEVENTIS	1	Sep-21
ZARIA ROAD RELIEF	11/0.415	300	Standardisation	11KV LEVENTIS	1	Sep-21
ZARIA BY ABEOKUTA RELIEF	11/0.415	300	Standardisation	11KV LEVENTIS	1	Sep-21
BARAKA	11/0.415	300	Standardisation	11KV POLY ROAD	1	Sep-21
M&K	11/0.415	300	Standardisation	11KV POLY ROAD	1	Sep-21
Tuntube Town	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
BAKIN TASHA TURETA	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
BISSILAM VILLAGE	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
BODAI 1	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
BODAI 2	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
DABAGIN ARDO	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
DORAWA VILLAGE	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
FURA GIRKE TURATE	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
GANTAMAU VILLAGE	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
GIDAN KARE	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
ILEIAR BISSILAM	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
KAFANIN ALA VILLAGE	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
KAMFANIN DIYA VILLAGE	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
KANWURI TURETA	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
LAMBAR TURETA	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
LAMBO NO. 1	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21

LAMBO NO. 2	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
LAMBO NO. 3	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
LOFA VILLAGE	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
RANDA VILLAGE TURETA	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
SABON GARIN TURETA	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
SABON HEGI TURETA	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
TSAFANADE VILLAGE	33/0.415	500	Standardisation	33KV POWER STATION	1	Sep-21
TSAKI VILLAGE	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
TSAMIYA VILLAGE	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
ZAMAU VILLAGE	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
ILELA GAJARA	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
DUMA VILLAGE	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
KANWURI SHUNI	33/0.415	500	Standardisation	33KV POWER STATION	1	Sep-21
BAKIN TASHA SHUNI	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
KWANDI VILLAGE	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
LUNGU VILLAGE	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
GAJARA VILLAGE	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
RUDU GERO	33/0.415	500	Standardisation	33KV POWER STATION	1	Sep-21
RUDU DIKKO	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
MAIYA VILLAGE	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
ALU QUARTERS TURETA	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
TSAMIYA P H C	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
PINNACLE HOTEL	33/0.415	500	Standardisation	33KV POWER STATION	1	Sep-21
MTN DABAGI	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
TURAWA VILLAGE	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
ALU QUARTERS	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
TSAMIYA VILLAGE 2	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
AMANAWA	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
MODAWA	33/0.415	300	Standardisation	33KV POWER STATION	1	Sep-21
GIDAN DADI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KATARAWA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
SAKAMARU	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
ADARAWA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21

AMBARURU	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
BACHAKA 1	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
BACHAKA 2	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
BAIDI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
BANGI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
BUNKARI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
CAIDAU	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
DADDALI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
DAMBAR KWANAWA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
DAN BOKA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
DAN KALA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
DANBEREMA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
DARNA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
FALANJE	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIDAN CHIWAKE	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIDAN MAIDEBE	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GARU	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIDAN AMAMATA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIDAN KATTA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIDAN YOROBA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIDAN MAI KAMBA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIDIMA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GONGONO	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GURDAM	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
HOLAI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
HUJIMA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
INNAME	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
JAMALE	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
JAMALE SABUWA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KADADIN BUDA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KAIGO	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KAIMALO	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KARFEN CHANA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21

KAREN SARKI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KIRI SALAMAWA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KUTUFARE	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KWANDAMO	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KYADAWA 1	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KYADAWA 2	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
MAIKULI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
MONGONO	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
MUNWADATA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
RAFIN DUMA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
UNGUWAR RUWA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
RUNJI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
RUWA WURI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
SAGERA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
SANTINNA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
SAURO	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
SILAME	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
SORO	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
T/MUWELA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
TUDUN KOSI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
TUNGAR BALLE	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
WALURU 2	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
WAZANGE	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
AMBARURA II	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
ASARA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
BAKIN GULBI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
BAKIN KASUWA KWARE	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
BALKORE	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
BANKANU	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
BOYEN KABAWA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
CHANCHA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
CHIMMOLA 1	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
CHIMMOLA 2	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21



COMPREHENSIVE KWARE	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
DAMBAR DIKKO	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
DAMO	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
DIMBISO	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
DUHUWA GUMSA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
DUNDAYE	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
FILASKO	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GANDE	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GAWON TOMO	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GEDAWA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIDAN ALKAU	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIDAN BUBU	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIDAN IDALTU	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIDAN KARMA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIDAN KAYA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIDAN SULE	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIDAN TUDU	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIDAN YARO	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIGANE 1	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIGANE 2	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GINIGA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIYAWA 1	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIYAWA 2	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GUMBURAWA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GUNFAR DAN GARA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GUNFAR GEBE	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
HUCHI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
HURA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
ILELA BARAYA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
JEMA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KADADIN MAL DABO	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KALABA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KALALAWA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21

KANEN TURU	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KANWURI KWARE	33/0.415	500	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KARAMBI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KOFAR YAMMA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KWAKWARAN ZAIN	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KWAKWALAWA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KWAMNA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KWARE 30 HOUSING	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KWARE JUMU'AT MOSQUE	33/0.415	500	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KWARE L.G.5	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
LAHODU	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
LAPSAMI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
LUKUWA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
MAKERA BABBA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
MAKERA KARAMA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
MAMMAN SUKA GARI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
MAMMAN SUKA GIDAN GEZA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
MAMMANDE	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
MARBAWA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
MASHIDI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
MTN BINJI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
MTN KWAKWARAN	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
MTN TANGAZA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
MUJIEA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
PSYCHIATRIC KWARE	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
RANGANDA 1	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
RANGANDA 2	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
RUMBUJE	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
RUNJIN YAMMA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
SABON BIRNI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
SABON GARIN BOYEKAI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
SALAME 1	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
SALAME 2	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21



SANGANDA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
SIRI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
TABANNI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
TAMBAGARKA 1	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
TAMBAGARKA 2	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
TAMBARANGA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
TANGWALE	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
TSALIBAWA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
TSOHON GARIN BOYE KAI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
TUDUN DOKI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
TUNGA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
TUNGAR KWANGI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
TUNGAR TUDU	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
TUNTSURUNGU	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
AIRTEL KWARE	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
WALURU 1	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
WULURE	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
YAKA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
YAR GADA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
YAR KANTA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
YAR LABE	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIDAN FATI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
ZORAMAWA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
YAR TUDU	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
RUNJI GAZO	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIDAN HAMIDU	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIDAN MALAMA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
MTEL UNIVERSITY	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
SHAMA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
DANJAWA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
UNIVERSITY STAFF QUARTERS	33/0.415	500	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
UDUS GIDAN PONTROTO	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIDAN RINI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21

GIDAN KARO	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
BAGAYAWA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIDAN SALA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
DOBA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
NASARAWA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
YAR ABBA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
BOYEN MACILI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
BADARON YAMMA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
MAKABARTA GIRABSHI	33/0.415	500	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
BADANO	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIDAN AYA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
SALAMI 3	33/0.415	500	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
MTN KWARE	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
MELI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
TSANGALAMDAM	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
DARNA SABON GARI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIDAN HAMMA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KIRI MAIKASUWA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIDAN SANDAGA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
BASANTA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GAIDAU	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
RUNJIN KALMALO	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIDAN KWANNI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GUNDUNGA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
AIRTEL GUNDUNGA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KALANIENI ASARAWA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KALANIENI DUTSE	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIDAN MALAM	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
DABBOWA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KABAWA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
TAUDI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
MARMARO	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KAYA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21



MALE	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GOKAI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
HANDA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
FADAN JEDO	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
DAFKALA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KOFAR KAMBE	33/0.415	500	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
30 HOUSING SILAME	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KARANGIYA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
MARAFI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
MARGAI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
MALE	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
ALHAZAWA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
KANDASAWA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GADAMBE	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
BETARE	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
RUMBUJI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
30 HOUSING GIDAN MADI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
MAIKAHO	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
MASALLACHI GWANGWANO	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
LABSANI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
30 HOUSING BALLE	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
30 HOUSING GWADABAWA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
TAKARAWA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
TUNGAR KWANGI 2	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
TABANI	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
NVSC CAMP	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
SABON GIDA	33/0.415	300	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
GIDAN ASSADA GROUP	33/0.415	500	Standardisation	33KV KWARE/UNIVERSITY	1	Sep-21
Dansodau 1	33/0.415	300	Standardisation	33KV MAGAMI	1	Sep-21
Dansodau 2	33/0.415	300	Standardisation	33KV MAGAMI	1	Sep-21
Dansodau 3	33/0.415	300	Standardisation	33KV MAGAMI	1	Sep-21
Gidan Anjo	33/0.415	300	Standardisation	33KV MAGAMI	1	Sep-21
Gidan Fokai	33/0.415	300	Standardisation	33KV MAGAMI	1	Sep-21

Jongeme	33/0.415	300	Standardisation	33KV MAGAMI	1	Sep-21
Kango	33/0.415	500	Standardisation	33KV MAGAMI	1	Sep-21
Kwakkwochi	33/0.415	500	Standardisation	33KV MAGAMI	1	Sep-21
Mogami 1	33/0.415	300	Standardisation	33KV MAGAMI	1	Sep-21
Mogami 2	33/0.415	300	Standardisation	33KV MAGAMI	1	Sep-21
Muruti	33/0.415	300	Standardisation	33KV MAGAMI	1	Sep-21
Nasarawa Wake	33/0.415	300	Standardisation	33KV MAGAMI	1	Sep-21
Rowan Kunku	33/0.415	300	Standardisation	33KV MAGAMI	1	Sep-21
Ruwan dawa	33/0.415	500	Standardisation	33KV MAGAMI	1	Sep-21
Tashar Sababi	33/0.415	300	Standardisation	33KV MAGAMI	1	Sep-21
Wanke Town	33/0.415	300	Standardisation	33KV MAGAMI	1	Sep-21
UNGUWAR Ali	11/0.415	300	Standardisation	11KV Canteen	1	Sep-21
UNGUWAR KAYA I	11/0.415	500	Standardisation	11KV Canteen	1	Sep-21
UNGUWAR MALAMAI	11/0.415	500	Standardisation	11KV Canteen	1	Sep-21
CONGO JUNCTION 1	11/0.415	300	Standardisation	11KV Canteen	1	Sep-21
CONGO JUNCTION 2	11/0.415	300	Standardisation	11KV Canteen	1	Sep-21
DAKACHE 1	11/0.415	500	Standardisation	11KV Canteen	1	Sep-21
DAKACHE 2	11/0.415	300	Standardisation	11KV Canteen	1	Sep-21
GANGAREN GWADI	11/0.415	300	Standardisation	11KV Canteen	1	Sep-21
LEVENTIS	11/0.415	300	Standardisation	11KV Canteen	1	Sep-21
MANGU VILLAGE	11/0.415	300	Standardisation	11KV Canteen	1	Sep-21
PARK ROAD	11/0.415	300	Standardisation	11KV Canteen	1	Sep-21
PZ	11/0.415	300	Standardisation	11KV Canteen	1	Sep-21
RIVER SIDE	11/0.415	500	Standardisation	11KV Canteen	1	Sep-21
SHAGALINKU	11/0.415	500	Standardisation	11KV Canteen	1	Sep-21
WTC	11/0.415	300	Standardisation	11KV Canteen	1	Sep-21
Ungwar KAYA II	11/0.415	300	Standardisation	11KV Canteen	1	Sep-21
UNGUWAR MALAMAI 2	11/0.415	300	Standardisation	11KV Canteen	1	Sep-21
DAKACE 4	11/0.415	500	Standardisation	11KV Canteen	1	Sep-21
JALZ BANK SABON GARI	11/0.415	300	Standardisation	11KV Canteen	1	Sep-21
BEAUTY GUEST INN	11/0.415	500	Standardisation	11KV GRA ZAR	1	Sep-21
NIPPOST	11/0.415	300	Standardisation	11KV GRA ZAR	1	Sep-21
DOGONVYARO	11/0.415	300	Standardisation	11KV GRA ZAR	1	Sep-21



GULIMA ROAD	11/0.415	300	Standardisation	11KV GRA ZAR	1	Sep-21
WESTERN WAY	11/0.415	500	Standardisation	11KV GRA ZAR	1	Sep-21
DOGARAWA 1	11/0.415	500	Standardisation	11KV GRA ZAR	1	Sep-21
DOGARAWA 2	11/0.415	300	Standardisation	11KV GRA ZAR	1	Sep-21
DORAWA 4	11/0.415	500	Standardisation	11KV GRA ZAR	1	Sep-21
DOGARAWA 3	11/0.415	300	Standardisation	11KV GRA ZAR	1	Sep-21
CHIKAJI LAYOUT	11/0.415	300	Standardisation	11KV GRA ZAR	1	Sep-21
TUDUN MUNTISIRA	11/0.415	300	Standardisation	11KV GRA ZAR	1	Sep-21
CIRCULAR ROAD 1	11/0.415	300	Standardisation	11KV GRA ZAR	1	Sep-21
CIRCULAR ROAD 2	11/0.415	300	Standardisation	11KV GRA ZAR	1	Sep-21
CIRCULAR ROAD 3	11/0.415	300	Standardisation	11KV GRA ZAR	1	Sep-21
QUEEN ELIZABETH ROAD 2 (CSP)	11/0.415	300	Standardisation	11KV GRA ZAR	1	Sep-21
MTD ROAD GRA CSP	11/0.415	300	Standardisation	11KV GRA ZAR	1	Sep-21
Unguwar Damakwarwa	11/0.415	300	Standardisation	11KV ABU	1	Sep-21
Unguwar Rimi	11/0.415	300	Standardisation	11KV ABU	1	Sep-21
Unguwar Yusi 1	11/0.415	300	Standardisation	11KV ABU	1	Sep-21
Unguwar Yusi 2	11/0.415	500	Standardisation	11KV ABU	1	Sep-21
Unguwar Yusi 3	11/0.415	300	Standardisation	11KV ABU	1	Sep-21
Basawa 1	11/0.415	300	Standardisation	11KV ABU	1	Sep-21
Basawa 2	11/0.415	300	Standardisation	11KV ABU	1	Sep-21
Emarto 2	11/0.415	300	Standardisation	11KV ABU	1	Sep-21
Emarto 1	11/0.415	500	Standardisation	11KV ABU	1	Sep-21
Kabarua layout	11/0.415	500	Standardisation	11KV ABU	1	Sep-21
Kwangila Kara 3	11/0.415	500	Standardisation	11KV ABU	1	Sep-21
Kwangila 2	11/0.415	300	Standardisation	11KV ABU	1	Sep-21
Kwangila 1	11/0.415	300	Standardisation	11KV ABU	1	Sep-21
Layin Zomo 1	11/0.415	500	Standardisation	11KV ABU	1	Sep-21
Layin Zomo 2	11/0.415	500	Standardisation	11KV ABU	1	Sep-21
Polladan 1	11/0.415	500	Standardisation	11KV ABU	1	Sep-21
Polladan 2	11/0.415	300	Standardisation	11KV ABU	1	Sep-21
Polladan 3	11/0.415	300	Standardisation	11KV ABU	1	Sep-21
Sakadadi	11/0.415	300	Standardisation	11KV ABU	1	Sep-21
Solama	11/0.415	300	Standardisation	11KV ABU	1	Sep-21

Seminary	11/0.415	500	Standardisation	11KV ABU	1	Sep-21
Hayin Liman	11/0.415	500	Standardisation	11KV ABU	1	Sep-21
Hayin Malam 1	11/0.415	300	Standardisation	11KV ABU	1	Sep-21
Hayin Malam 2	11/0.415	300	Standardisation	11KV ABU	1	Sep-21
Jama' a Village	11/0.415	300	Standardisation	11KV ABU	1	Sep-21
Koreye	11/0.415	300	Standardisation	11KV ABU	1	Sep-21
Tudun Sarki	11/0.415	300	Standardisation	11KV ABU	1	Sep-21
Zango Village	11/0.415	300	Standardisation	11KV ABU	1	Sep-21
Limaco	11/0.415	300	Standardisation	11KV ABU	1	Sep-21
Harwa Kwangila	11/0.415	300	Standardisation	11KV ABU	1	Sep-21
RANDAN KANO	11/0.415	300	Standardisation	11KV ABU	1	Sep-21
UNIT 2	11/0.415	500	Replacement	11KV HIGHCOST	1	Nov-21
ZAMBIA CRESCENT	11/0.415	500	Replacement	11KV HIGHCOST	1	Nov-21
PAMA 4	11/0.415	500	Replacement	11KV/PAMA	1	Nov-21
MAISAMARI	11/0.415	500	Replacement	11KV/PAMA	1	Nov-21
PAMA 6	11/0.415	500	Replacement	11KV/PAMA	1	Nov-21
Naroyi 7	11/0.415	500	Replacement	11KV VILAGE	1	Nov-21
Karji 1	11/0.415	500	Replacement	11KV VILAGE	1	Nov-21
Karji 2	11/0.415	500	Replacement	11KV VILAGE	1	Nov-21
JANRUWA 2	33/0.415	500	Replacement	33KV U/BORO	1	Nov-21
MAHUTA NEW EXTENSION 2	33/0.415	500	Replacement	33KV U/BORO	1	Nov-21
KAMATOM	11/0.415	500	Replacement	11KV SABO	1	Nov-21
BULUS 2	11/0.415	500	Replacement	11KV SABO	1	Nov-21
JULI 5	11/0.415	500	Replacement	11KV SABO	1	Nov-21
GURE 2	11/0.415	500	Replacement	11KV/PAMA	1	Nov-21
PAMA 7	11/0.415	500	Replacement	11KV/PAMA	1	Nov-21
NASARAWA 2	11/0.415	500	Replacement	11KV/PAMA	1	Nov-21
NARAYI 11	11/0.415	500	Replacement	11KV VILAGE	1	Nov-21
NARAYI 12	11/0.415	500	Replacement	11KV VILAGE	1	Nov-21

MAIGERO 11	11/0.415	500	Replacement	11KV VILLAGE	1	Nov-21
BACHAMA SUBSTATION	11/0.415	500	Replacement	11KVHIGHCOST	1	Nov-21
GANGARA STREET JUNCTION	11/0.415	500	Replacement	11KVHIGHCOST	1	Nov-21
OLD MAHUTA 3	33/0.415	500	Replacement	33KV U/BORO	1	Nov-21
JANRIWA 5	33/0.415	500	Replacement	33KV U/BORO	1	Nov-21
KAMAZOU 1	33/0.415	500	Replacement	33KV U/BORO	1	Nov-21
MARARABAN RIDO 9	33/0.415	500	Replacement	33KV U/BORO	1	Nov-21
MARARABAN RIDO 10	33/0.415	500	Replacement	33KV U/BORO	1	Nov-21
KUJAMA 3	33/0.415	500	Replacement	33KV U/BORO	1	Nov-21
RIDO VILLAGE 2	33/0.415	500	Replacement	33KV U/BORO	1	Nov-21
MARARABAN RIDO 11	33/0.415	500	Replacement	33KV U/BORO	1	Nov-21
KAMAZOU GRA	11/0.415	500	Replacement	11KV MAHUTA	1	Nov-21
KALADI 2	11/0.415	500	Replacement	11KV MAHUTA	1	Nov-21
BORO 6	11/0.415	500	Replacement	11KV MAHUTA	1	Nov-21
JULI 8	11/0.415	500	Replacement	11KV SABO	1	Nov-21
JULI 9	11/0.415	500	Replacement	11KV SABO	1	Nov-21
ALWALIKAZIR 3	11/0.415	500	Replacement	11KV SABO	1	Nov-21
BARAKALLAHU 1,5/5s	11/0.415	500	New Construction	11KV ZARIA ROAD	1	Dec-21
BARAKALLAHU 2 S/5s	11/0.415	500	New Construction	11KV ZARIA ROAD	1	Dec-21
BARAKALLAHU 3 S/5s	11/0.415	500	New Construction	11KV ZARIA ROAD	1	Dec-21
A/YERO	11/0.415	500	New Construction	11KV RABAH	1	Dec-21
YAN SHINKAFA	11/0.415	500	New Construction	11KV NASFAT	1	Dec-21
NATA'ALLAH 1	11/0.415	500	New Construction	11KV NASFAT	1	Dec-21
FARINGIDA 1 S/5	11/0.415	500	New Construction	11KV NASFAT	1	Dec-21
FARINGIDA 2 S/5	11/0.415	500	New Construction	11KV NASFAT	1	Dec-21

FARINGIDA 3 S/S	11/0.415	500	New Construction	11KV NASFAT	1	Dec-21
AGRI QTRS	11/0.415	500	New Construction	11KV NASFAT	1	Dec-21
BOLA U/KANAWA	11/0.415	500	New Construction	11KV NDA	1	Dec-21
BARRACKS 1	11/0.415	500	New Construction	11KV NDA	1	Dec-21
MUFTAHU S/S	11/0.415	500	New Construction	11KV A/BELLO	1	Dec-21
ROAD SAFETY	11/0.415	500	New Construction	11KV A/BELLO	1	Dec-21
TELY WOOD S/S	11/0.415	500	New Construction	11KV A/BELLO	1	Dec-21
POLICE HQTRS	11/0.415	500	New Construction	11KV T/HOSPITAL	1	Dec-21
MARYAM S/S	11/0.415	500	New Construction	11KV T/HOSPITAL	1	Dec-21
ED S/S	11/0.415	500	New Construction	11KV T/HOSPITAL	1	Dec-21
BABBAN SAURA 1 S/S	11/0.415	500	New Construction	11KV T/HOSPITAL	1	Dec-21
BABBAN SAURA 2	11/0.415	500	New Construction	11KV T/HOSPITAL	1	Dec-21
BABBAN SAURA 3	11/0.415	500	New Construction	11KV T/HOSPITAL	1	Dec-21
KABALA BY GOBARAU	11/0.415	500	New Construction	11KV T/HOSPITAL	1	Dec-21
HALIRU DANTORO	11/0.415	500	New Construction	11KV MALAU	1	Dec-21
MALAU LAYOUT	11/0.415	500	New Construction	11KV MALAU	1	Dec-21
GONI CLOSE	11/0.415	500	New Construction	11KV COSTAIN	1	Dec-21
KASUPDA	11/0.415	500	New Construction	11KV COSTAIN	1	Dec-21



SONG/KINSHAHA	11/0.415	500	New Construction	11KVA NACB	1	Dec-21
SONG ROAD	11/0.415	500	New Construction	11KVA NACB	1	Dec-21
ABAKPA BY RAIL 2 RELIEF	11/0.415	300	Replacement	11KV NDA	1	Dec-21
AL'UMMA 2 RELIEF	11/0.415	300	New Construction	11KV NDA	1	Dec-21
KAWO JUNCTION 2 RELIEF	11/0.415	300	Replacement	11KV STATE HOUSE	1	Dec-21
MECHANIC VILLAGE 2	11/0.415	300	Replacement	11KV KURMIN MASHI	1	Dec-21
SABON LAVI 3 S/5	11/0.415	300	Replacement	11KV KURMIN MASHI	1	Dec-21
MARKET 2 S/5	11/0.415	300	Replacement	11KV KURMIN MASHI	1	Dec-21
SHOOTING 3 RELIEF	11/0.415	300	Replacement	11KV T/HOSPITAL	1	Dec-21
CUSTOM 3 S/5 RELIEF	11/0.415	300	Replacement	11KV T/HOSPITAL	1	Dec-21
CAMP ROAD 2 RELIEF	11/0.415	300	Replacement	11KV T/HOSPITAL	1	Dec-21
MD ABUBAKR ESTATE 2 RELIEF	11/0.415	300	Replacement	11KV T/HOSPITAL	1	Dec-21
BLUE VELVET 2 RELIEF	11/0.415	300	Replacement	11KV T/HOSPITAL	1	Dec-21
ZAMBIA BY GAMBIA 2 RELIEF	11/0.415	300	Replacement	11KV MALALI	1	Dec-21
SAN SAMI 2 RELIEF	11/0.415	300	Replacement	11KV MALALI	1	Dec-21
KEKE A&B 2 RELIEF - EACH	11/0.415	300	Replacement	11KV MALALI	2	Dec-21
DOKA MAI JAMA'A RELIEF	11/0.415	300	Replacement	11KV MALALI	1	Dec-21
KAMSELEM 2 RELIEF	11/0.415	300	Replacement	11KV DAWAKI	1	Dec-21
ISHAKU/OGBADU 2 RELIEF	11/0.415	300	Replacement	11KV DAWAKI	1	Dec-21
UNG. MA'ALI 2 RELIEF	11/0.415	300	Replacement	11KV UNG. RIMI	1	Dec-21
KYAUTA VILLAGE 2 RELIEF	11/0.415	300	Replacement	11KV UNG. RIMI	1	Dec-21
DANHUNDO 2 RELIEF	11/0.415	300	Replacement	11KV UNG. RIMI	1	Dec-21
GIDAN DAUJ 2 RELIEF	11/0.415	300	Replacement	11KV UNG. RIMI	1	Dec-21
KADALURE/MASSALACI 2 RELIEF	11/0.415	300	Replacement	11KV UNG. RIMI	1	Dec-21
KADALURE/JUMINA 2 RELIEF	11/0.415	300	Replacement	11KV UNG. RIMI	1	Dec-21
SABON GIDA 2 RELIEF	11/0.415	300	Replacement	11KV UNG. RIMI	1	Dec-21
BUS-STOP 2 RELIEF	11/0.415	300	Replacement	11KV UNG. RIMI	1	Dec-21
DANBUSHIYA 4 RELIEF	11/0.415	300	Replacement	11KV UNG. RIMI	1	Dec-21
DANBUSHIYA 5 RELIEF	11/0.415	300	Replacement	11KV UNG. RIMI	1	Dec-21
POLICE COLLEGE PUBLIC 2	11/0.415	300	Replacement	11KV CONSTITUTION	1	Dec-21
BUS-STOP 2 RELIEF	11/0.415	300	Replacement	11KV COSTAIN	1	Dec-21

KAN BOLA 2 RELIEF	11/0.415	300	Replacement	11KV COSTAIN	1	Dec-21
ETSU/OHINOYE 2 RELIEF	11/0.415	300	Replacement	11KV NACB	1	Dec-21
GALADIMA ROAD 2 RELIEF	11/0.415	300	Replacement	11KV LUGARD HALL	1	Dec-21
DANKANDE 1	11/0.415	300	Replacement	11KV DANKANDE	1	Dec-21
KERAMA VILLAGE	11/0.415	500	Replacement	11KV DANKANDE	1	Dec-21
KARAMA S/S	11/0.415	500	Replacement	11KV ZARIA ROAD	1	Dec-21
KWARU 1 S/S	11/0.415	500	Replacement	11KV RABAH	1	Dec-21
G.CAPPA S/S	11/0.415	300	Replacement	11KV RABAH	1	Dec-21
NASFEAT 1 S/S	11/0.415	300	Replacement	11KV NASFEAT	1	Dec-21
DANMALIKI	33/0.415	300	Replacement	33KV NNPC	1	Dec-21
KWANGWAMI	33/0.415	300	Replacement	33KV MARADUN	1	Dec-21
BANI GA HANNU	33/0.415	300	Replacement	33KV KAUWA	1	Dec-21
ADARAWA	33/0.415	300	Replacement	33KV MAFARA	1	Dec-21
RIBE VILLAGE	33/0.415	300	Replacement	33KV MAFARA	1	Dec-21
ZARIA ST.	11/0.415	300	Replacement	11KV KAFANCHAN (TOWNSHIP)	1	Dec-21
SOKOTO STREET	11/0.415	300	Replacement	11KV KAFANCHAN (TOWNSHIP)	1	Dec-21
TTM	11/0.415	300	Replacement	11KV KAFANCHAN (TOWNSHIP)	1	Dec-21
BAPTIST	11/0.415	300	Replacement	11KV KAFANCHAN (TOWNSHIP)	1	Dec-21
BINZOM	11/0.415	300	Replacement	11KV KAFANCHAN (TOWNSHIP)	1	Dec-21
NITEL	11/0.415	300	Replacement	11KV KAFANCHAN (TOWNSHIP)	1	Dec-21
ECWA 2	11/0.415	300	Replacement	11KV KAFANCHAN (TOWNSHIP)	1	Dec-21
ZARIA ST 2	11/0.415	500	New Construction	11KV KAFANCHAN	1	Dec-21
UNGUWAN MUSA RELIEF	33/0.415	500	New Construction	33KV KAFANCHAN	1	Dec-21
UNGUWAN MUSA	33/0.415	500	Replacement	33KV KAFANCHAN	1	Dec-21
ANTHOR	33/0.415	300	Replacement	33KV KAFANCHAN	1	Dec-21



MALAM ACHU	33/0.415	500	Replacement	33KV KAFANCHAN	1	Dec-21
MAGAMIA 2	33/0.415	300	Replacement	33KV KAFANCHAN	1	Dec-21
UNGWAN RUHOGO	33/0.415	300	Replacement	33KV KAFANCHAN	1	Dec-21
SABON GARI	33/0.415	300	Replacement	11KV MANCHOK	1	Dec-21
JOS ROAD	33/0.415	300	Replacement	33KV KAFANCHAN	1	Dec-21
BAYAN GIDAN WAYA	33/0.415	300	Replacement	33KV KAFANCHAN	1	Dec-21
GODOGODO2	33/0.415	300	Replacement	33KV KAFANCHAN	1	Dec-21
RAMAI	33/0.415	300	Replacement	33KV KAFANCHAN	1	Dec-21
YANKALI	33/0.415	300	Replacement	SAMINAKA UNMANNED	1	Dec-21
IGC	33/0.415	300	Replacement	33KV KAFANCHAN	1	Dec-21
FADAN KAFE	33/0.415	300	Replacement	33KV KAFANCHAN	1	Dec-21
CHORI GALADIMA	33/0.415	300	Replacement	33KV KAFANCHAN	1	Dec-21
CHORI BURWAYE	33/0.415	300	Replacement	33KV KAFANCHAN	1	Dec-21
TAJME	33/0.415	300	Replacement	33KV KAFANCHAN	1	Dec-21
INDOFA	33/0.415	300	Replacement	33KV KAFANCHAN	1	Dec-21
BITARO 1	33/0.415	300	Replacement	33KV KAFANCHAN	1	Dec-21
GORA GAN 1	33/0.415	300	Replacement	33KV KAFANCHAN	1	Dec-21
KURMIN MASARA 1	33/0.415	300	Replacement	33KV KAFANCHAN	1	Dec-21
KURMIN MASARA 2	33/0.415	300	Replacement	33KV KAFANCHAN	1	Dec-21
ANKUNG 1	33/0.415	300	Replacement	33KV KAFANCHAN	1	Dec-21
KALAMBAINA	11/0.415	500	New Construction	KALAMBAINA	8	Dec-21
ZURU	11/0.415	500	New Construction	ZURU	4	Dec-21
GIDAN DARE (UNMANNED)	11/0.415	500	New Construction	GIDAN DARE (UNMANNED)	4	Dec-21
TAMAJE	11/0.415	500	New Construction	TAMAJE	8	Dec-21
HAYIN DANMANI	11/0.415	500	New Construction	HAYIN DANMANI	8	Dec-21
11KV Costain	11/0.415	500	New Construction	11KV Costain	4	Dec-21
ARGUNGU	11/0.415	500	New Construction	ARGUNGU	2	Dec-21

MILLENNIUM CITY	11/0.415	500	New Construction	MILLENNIUM CITY	7	Dec-21
11KV HIGH COST	11/0.415	500	Replacement	Spare DT	3	
11KV AHMADU BELLO WAY	11/0.415	500	Replacement	Spare DT	3	
11KV CONSTITUTION ROAD	11/0.415	500	Replacement	Spare DT	3	
11KV DAWAKI	11/0.415	500	Replacement	Spare DT	3	
11KV ISA KAITA	11/0.415	500	Replacement	Spare DT	3	
11KV LEGISLATIVE QUARTERS	11/0.415	500	Replacement	Spare DT	3	
11KV LUGGARD HALL	11/0.415	500	Replacement	Spare DT	3	
11KV NACB	11/0.415	500	Replacement	Spare DT	3	
11KV TEACHING HOSPITAL DKA	11/0.415	500	Replacement	Spare DT	3	
11KV UNGUWAN RIMI	11/0.415	500	Replacement	Spare DT	3	
11KV BULASA	11/0.415	500	Replacement	Spare DT	3	
11KV GRA KBI	11/0.415	500	Replacement	Spare DT	3	
11KV GWADANGWAI	11/0.415	500	Replacement	Spare DT	3	
11KV GWARI AVENUE	11/0.415	500	Replacement	Spare DT	3	
11KV NASSARAWA MKR	11/0.415	500	Replacement	Spare DT	3	
11KV GOVERNMENT HOUSE KADUNA	11/0.415	500	Replacement	Spare DT	3	
11KV LEVENTS	11/0.415	500	Replacement	Spare DT	3	
11KV POLY ROAD	11/0.415	500	Replacement	Spare DT	3	
11KV YANTUKWANE	11/0.415	500	Replacement	Spare DT	3	
11KV KADUNA ROAD	11/0.415	500	Replacement	Spare DT	3	
11KV LODGE ROAD	11/0.415	500	Replacement	Spare DT	3	
11KV ABU	11/0.415	500	Replacement	Spare DT	3	
11KV CANTEEN	11/0.415	500	Replacement	Spare DT	3	
11KV GRA ZAR	11/0.415	500	Replacement	Spare DT	3	
Total					1231	



Network: Injection Substations (33/11kV)							
Project Type: Construction, Reinforcement and Standardisation of Injection Sub-station							
#	Name of Substation	Location	N ^o of units	Type of work	Rating - MVA	Project Completion Date (MM - YY)	Expected Impact (MW)
1	KALAMBALINA	SOKOTO	2	New Construction	7.5	Nov-21	8
2	ZURU	KEBBI	1	New Construction	7.5	Nov-21	4
3	GIDAN DARE (UNMANNED)	SOKOTO	1	New Construction	7.5	Nov-21	5
4	TAMAJE	SOKOTO	2	New Construction	7.5	Nov-21	8
5	HAYIN DANMANI	RIGASA	2	New Construction	15	Nov-21	20
6	ABAKPA	DOKA	1	Additional Power Transformer	15	Nov-21	Improve hours of supply and upgrade of customers to Band A
7	AIRFORCE BASE (NAF)	KAWO	1	Additional Power Transformer	7.5	Nov-21	Improve hours of supply and upgrade of customers to Band A
8	DAWAKI	DOKA	1	Additional Power Transformer	15	Nov-21	Improve hours of supply and upgrade of customers to Band A
9	GONIN GORA	MAKERA	1	Additional Power Transformer	15	Nov-21	Improve hours of supply and upgrade of customers to Band A
10	MOGADISHU	RIGASA	1	Additional Power Transformer	15	Nov-21	Improve hours of supply and upgrade of customers to Band A
11	ARGUNGU	KEBBI	1	New Construction	15	Nov-21	4.3
12	MILLENIUM CITY	DOKA	1	New Construction	15	Nov-21	15
13	SHIKA	ZARIA	1	New Construction	15	Nov-21	5
14	ABU	ZARIA	1	New Construction	2.5	Nov-21	1
	Total				160		

Network: Standardisation of Existing Injection Substations (33/11KV)

Project Type: Replacement of Switch Gears, Control Panel and Protection Equipment

#	Name of Substation	Description	Location	Quantity	Project Completion Date (MM - YY)
1	33KV UNGUWAN BORO	33kV indoor Control Panel	Barnawa	1	Nov-21
2	33KV WATER WORKS	33kV indoor Control Panel	DOKA	1	Nov-21
3	33KV MOGADISHU	33kV indoor Control Panel	RIGASA	2	Nov-21
4	33KV POWER STATION	33kV indoor Control Panel	SOKOTO	1	Nov-21
10	33KV WATER WORKS	33kV Voltage Transformer	DOKA	1	Nov-21
11	33KV GONIN GORA	33kV Voltage Transformer	MAKERA	1	Nov-21
15	33KV WATER WORKS	Tripping Unit	DOKA	1	Nov-21
16	33KV KINKINAU	Tripping Unit	RIGASA	1	Nov-21
17	33KV POWER STATION	Tripping Unit	SOKOTO	1	Nov-21
	Total			10.00	

AT&C Loss Reduction Plan

#	Name	Description	Quantity	Project Completion Date
#	Commercial Management System (CMS) - (Module 1- Revenue Cycle Management)	The system will automate the process of new customer capture (Form 74), centralization of the Postpaid and Prepaid billing, Meter allocation, installation, and activation process, energy audit, payment channel's integration and aggregation.	400,000 Postpaid and 200,000 Prepaid in phase 1.	Nov-21

Customer Service Improvement Plan

#	Name	Description	Quantity	Project Completion Date (MM - YY)
1	Self Service Kiosk	ATM enabled self-service kiosk that will allow customers to pay their bills, vend electricity token, and lodge complaints. The kiosk will be installed at all the service centers starting from Band A and B service centers.	40	Nov-21
2	Call Centre Management System	Deployment of call centre management system	1	Nov-21
	Total		41	



IT Investments (GIS)		Project Completion Date (MM - YY)
#	Name	Description
1	Geographical Information System (GIS)Phase 1	Deployment of phase 1 GIS to monitor and control network, customer
		Nov-21

IT Investments (ERP)		Project Completion Date (MM - YY)	Expected Impact
#	Name		
1	Enterprise Resource Planning (Finance, HR & Payroll)	21-Nov	

IT Investments (AMI)		Description	Project Completion Date (MM - YY)	Expected Impact
#	Name			
1	Revenue Protection Project (RPP) supported by Advanced Metering Infrastructure (AMI)-Phase 1	Deployment of full AMI to monitor and control	Dec-21	

IT Investments (HSE)		Description	Project Completion Date
	Name		
1	Installation of Smoke Detectors and Fire Alarms.	Safety Equipment	Nov-21
2	Purchase of Fire Extinguishers for offices and Injection Substations.	Safety Equipment	Nov-21
3	Construction of Fire Hydrants for high rise building (KEDC HQ.)	Safety Equipment	Nov-21
4	Purchase of First Aid Boxes and accessories.	Safety Equipment	Nov-21
5	Purchase of Grounding Kits and Neon Testers.	Safety Equipment	Nov-21
6	Production of Safety Signages	Safety Equipment	Nov-21
7	HT LADDER	Safety Equipment	Nov-21
8	LT LADDER	Safety Equipment	Nov-21
9	Safety belt	Safety Equipment	Nov-21
10	(Electrical gloves)	Safety Equipment	Nov-21
11	(Tool box)	Safety Equipment	Nov-21
12	(Helmet)	Safety Equipment	Nov-21
13	(Safety boot)	Safety Equipment	Nov-21
14	(Coverall)	Safety Equipment	Nov-21

Network Metering (Smart Meters)			
#	Project Description	Description	Quantity
1	DT Meters	DT Metering system	1,860
2	Feeder Meters	33KV and 11KV Feeder Meters	300
MD Meters			
4	33KV CT/PT METERING PANEL	30/1, 100/5, 150/5	128
5	33KV OUTDOOR METERING PANEL (Oil Filled)	30/1, 100/5, 150/5	20
6	11KV MD CUSTOMER METERING PANEL	25/1, 50/5, 100/5, 200/5	300
7	11KV OUTDOOR METERING PANEL (Oil Filled)	50/5A, 100/5A	20
8	EMBEDDED MD CT OPERATED	100,200,300,500,800/5A	558
9	WHOLE CURRENT METERS	10(100)A	1000
	Total		2,308

Other Service Improvement Plan		
#	Name	Description
1	10KV Megger (MIT520/2)	Testing Equipment
2	Fluke Clamp-on Ammeter	Testing Equipment
3	Portable oil dielectric strength test set(OTS60P8)	Testing Equipment
4	Earth Resistance Tester (DET4TCR2)	Testing Equipment
5	Electrical Tool Box	Testing Equipment
6	Power Cable crimping tools (Cembra HT131-C Hydraulic Crimping Tool)	Testing Equipment
7	Power Cable Termination tools	Testing Equipment
8	Phase sequence tester	Testing Equipment
9	60KV High Pot (Hipotronics)	Testing Equipment
10	Digital Low Resistance Ammeter DLROs (247000 Series)	Testing Equipment
11	AC Leakage Current Clamp meter (MMMC850)	Testing Equipment
12	Megger Transformer Turn Ratio Tester (Handheld TRR20)	Testing Equipment
13	Power Quality Analyzer (Megger MPO2000 or Fluke 435-II)	Testing Equipment
14	Infrared Thermal Imager (Seek Thermal Compact Android USB-C Smartphone Thermal Camera (9Hz))	Testing Equipment
15	Infrared Thermal Imager (Fluke Ti450)	Testing Equipment
16	Cable Joining Tool (Thorne & Derrick GA-M30)	Testing Equipment



IT Investments (Other IT Projects)				
#	Name	Description	Quantity	Project Completion Date (MM - YY)
	VHF Radio Communication	Deployment of radio technology to ease communication	Lot	Dec-21
	Works Management System (Field Force Automation) Phase 1	Phase 1 WMS deployment	Lot	Dec-21
	Microsoft Enterprise System	Development of an Intranet system to automation and secured hosting of the corporate email, active directory, and SharePoint for ease of collaboration and document management within the company.	1000	Dec-21
	Fiber Optics Internet Connectivity	The fiber optics connectivity at the HQ has become necessary to ensure network reliability for both internet users and the applications hosted locally within the company's datacenter. Ongoing discussion already started with Backbone Connectivity Network.	155mbps	Dec-21
	Desktop Computers	Desktop computers for Administrative use across the company.	300	Dec-21
	Laptop Computers	Laptop computers for operational staff e.g. Area Mgrs, Heads of units, and Commercial Mgrs and Service Center Managers, HR and Finance Managers, etc. Also some key employees that are required to work on the go.	350	Dec-21
	High performance laptops	High end performance laptops	40	Dec-21
	NEPLAN Software		Lot	Dec-21
	42" Flat Screen TV	ICT monitoring centre for data analytics and infographics, GIS, network monitoring, smart metering system	10	Dec-21

Appendix 2 - Details of Planned 2022 Investments for Koduna Electricity Distribution Company

<i>Distribution Network: lines</i>					
<i>Project Type: Construction of 33kV Feeder</i>					
#	Project Description	Location	Route Length (km)	Project Completion Date (MM - YY)	Expected Impact in MW)
1	Construction of 33KV lines	Jaji	15	Dec-22	2
2	Construction of 33KV lines	Jere	20	Dec-22	2
3	Construction of 33KV lines	Saminaka	30	Dec-22	5
4	Construction of 33KV lines	Kohar Doka	10	Dec-22	2

<i>Distribution Network: lines</i>						
<i>Project Type: Rehabilitation of 33kV Feeder</i>						
#	Project Description	Type of Rehabilitation	Location	Route Length (km)	Project Completion Date (MM - YY)	Expected Impact in MW)
1	33KV NARAYI VILLAGE	Reconducing, Replacement of Poles, Replacement of Poles accessories	Barnawa	7	April 2022	0.44
2	33KV KAFANCHAN	Reconducing, Replacement of Poles, Replacement of Poles accessories	Kolanchan	22	June 2022	2.30
3	33KV ARGUNGU	Reconducing, Replacement of Poles, Replacement of Poles accessories	Kebbi	53	April 2022	1.08
4	33KV JEGA	Reconducing, Replacement of Poles, Replacement of Poles accessories	Kebbi	57	April 2022	0.06
5	33KV LABANA (DEDICATED)	Reconducing, Replacement of Poles, Replacement of Poles accessories	Kebbi	6	April 2022	1.82



6	33KV UNIVERSITY (DEDICATED)	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Kebbi	7	April 2022	0.05
7	33KV PAN	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Makera	11	April 2022	1.50
8	33KV UNIT (DEDICATED)	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Makera	10	April 2022	1.04
9	33KV AIRPORT ROAD	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Rigasa	20	April 2022	0.21
10	33KV RIGASA	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Rigasa	11	April 2022	0.04
11	33KV CCNN	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Sokoto	9	April 2022	2.7
12	33KV NEW INJECTION	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Sokoto	10	April 2022	0.8
13	33KV TOWNSHIP	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Sokoto	6	April 2022	0.1
14	33KV YABO/SHAGAR	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Sokoto	30	April 2022	2.0
15	33KV POWER HOUSE	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Zamfara	4	April 2022	1.4
16	33KV AVIATION	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Zaria	16	April 2022	0.8
17	33KV KOFAN DOKA	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Zaria	9	April 2022	0.8
18	33KV ZARIA WATER WORKS (DEDICATED)	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Zaria	9	April 2022	0.8

Distribution Network: lines

Project Type: Construction of 11kV Feeder

#	Project Description	Location	Route Length (km)	Project Completion Date (MM - YY)	Expected Impact in MW
---	---------------------	----------	-------------------	-----------------------------------	-----------------------

1	Line extension for new distribution transformers	11KV AREWA BOTTLERS	12	Dec-22	8
2	Line extension for new distribution transformers	11KV Barnowa	8	Dec-22	4
3	Line extension for new distribution transformers	11KV Gwari Avenue	2	Dec-22	5
4	Line extension for new distribution transformers	11KV SUNGLASS	2	Dec-22	8
5	Line extension for new distribution transformers	33KV Birnin Gwari	6	Dec-22	4
6	Line extension for new distribution transformers	33KV GWAGWADA	30	Dec-22	1
7	Line extension for new distribution transformers	33KV JERE	12	Dec-22	4.3
8	Line extension for new distribution transformers	ABU	12	Dec-22	8
9	Line extension for new distribution transformers	AIRPORT ROAD	2	Dec-22	4
10	Line extension for new distribution transformers	ASIKOLAYE	8	Dec-22	5
11	Line extension for new distribution transformers	Birnin Gwari	4	Dec-22	8
12	Line extension for new distribution transformers	Bulasa KBI	10	Dec-22	20
13	Line extension for new distribution transformers	DAM	10	Dec-22	1
14	Line extension for new distribution transformers	Federal Housing	6	Dec-22	8
15	Line extension for new distribution transformers	Federal Housing	6	Dec-22	4
16	Line extension for new distribution transformers	G.R.A KBI	8	Dec-22	5
17	Line extension for new distribution transformers	GRA	2	Dec-22	8
18	Line extension for new distribution transformers	Gwandan guji KBI	10	Dec-22	4
19	Line extension for new distribution transformers	HAYIN RIGASA	10	Dec-22	1
20	Line extension for new distribution transformers	KAKURI	4	Dec-22	8
21	Line extension for new distribution transformers	Kara	10	Dec-22	4
22	Line extension for new distribution transformers	KKB	6	Dec-22	5
23	Line extension for new distribution transformers	KUD	2	Dec-22	8
24	Line extension for new distribution transformers	LEVENTIS	2	Dec-22	4
25	Line extension for new distribution transformers	MAKARFI ROAD	14	Dec-22	1
26	Line extension for new distribution transformers	MANDO ROAD	10	Dec-22	8
26	Line extension for new distribution transformers	Nassarawa KBI	4	Dec-22	4
27	Line extension for new distribution transformers	NPZ	4	Dec-22	5
27	Line extension for new distribution transformers	POLY ROAD	4	Dec-22	8
28	Line extension for new distribution transformers	SABON GARIN KADUNA	6	Dec-22	4
28	Line extension for new distribution transformers	SOB	2	Dec-22	1



29	Line extension for new distribution transformers	Tudan woda KBI	2	Dec-22	8
29	Line extension for new distribution transformers	UNGUWAN MUAZU	4	Dec-22	4
30	Line extension for new distribution transformers	Ungurwan Yelwa	2	Dec-22	5
30	Line extension for new distribution transformers	WSS	4	Dec-22	8
31	Line extension for new distribution transformers	YANTUKWANE	4	Dec-22	4
31	Line extension for new distribution transformers	Zaria City	4	Dec-22	1

Distribution Network: lines

Project Type: Rehabilitation of 11kV Feeder

#	Project Description	Type of Rehabilitation	Location	Route Length (km)	Project Completion Date (MM - YY)	Expected Impact in MW
1	11KV MAHUTA	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Barnawa	9	April 2022	0.62
2	11KV PAMA	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Barnawa	21	April 2022	3.49
3	11KV SABON TASHA	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Barnawa	12	March 2022	8.23
4	11KV VILLAGE	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Barnawa	27	April 2022	3.15
5	11KV COSTAIN	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Doka	2	March 2022	0.37
6	11KV KAWO	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Doka	10	April 2022	2.47
7	11KV KURMIN MASHI	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Doka	26	March 2022	0.33
8	11KV MALALI	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Doka	12	February 2022	0.10
9	11KV NAFBASE	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Doka	18	March 2022	0.48
10	11KV NASFAT	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Doka	27	April 2022	7.18
11	11KV NIDA	Reconductoring, Replacement of Poles, Replacement of Poles accessories	Doka	7	February 2022	0.89

12	11KV NTA (DEDICATED)	Reconducing, Replacement of Poles, Replacement of Poles accessories	Doko	4	June 2022	0.26
13	11KV RABAH ROAD	Reconducing, Replacement of Poles, Replacement of Poles accessories	Doko	20	April 2022	0.37
14	11KV RAFIN GUZA	Reconducing, Replacement of Poles, Replacement of Poles accessories	Doko	6	April 2022	2.92
15	11KV STATEHOUSE	Reconducing, Replacement of Poles, Replacement of Poles accessories	Doko	10	April 2022	9.50
16	11KV ZARIA ROAD	Reconducing, Replacement of Poles, Replacement of Poles accessories	Doko	27	April 2022	1.66
17	11KV KARA	Reconducing, Replacement of Poles, Replacement of Poles accessories	Kebbi	15	April 2022	2.31
18	11KV NASSARAWA KBI	Reconducing, Replacement of Poles, Replacement of Poles accessories	Kebbi	8	February 2022	3.46
19	11KV TUDUN WADA KBI	Reconducing, Replacement of Poles, Replacement of Poles accessories	Kebbi	17	February 2022	0.65
20	11KV AREWA BOTTERS	Reconducing, Replacement of Poles, Replacement of Poles accessories	Makero	19	March 2022	0.32
21	11KV BARNAWA MKR	Reconducing, Replacement of Poles, Replacement of Poles accessories	Makero	20	April 2022	1.37
22	11KV CHEICO	Reconducing, Replacement of Poles, Replacement of Poles accessories	Makero	14	April 2022	1.75
23	11KV FEDERAL HOUSING	Reconducing, Replacement of Poles, Replacement of Poles accessories	Makero	25	April 2022	1.09
24	11KV KAKURI	Reconducing, Replacement of Poles, Replacement of Poles accessories	Makero	11	April 2022	0.92
25	11KV NOCACO	Reconducing, Replacement of Poles, Replacement of Poles accessories	Makero	9	April 2022	0.36
26	11KV NORTEX	Reconducing, Replacement of Poles, Replacement of Poles accessories	Makero	4	June 2022	0.49
27	11KV SUNGLASS	Reconducing, Replacement of Poles, Replacement of Poles accessories	Makero	4	Dec-22	7.18



28	11KV UNGUWAN YEIWA	Reconducting, Replacement of Poles, Replacement of Poles accessories	Makera	10	Dec-22	0.89
29	11KV ASIKOLAYE	Reconducting, Replacement of Poles, Replacement of Poles accessories	Rigasa	9	Dec-22	0.26
30	11KV HAYIN RIGASA	Reconducting, Replacement of Poles, Replacement of Poles accessories	Rigasa	14	Dec-22	0.37
31	11KV MAKARFI ROAD	Reconducting, Replacement of Poles, Replacement of Poles accessories	Rigasa	12	Dec-22	2.92
32	11KV MANDO ROAD	Reconducting, Replacement of Poles, Replacement of Poles accessories	Rigasa	16	Dec-22	9.50
33	11KV SABON GARIN RIG	Reconducting, Replacement of Poles, Replacement of Poles accessories	Rigasa	11	Dec-22	1.66
34	11KV TUDUN WADA RIG	Reconducting, Replacement of Poles, Replacement of Poles accessories	Rigasa	9	Dec-22	2.31
35	11KV UNGUWAN MUAZU	Reconducting, Replacement of Poles, Replacement of Poles accessories	Rigasa	16	Dec-22	3.46
36	11KV WATER RESOURCES (DEDICATED)	Reconducting, Replacement of Poles, Replacement of Poles accessories	Rigasa	13	Dec-22	0.65
37	11KV ARMY BARRACK	Reconducting, Replacement of Poles, Replacement of Poles accessories	Sokoto	26	Dec-22	0.32
38	11KV DIORI HAMMANI	Reconducting, Replacement of Poles, Replacement of Poles accessories	Sokoto	23	Dec-22	1.37
39	11KV DURBAWA	Reconducting, Replacement of Poles, Replacement of Poles accessories	Sokoto	10	Dec-22	1.75
40	11KV FARFARU	Reconducting, Replacement of Poles, Replacement of Poles accessories	Sokoto	28	Dec-22	1.09
41	11KV INDUSTRIAL SOK	Reconducting, Replacement of Poles, Replacement of Poles accessories	Sokoto	24	Dec-22	0.92
42	11KV KUEPERS	Reconducting, Replacement of Poles, Replacement of Poles accessories	Sokoto	12	Dec-22	0.36

43	11KV MABERA	Reconducing, Replacement of Poles,Replacement of Poles accessories	Sokoto	20	Dec-22	7.18
44	11KV NTA SOK	Reconducing, Replacement of Poles,Replacement of Poles accessories	Sokoto	18	Dec-22	0.89
45	11KV SULTAN PALACE	Reconducing, Replacement of Poles,Replacement of Poles accessories	Sokoto	11	Dec-22	0.26
46	11KV TOWN	Reconducing, Replacement of Poles,Replacement of Poles accessories	Sokoto	15	Dec-22	0.37
47	11KV WATERWORK S SOK	Reconducing, Replacement of Poles,Replacement of Poles accessories	Sokoto	37	Dec-22	2.92
48	11KV DAMBA	Reconducing, Replacement of Poles,Replacement of Poles accessories	Zamfara	12	Dec-22	9.50
49	11KV FGGC	Reconducing, Replacement of Poles,Replacement of Poles accessories	Zamfara	6	Dec-22	1.66
50	11KV GADA BIJU	Reconducing, Replacement of Poles,Replacement of Poles accessories	Zamfara	18	Dec-22	2.31
51	11KV GRA ZAM	Reconducing, Replacement of Poles,Replacement of Poles accessories	Zamfara	17	Dec-22	3.46
52	11KV INDUSTRIAL ZAM	Reconducing, Replacement of Poles,Replacement of Poles accessories	Zamfara	27	Dec-22	0.65
53	11KV POLY GATE	Reconducing, Replacement of Poles,Replacement of Poles accessories	Zamfara	7	Dec-22	0.32
54	11KV SABON GARIN ZAM	Reconducing, Replacement of Poles,Replacement of Poles accessories	Zamfara	14	Dec-22	1.37
55	11KV TUDUN WADA ZAM	Reconducing, Replacement of Poles,Replacement of Poles accessories	Zamfara	7	Dec-22	1.75
56	11KV WATER BOARD	Reconducing, Replacement of Poles,Replacement of Poles accessories	Zamfara	25	Dec-22	1.09
57	11KV ZAMTEX	Reconducing, Replacement of Poles,Replacement of Poles accessories	Zamfara	3	Dec-22	0.92
58	11KV DAM	Reconducing, Replacement of Poles,Replacement of Poles accessories	Zaria	20	Dec-22	0.36
59	11KV KOFAN KIBO	Reconducing, Replacement of Poles,Replacement of Poles accessories	Zaria	21	Dec-22	0.32



60	11KV NNPC ZAR	Reconducing, Replacement of Poles, Replacement of Poles accessories	Zaria	26	Dec-22	0.32
61	11KV RLY/NTC	Reconducing, Replacement of Poles, Replacement of Poles accessories	Zaria	9	Dec-22	1.37
62	11KV SABON GARI ZAR	Reconducing, Replacement of Poles, Replacement of Poles accessories	Zaria	10	Dec-22	1.75
63	11KV SAMARU	Reconducing, Replacement of Poles, Replacement of Poles accessories	Zaria	33	Dec-22	0.32
64	11KV TEACHING HOSPITAL ZAR	Reconducing, Replacement of Poles, Replacement of Poles accessories	Zaria	12	Dec-22	1.37
65	11KV WUSASA	Reconducing, Replacement of Poles, Replacement of Poles accessories	Zaria	21	Dec-22	1.75
66	11KV ZARIA CITY	Reconducing, Replacement of Poles, Replacement of Poles accessories	Zaria	20	Dec-22	1.75

Distribution Network: lines

Project Type: Construction and Rehabilitation of 0.400KV Feeder

#	Project Description	Location	Route Length (km)	Project Completion Date (MM - YY)
1	Rehabilitation of 415KV lines	11KV MAHUTA	30	June 2022
2	Rehabilitation of 415KV lines	11KV PAMA	25	June 2022
3	Rehabilitation of 415KV lines	11KV SABON TASHA	26	June 2022
4	Rehabilitation of 415KV lines	11KV VILLAGE	25	June 2022
5	Rehabilitation of 415KV lines	11KV COSTAIN	26	June 2022
6	Rehabilitation of 415KV lines	11KV KAWO	25	June 2022
7	Rehabilitation of 415KV lines	11KV KURMIN MASHI	25	June 2022
8	Rehabilitation of 415KV lines	11KV MALAI	25	June 2022
9	Rehabilitation of 415KV lines	11KV NAFBASE	25	June 2022
10	Rehabilitation of 415KV lines	11KV NASFAT	30	June 2022
11	Rehabilitation of 415KV lines	11KV NDA	27	June 2022
12	Rehabilitation of 415KV lines	11KV NTA (DEDICATED)	25	June 2022

13	Rehabilitation of 415KV lines	11KV RABAH ROAD	28	June 2022
14	Rehabilitation of 415KV lines	11KV RAFIN GUZA	20	June 2022
15	Rehabilitation of 415KV lines	11KV STATEHOUSE	26	June 2022
16	Rehabilitation of 415KV lines	11KV ZARIA ROAD	25	June 2022
17	Rehabilitation of 415KV lines	11KV KARA	29	June 2022
18	Rehabilitation of 415KV lines	11KV NASSARAWA KBI	25	June 2022
19	Rehabilitation of 415KV lines	11KV TUDUN WADA KBI	30	June 2022
20	Rehabilitation of 415KV lines	11KV AREWA BOTTLERS	25	June 2022
21	Rehabilitation of 415KV lines	11KV BARNAWA MKR	25	June 2022
22	Rehabilitation of 415KV lines	11KV CHELCO	25	June 2022
23	Rehabilitation of 415KV lines	11KV FEDERAL HOUSING	29	June 2022
24	Rehabilitation of 415KV lines	11KV KAKURI	25	June 2022
25	Rehabilitation of 415KV lines	11KV NOCACO	25	June 2022
26	Rehabilitation of 415KV lines	11KV NORTEX	29	June 2022
	Construction of new 415 lines	11KV AREWA BOTTLERS	2	Dec-22
	Construction of new 415 lines	11KV Barnawa	2	Dec-22
	Construction of new 415 lines	11KV Gwari Avenue	2	Dec-22
	Construction of new 415 lines	11KV SUNGLASS	2	Dec-22
	Construction of new 415 lines	33KV Birnin Gwari	2	Dec-22
	Construction of new 415 lines	33KV GWAGWADA	2	Dec-22
	Construction of new 415 lines	33KV JERE	2	Dec-22
	Construction of new 415 lines	ABU	2	Dec-22
	Construction of new 415 lines	AIRPORT ROAD	2	Dec-22
	Construction of new 415 lines	ASIKOLAYE	2	Dec-22
	Construction of new 415 lines	Birnin Gwari	2	Dec-22
	Construction of new 415 lines	Bulasa KBI	2	Dec-22
	Construction of new 415 lines	DAM	2	Dec-22
	Construction of new 415 lines	Federal Housing	2	Dec-22
	Construction of new 415 lines	Federal Housing	2	Dec-22
	Construction of new 415 lines	G.R.A KBI	2	Dec-22
	Construction of new 415 lines	GRA	2	Dec-22
	Construction of new 415 lines	Gwandan goji KBI	2	Dec-22



	Construction of new 415 lines	HAYIN RIGASA	2	Dec-22
	Construction of new 415 lines	KAKURI	2	Dec-22
	Construction of new 415 lines	Kara	2	Dec-22
	Construction of new 415 lines	KKB	2	Dec-22
	Construction of new 415 lines	KUD	2	Dec-22
	Construction of new 415 lines	LEVENTIS	2	Dec-22
	Construction of new 415 lines	MAKARFI ROAD	2	Dec-22
	Construction of new 415 lines	MANDO ROAD	2	Dec-22
	Construction of new 415 lines	Nassarawa KBI	2	Dec-22
	Construction of new 415 lines	NPZ	2	Dec-22
	Construction of new 415 lines	POLY ROAD	2	Dec-22
	Construction of new 415 lines	SABON GARIN KADUNA	2	Dec-22
	Construction of new 415 lines	SOB	2	Dec-22
	Construction of new 415 lines	Tudun wado KBI	2	Dec-22
	Construction of new 415 lines	UNGUWAN MUAZU	2	Dec-22
	Construction of new 415 lines	Ungwan Yelwa	2	Dec-22
	Construction of new 415 lines	WSS	2	Dec-22
	Construction of new 415 lines	YANTUKWANE	2	Dec-22
	Construction of new 415 lines	Zaria City	2	Dec-22

Distribution Network: stations

Project Type: New Construction, Reinforcement and Standardisation of Distribution Sub-station

#	Name of Substation	Transformation Voltage (kV)	Rating - kVA	Location	Quantity	Project Completion Date (MM - YY)
	Almu Yari Form	11/0.415	500	G.R.A KBI	1	Dec-22
1	Alu Zoki	11/0.415	500	G.R.A KBI	1	Dec-22
2	Aboki	11/0.415	500	G.R.A KBI	1	Dec-22
3	Ribado 2	11/0.415	500	G.R.A KBI	1	Dec-22
4	Heroes	11/0.415	500	Kara	1	Dec-22
5	Kallamu Alero	11/0.415	500	Kara	1	Dec-22

6	Mangorori relief	11/0.415	500	Kara		1	Dec-22
7	Langodo relief	11/0.415	500	Kara		1	Dec-22
8	Massoloci	11/0.415	500	Kara		1	Dec-22
9	H.A.T.C	11/0.415	500	Nassarawa KBI		1	Dec-22
10	Kabu-kabu	11/0.415	500	Nassarawa KBI		1	Dec-22
11	Aliero Quarter 2 (main gate)	11/0.415	500	Gwandon gaji KBI		1	Dec-22
12	Gwodangaji 1	11/0.415	500	Gwandon gaji KBI		1	Dec-22
13	Immigration	11/0.415	500	Gwandon gaji KBI		1	Dec-22
14	Larix 1	11/0.415	500	Gwandon gaji KBI		1	Dec-22
15	Kawara layout	11/0.415	500	Gwandon gaji KBI		1	Dec-22
16	Gandun kaya	11/0.415	500	Tudun wada KBI		1	Dec-22
17	Kala road	11/0.415	500	Bulasa KBI		1	Dec-22
18	Tonki	11/0.415	500	Bulasa KBI		1	Dec-22
19	Jogwodeji	11/0.415	500	Bulasa KBI		1	Dec-22
20	Perm. Sec.	11/0.415	500	Bulasa KBI		1	Dec-22
21	Abi 2	11/0.415	500	Bulasa KBI		1	Dec-22
22	Old Barnawa	11KV/0.415V	500	11KV Barnawa		1	Dec-22
23	New Barnawa	11KV/0.415V	500	11KV Barnawa		1	Dec-22
24	Tonko tele	11KV/0.415V	300	11KV Gwari Avenue		1	Dec-22
	GOVERNMENT LAND1	33KV/0.415V	500	33KV GWAGWADA		1	Dec-22
	U/ZAWU	33KV/0.415V	500	33KV GWAGWADA		1	Dec-22
	DUTSE	33KV/0.415V	500	33KV GWAGWADA		1	Dec-22
	GWAGWADA 2	33KV/0.415V	500	33KV GWAGWADA		1	Dec-22
	TOLL GATE	33KV/0.415V	500	33KV GWAGWADA		1	Dec-22
	A/BARDE	33KV/0.415	500	33KV GWAGWADA		1	Dec-22
	ROMI BUS STOP	11KV/0.415V	500	11KV AREWA BOTTLEERS		1	Dec-22
	CHURCH ROAD	11KV/0.415V	500	11KV AREWA BOTTLEERS		1	Dec-22
	MANYA	11KV/0.415V	300	11KV AREWA BOTTLEERS		1	Dec-22
	COMMITTEE	11KV/0.415V	500	11KV AREWA BOTTLEERS		1	Dec-22
	GBAGYI VILLA II	11KV/0.415V	300	11KV AREWA BOTTLEERS		1	Dec-22
	MASALACI II	11KV/0.415V	500	11KV AREWA BOTTLEERS		1	Dec-22



	ZOKORIKO 2	11KV/0.415V	300	11KV SUNGLASS	2	Dec-22
	Bahago	11KV/0.415V	500	Ungwan Yelwa	1	Dec-22
	MAKAMA	33KV/0.415V	500	33KV JERE	2	Dec-22
	KASABERE	33KV/0.415V	500	33KV JERE	1	Dec-22
	KATERI	33KV/0.415V	500	33KV JERE	2	Dec-22
	IDDAH 3	33KV/0.415V	500	33KV JERE	2	Dec-22
	TAFA I	33KV/0.415V	500	33KV JERE	2	Dec-22
	TAFA II	33KV/0.415V	500	33KV JERE	2	Dec-22
	UNGWAN TANKO II	11KV/0.415V	500	Federal Housing	1	Dec-22
	UNGWAN WAZIRI II	11KV/0.415V	500	Federal Housing	1	Dec-22
	ROMI NEW EXTENSION II	11KV/0.415V	500	Federal Housing	1	Dec-22
	DADINKOWA2	11KV/0.415V	300	KAKURI	1	Dec-22
	DANDAU2	11KV/0.415V	300	KAKURI	1	Dec-22
	Federal Housing II	11KV/0.415V	500	Federal Housing	1	Dec-22
	Ungwan Woziri I Relief	11KV/0.415V	500	Federal Housing	1	Dec-22
#	Daruni/Gov Land II Relief	11KV/0.415V	500	Federal Housing	1	Dec-22
	Old Barnawa 2	11KV/0.415V	500	11KV Barnawa	1	Dec-22
	New Barnawa 2	11KV/0.415V	500	11KV Barnawa	1	Dec-22
	LAMIGYI 3	33KV/0.415	500	33KV GWAGWADA	1	Dec-22
	LAMIGYI 4	33KV/0.415	500	33KV GWAGWADA	1	Dec-22
	U/ZAWU 2	33KV/0.415	500	33KV GWAGWADA	1	Dec-22
	SABON GARI 4	33KV/0.415	500	33KV GWAGWADA	1	Dec-22
	SABON GARI 5	33KV/0.415	500	33KV GWAGWADA	1	Dec-22
	SABON GARI 6	33KV/0.415	500	33KV GWAGWADA	1	Dec-22
	AUDU JAGWAM 1	33KV/0.415	300	33KV GWAGWADA	1	Dec-22
	DOKA VILLAGE 1	33KV/0.415	300	33KV GWAGWADA	1	Dec-22
	KONAN BATURE 1	33KV/0.415	300	33KV GWAGWADA	1	Dec-22
	LAMIGYI III	33KV/0.415	500	33KV GWAGWADA	1	Dec-22
	LAMIGYI IV	33KV/0.415	500	33KV GWAGWADA	1	Dec-22
	UNGWAN / ZAWU II	33KV/0.415	500	33KV GWAGWADA	1	Dec-22
	SABON GARI IV	33KV/0.415	500	33KV GWAGWADA	1	Dec-22

SABON GARI V	33KV/0.415	500	33KV GWAGWADA	1	Dec-22
Kurmin Gwari/Alaka 1	11KV/0.415V	500	11KV Norhex.	1	Dec-22
Strike Force 1	11KV/0.415V	500	11KV Norhex.	1	Dec-22
NEW ZOKORIKO	11KV/0.415V	500	SUNGLASS	1	Dec-22
MAKAMA	33KV/0.415	500	JERE	1	Dec-22
TAFAVI	33KV/0.415	500	JERE	1	Dec-22
UNGLUWAN WANDARA KATARI	33KV/0.415	500	JERE	1	Dec-22
GWAKURU	33KV/0.415	500	JERE	1	Dec-22
Old Barnawa	11KV/0.415V	500	11KV Barnawa	1	Dec-22
New Barnawa	11KV/0.415V	500	11KV Barnawa	1	Dec-22
Geological survey	11KV/0.415V	300	11KV NASSARAWA	1	Dec-22
Television G.R.A.	11KV/0.415V	300	U/Yelwa	1	Dec-22
Makaranta 1	11KV/0.415V	300	U/Yelwa	1	Dec-22
Makaranta 2	11KV/0.415V	300	U/Yelwa	1	Dec-22
Bako	11KV/0.415V	300	U/Yelwa	1	Dec-22
Halima	11KV/0.415V	300	U/Yelwa	1	Dec-22
Television Market	11KV/0.415V	500	U/Yelwa	1	Dec-22
Damaguri	11KV/0.415V	300	11kv Gwari Avenue	1	Dec-22
ongola	11KV/0.415V	300	11kv Gwari Avenue	1	Dec-22
Cameroon 1	11KV/0.415V	300	11kv Gwari Avenue	1	Dec-22
Somalia 2	11KV/0.415V	300	11kv Gwari Avenue	1	Dec-22
JULI 1	11KV/0.415V	300	GWAGWADA FEEDER	1	Dec-22
JULI 2	11KV/0.415V	300	GWAGWADA FEEDER	1	Dec-22
KONAN BATURE	11KV/0.415V	300	GWAGWADA FEEDER	1	Dec-22
SABON MARO	11KV/0.415V	300	GWAGWADA FEEDER	1	Dec-22
AUDU JAGWAM	11KV/0.415V	300	GWAGWADA FEEDER	1	Dec-22
KUBACHA	33KV/0.415	300	JERE FEEDER	1	Dec-22
MALAM TANKO	33KV/0.415	300	JERE FEEDER	1	Dec-22
BAKIN KASUWA	33KV/0.415	500	JERE FEEDER	1	Dec-22
SARKI HOUSE	33KV/0.415	500	JERE FEEDER	1	Dec-22
TAFAV	33KV/0.415	300	JERE FEEDER	1	Dec-22
DUDU	11KV/0.415V	500	YAUURI	1	Dec-22



HILLSIDE	11KV/0.415V	500	YAUJRI	1	Dec-22
COPPERS LODGE CLUB	11KV//0.415V	500	YAUJRI	1	Dec-22
ACHA VILLA	11KV//0.415V	500	YAUJRI	1	Dec-22
LOWCOAST	11KV//0.415V	500	YELWA	1	Dec-22
MAKAMA	11KV//0.415V	500	YELWA	1	Dec-22
UNGUWAN KABO	11KV//0.415V	500	YELWA	1	Dec-22
TASHA	11KV//0.415V	500	ZURU	1	Dec-22
KASUWAN DAJI	11KV//0.415V	500	ZURU	1	Dec-22
DAN MANGORO	11KV//0.415V	500	ZURU	1	Dec-22
GARAGE	11KV//0.415V	500	ZURU	1	Dec-22
SHADIWANKA	11KV//0.415V	500	ZURU	1	Dec-22
GRA 1	11KV//0.415V	500	ZURU	1	Dec-22
DONGO 1	11KV//0.415V	500	ZURU	1	Dec-22
KWANA BAGUDO	33KV//0.415	500	KOKO	1	Dec-22
HILIN HARISU	33KV//0.415	500	KOKO	1	Dec-22
KASUWAN BAGUDO	33KV//0.415	500	KOKO	1	Dec-22
UNION BANK BADUGO	33KV//0.415	500	KOKO	1	Dec-22
NGASKI 1	33KV//0.415	500	NGASKI	1	Dec-22
WATER BOARD	33KV//0.415	500	NGASKI	1	Dec-22
SARKIN YARBAWA	33KV//0.415	500	NGASKI	1	Dec-22
CGC	33KV//0.415	500	NGASKI	1	Dec-22
HAYIN SHITTU 1	11//0.415KV	500	Birin Gwari	1	Dec-22
YANTUKWANE II	11//0.415KV	500	YANTUKWANE	1	Dec-22
BURUKU 1	33//0.415KV	500	AIRPORT ROAD	1	Dec-22
MASALLACIN KANO ROAD	11//0.415KV	500	LEVENTIS	1	Dec-22
C 8 N BIDA ROAD	11//0.415KV	500	POLY ROAD	1	Dec-22
M&K	11//0.415KV	500	POLY ROAD	1	Dec-22
JUBRIL S/S	11//0.415KV	500	MANDO ROAD	1	Dec-22
STERLING 2	11//0.415KV	500	MANDO ROAD	1	Dec-22

STERLING 3	11/0.415KV	500	MANDO ROAD	1	Dec-22
ASIKOLAYE II	11/0.415KV	500	ASIKOLAYE	1	Dec-22
DABBA II	11/0.415KV	500	ASIKOLAYE	1	Dec-22
DABBA III	11/0.415KV	500	ASIKOLAYE	1	Dec-22
ORI OKIN	11/0.415KV	500	ASIKOLAYE	1	Dec-22
ABUJA 4 S/5	11/0.415KV	500	HAYIN RIGASA	1	Dec-22
B.M S/5	11/0.415KV	500	MAKARFI ROAD	1	Dec-22
MASHI WAZIRI	11/0.415KV	500	MAKARFI ROAD	1	Dec-22
MADINA	11/0.415KV	500	SABON GARIN KADUNA	1	Dec-22
TUDUN CINEMA 2	11/0.415KV	500	SABON GARIN KADUNA	1	Dec-22
DAMARI 1	33/0.415KV	500	33KV Birnin Gwari	1	Dec-22
UDAWA 1	33/0.415KV	500	33KV Birnin Gwari	1	Dec-22
UDAWA 2	33/0.415KV	500	33KV Birnin Gwari	1	Dec-22
KABIRU HOSPITAL 2	11/0.415KV	300	Birnin Gwari	1	Dec-22
NAIRI 4	11/0.415KV	300	UNGUWAN MUAZU	1	Dec-22
U/MUAZU VILLAGE 2	11/0.415KV	300	UNGUWAN MUAZU	1	Dec-22
AMINA NAMADI 3	11/0.415KV	300	YANTUKWANE	1	Dec-22
BALA HARUNA 2	11/0.415KV	300	MANDO ROAD	1	Dec-22
NECCO 3	11/0.415KV	300	MANDO ROAD	1	Dec-22
ADDO GWARAM 2	11/0.415KV	300	HAYIN RIGASA	1	Dec-22
BAYAN WUYA 3	11/0.415KV	300	HAYIN RIGASA	1	Dec-22
BILIYAMINU 3	11/0.415KV	300	HAYIN RIGASA	1	Dec-22
TARO TARO 3	11/0.415KV	300	HAYIN RIGASA	1	Dec-22
ALMUSTAPHA 5	11/0.415KV	300	MAKARFI ROAD	1	Dec-22
JUMARE 3	11/0.415KV	300	MAKARFI ROAD	1	Dec-22
SARKIN AREWA 2	11/0.415KV	300	MAKARFI ROAD	1	Dec-22



YANKFI 2	11/0.415KV	300	MAKARFI ROAD	1	Dec-22
BIDDA 2	11/0.415KV	300	MAKARFI ROAD	1	Dec-22
GIDAN KADA 2	11/0.415KV	300	SABON GARIN KADUNA	1	Dec-22
NARIYA 1	11/0.415KV	500	11KV UNGWAR MUAZU	1	Dec-22
WATER RESOURCES PUBLIC	11/0.415KV	300	11KV MANDO ROAD	1	Dec-22
<i>Hanwa village</i>	11/0.415KV	500	NPZ	1	Dec-22
<i>Hanwa Water Tank 2</i>	11/0.415KV	500	NPZ	1	Dec-22
UNGUWAR ALKALI 1	11/0.415KV	500	KKB	1	Dec-22
UNGUWAR DANMADAMI	11/0.415KV	500	KKB	1	Dec-22
KOFAN/KIBO	11/0.415KV	500	KKB	1	Dec-22
UNGUWAR ZAKARA	11/0.415KV	500	WSS	1	Dec-22
LOW COST 2	11/0.415KV	500	WSS	1	Dec-22
K / DOKA 2	11/0.415KV	500	Zaria City	1	Dec-22
PARADISE	11/0.415KV	500	Zaria City	1	Dec-22
DOGARAWA SUBSTATION III	11/0.415KV	500	GRA	1	Dec-22
<i>Abattoir Zango</i>	11/0.415KV	500	ABU	1	Dec-22
<i>Basawa 1</i>	11/0.415KV	500	ABU	1	Dec-22
<i>Kwangila 2</i>	11/0.415KV	500	ABU	1	Dec-22
<i>Palladan 2</i>	11/0.415KV	500	ABU	1	Dec-22
<i>Sakofadi</i>	11/0.415KV	500	ABU	1	Dec-22
<i>Hoyin Melem 1</i>	11/0.415KV	500	ABU	1	Dec-22
HAYIN OJO SUBSTATION II	11/0.415KV	500	DAM	1	Dec-22
HAYIN OJO SUBSTATION I	11/0.415KV	500	DAM	1	Dec-22
KAKIYEI	11/0.415KV	500	DAM	1	Dec-22
MUCHIYA B/TITI	11/0.415KV	500	DAM	1	Dec-22
UCHE ROAD	11/0.415KV	500	DAM	1	Dec-22
Kidandan SUBSTATION 2	33KV/0.415	500	SOB	1	Dec-22
BAGADAZA VILLAGE	33KV/0.415	500	KUD	1	Dec-22
NBTE 2	11/0.415KV	300	11KV HIGH COST	1	Dec-22
ABDULLAH 1	11/0.415KV	300	11KV VILLAGE	1	Dec-22

ABDULAH 2	11/0.415KV	300	11KV VILLAGE	1	Dec-22
AGRIC QUARTERS	11/0.415KV	300	11KV VILLAGE	1	Dec-22
DAILY TIMES	11/0.415KV	500	11KV VILLAGE	1	Dec-22
DAN ALHAI	11/0.415KV	300	11KV VILLAGE	1	Dec-22
EGYPT ROAD	11/0.415KV	500	11KV VILLAGE	1	Dec-22
GUGA	11/0.415KV	500	11KV VILLAGE	1	Dec-22
I. G. 1	11/0.415KV	500	11KV VILLAGE	1	Dec-22
I. G. 2	11/0.415KV	500	11KV VILLAGE	1	Dec-22
KUJAMA ROAD	11/0.415KV	500	11KV VILLAGE	1	Dec-22
LAMIDO CLOSE	11/0.415KV	300	11KV VILLAGE	1	Dec-22
MAIGERO 3	11/0.415KV	300	11KV VILLAGE	1	Dec-22
MAIGERO 4	11/0.415KV	300	11KV VILLAGE	1	Dec-22
METCHO	11/0.415KV	500	11KV VILLAGE	1	Dec-22
CHORI	11/0.415KV	500	11KV VILLAGE	1	Dec-22
NARAYI 1	11/0.415KV	500	11KV VILLAGE	1	Dec-22
NARAYI 2	11/0.415KV	500	11KV VILLAGE	1	Dec-22
NARAYI 3	11/0.415KV	500	11KV VILLAGE	1	Dec-22
NARAYI 4	11/0.415KV	500	11KV VILLAGE	1	Dec-22
NARAYI 5	11/0.415KV	500	11KV VILLAGE	1	Dec-22
NARAYI 6	11/0.415KV	500	11KV VILLAGE	1	Dec-22
NARAYI 7	11/0.415KV	500	11KV VILLAGE	1	Dec-22
NARAYI 8	11/0.415KV	500	11KV VILLAGE	1	Dec-22
STUDIO 24	11/0.415KV	300	11KV VILLAGE	1	Dec-22
TIPPER GARAGE	11/0.415KV	500	11KV VILLAGE	1	Dec-22
UNGUWAR MAIGERO 1	11/0.415KV	500	11KV VILLAGE	1	Dec-22
UNGUWAR MAIGERO 2	11/0.415KV	500	11KV VILLAGE	1	Dec-22
TERBANACLE	11/0.415KV	500	11KV VILLAGE	1	Dec-22
MAIGERO 5	11/0.415KV	300	11KV VILLAGE	1	Dec-22
MAIGERO 6	11/0.415KV	500	11KV VILLAGE	1	Dec-22
HAKIMI	11/0.415KV	300	11KV VILLAGE	1	Dec-22
DEEPER LIFE	11/0.415KV	500	11KV VILLAGE	1	Dec-22
UNGUWAN MAIGERO 7	11/0.415KV	500	11KV VILLAGE	1	Dec-22



KARI 1	11/0.415KV	300	11KV VILLAGE	1	Dec-22
KARI 2	11/0.415KV	500	11KV VILLAGE	1	Dec-22
NARAYI 9	11/0.415KV	300	11KV VILLAGE	1	Dec-22
UNGUWAR MAGERO 8	11/0.415KV	300	11KV VILLAGE	1	Dec-22
UNGUWAR MAGERO 9	11/0.415KV	300	11KV VILLAGE	1	Dec-22
TIPPER GARAGE 2	11/0.415KV	300	11KV VILLAGE	1	Dec-22
BORO 1	11/0.415KV	500	11KV PAMA	1	Dec-22
GURE	11/0.415KV	500	11KV PAMA	1	Dec-22
KINGS	11/0.415KV	300	11KV PAMA	1	Dec-22
MAISAMARI	11/0.415KV	300	11KV PAMA	1	Dec-22
PAMA 1	11/0.415KV	500	11KV PAMA	1	Dec-22
PAMA 2	11/0.415KV	500	11KV PAMA	1	Dec-22
PAMA 3	11/0.415KV	500	11KV PAMA	1	Dec-22
PAMA 4	11/0.415KV	300	11KV PAMA	1	Dec-22
PAMA 5	11/0.415KV	500	11KV PAMA	1	Dec-22
PAMA 6	11/0.415KV	300	11KV PAMA	1	Dec-22
PAMA 7	11/0.415KV	300	11KV PAMA	1	Dec-22
YERIMA	11/0.415KV	300	11KV PAMA	1	Dec-22
NASSARAWA	11/0.415KV	500	11KV PAMA	1	Dec-22
Abakpa / Rai 2	11/0.415KV	300	11KV NDA	1	Dec-22
Abakpa 1/ rail 1	11/0.415KV	500	11KV NDA	1	Dec-22
Mosaliaci 1	11/0.415KV	500	11KV NDA	1	Dec-22
Mosaliaci 2	11/0.415KV	300	11KV NDA	1	Dec-22
Yantaba Road	11/0.415KV	500	11KV NDA	1	Dec-22
YANTABA 2	11/0.415KV	300	11KV NDA	1	Dec-22
ADAMS	11/0.415KV	500	11KV NDA	1	Dec-22
BARRACKS 1	11/0.415KV	300	11KV NDA	1	Dec-22
BARRACKS 2	11/0.415KV	300	11KV NDA	1	Dec-22
Aliyu Moh'd Jamma 1	11/0.415KV	300	11KV NDA	1	Dec-22
Aliyu Moh'd Jamma 2	11/0.415KV	300	11KV NDA	1	Dec-22
Bola	11/0.415KV	500	11KV NDA	1	Dec-22
Alhumaah Clinic	11/0.415KV	300	11KV NDA	1	Dec-22

ALHUMAH CLINIC 2	11/0.415KV	300	11KV NDA	1	Dec-22
GIMI	11/0.415KV	300	11KV MC (DEDICATED)	1	Dec-22
RAILWAY 1	11/0.415KV	500	11KV MC (DEDICATED)	1	Dec-22
WOSONO VILLAGE	11/0.415KV	300	11KV MC (DEDICATED)	1	Dec-22
RAILWAY 2	11/0.415KV	300	11KV MC (DEDICATED)	1	Dec-22
CONOIL	11/0.415KV	500	11KV Dankande	1	Dec-22
DANJIANGA	11/0.415KV	300	11KV Dankande	1	Dec-22
DANKANDE 1	11/0.415KV	300	11KV Dankande	1	Dec-22
DANKANDE 2	11/0.415KV	300	11KV Dankande	1	Dec-22
DANMORI	11/0.415KV	500	11KV Dankande	1	Dec-22
DEVELOPMENT AREA 1	11/0.415KV	300	11KV Dankande	1	Dec-22
DEVELOPMENT AREA 2	11/0.415KV	300	11KV Dankande	1	Dec-22
GDS5 RIGACHICHUKUN	11/0.415KV	300	11KV Dankande	1	Dec-22
HAKIMI	11/0.415KV	300	11KV Dankande	1	Dec-22
HUSSAINI JALO	11/0.415KV	500	11KV Dankande	1	Dec-22
KIRAMA	11/0.415KV	300	11KV Dankande	1	Dec-22
MARKET	11/0.415KV	300	11KV Dankande	1	Dec-22
MASALLACI	11/0.415KV	500	11KV Dankande	1	Dec-22
POLICE BARRACK	11/0.415KV	300	11KV Dankande	1	Dec-22
SULEI MAILAMBU	11/0.415KV	500	11KV Dankande	1	Dec-22
UNGUWAR KADI	11/0.415KV	300	11KV Dankande	1	Dec-22
CONOIL 2	11/0.415KV	300	11KV Dankande	1	Dec-22
SARKIN FULANI	11/0.415KV	500	11KV Dankande	1	Dec-22
M.D YUSUF	11/0.415KV	300	11KV Dankande	1	Dec-22
NEW DEVELOPMENT AREA	11/0.415KV	300	11KV Dankande	1	Dec-22
DEVELOPMENT AREA 3 (DB ESTATE 1)	11/0.415KV	500	11KV Dankande	1	Dec-22
NEW DEVELOPMENT	11/0.415KV	300	11KV Dankande	1	Dec-22
JUSTICE TANIMU ZAILANI	11/0.415KV	300	11KV Dankande	1	Dec-22
2 Bedroom SMC	11/0.415KV	500	11KV StateHouse	1	Dec-22
Baba Marfe road	11/0.415KV	300	11KV StateHouse	1	Dec-22
Galadima road	11/0.415KV	300	11KV StateHouse	1	Dec-22



GGSS	11/0.415KV	300	11KV	StateHouse	1	Dec-22
Karaye road	11/0.415KV	500	11KV	StateHouse	1	Dec-22
KTC 1	11/0.415KV	500	11KV	StateHouse	1	Dec-22
KTC 2	11/0.415KV	300	11KV	StateHouse	1	Dec-22
KTC 3	11/0.415KV	300	11KV	StateHouse	1	Dec-22
Luchia road	11/0.415KV	500	11KV	StateHouse	1	Dec-22
SMC school	11/0.415KV	300	11KV	StateHouse	1	Dec-22
WAEC	11/0.415KV	300	11KV	StateHouse	1	Dec-22
3 bedroom	11/0.415KV	500	11KV	StateHouse	1	Dec-22
bakin layi	11/0.415KV	300	11KV	StateHouse	1	Dec-22
kawo junction 1	11/0.415KV	500	11KV	StateHouse	1	Dec-22
kawo junction 2	11/0.415KV	300	11KV	StateHouse	1	Dec-22
LAFIYA ROAD	11/0.415KV	300	11KV	StateHouse	1	Dec-22
BARAKALLAHU 1	11/0.415KV	300	11KV	Zaria Road	1	Dec-22
BARAKALLAHU 2	11/0.415KV	300	11KV	Zaria Road	1	Dec-22
BARAKALLAHU 3	11/0.415KV	300	11KV	Zaria Road	1	Dec-22
Habib T/School	11/0.415KV	500	11KV	Zaria Road	1	Dec-22
Trade Fair Complex 1	11/0.415KV	500	11KV	Zaria Road	1	Dec-22
Ungwar Gwari	11/0.415KV	500	11KV	Zaria Road	1	Dec-22
Engr. Bunzo	11/0.415KV	300	11KV	Zaria Road	1	Dec-22
Engr. Salisu	11/0.415KV	300	11KV	Zaria Road	1	Dec-22
Gidan Modara	11/0.415KV	300	11KV	Zaria Road	1	Dec-22
Harrisu Abubakar	11/0.415KV	300	11KV	Zaria Road	1	Dec-22
Hayin Naiya 1	11/0.415KV	500	11KV	Zaria Road	1	Dec-22
Hayin Naiya 2	11/0.415KV	500	11KV	Zaria Road	1	Dec-22
Molali Gabas	11/0.415KV	500	11KV	Zaria Road	1	Dec-22
MC	11/0.415KV	300	11KV	Zaria Road	1	Dec-22
Sabon layi	11/0.415KV	300	11KV	Zaria Road	1	Dec-22
Zangon Daura	11/0.415KV	500	11KV	Zaria Road	1	Dec-22
Zoure Village	11/0.415KV	300	11KV	Zaria Road	1	Dec-22
MAJOR JAFARU	11/0.415KV	500	11KV	Zaria Road	1	Dec-22
AVM NDANA	11/0.415KV	300	11KV	Zaria Road	1	Dec-22

KARAMA H/NAIYA	11/0.415KV	500	11KV Zaria Road	1	Dec-22
FASKARI ROAD	11/0.415KV	300	11KV Zaria Road	1	Dec-22
IDRIS BAWA	11/0.415KV	500	11KV Zaria Road	1	Dec-22
CONOIL	11/0.415KV	500	11KV Zaria Road	1	Dec-22
DANJIANGA	11/0.415KV	300	11KV Zaria Road	1	Dec-22
DANMORI	11/0.415KV	500	11KV Zaria Road	1	Dec-22
DEVELOPMENT AREA 1	11/0.415KV	300	11KV Zaria Road	1	Dec-22
DEVELOPMENT AREA 2	11/0.415KV	300	11KV Zaria Road	1	Dec-22
GDSS RIGACHICHUKUN	11/0.415KV	300	11KV Zaria Road	1	Dec-22
HAKIMI	11/0.415KV	300	11KV Zaria Road	1	Dec-22
HUSSAINI JALO	11/0.415KV	500	11KV Zaria Road	1	Dec-22
KIRAMA	11/0.415KV	300	11KV Zaria Road	1	Dec-22
MARKET	11/0.415KV	300	11KV Zaria Road	1	Dec-22
MASALLACI	11/0.415KV	500	11KV Zaria Road	1	Dec-22
SULEI MALLAMBU	11/0.415KV	500	11KV Zaria Road	1	Dec-22
UNGUWAR KADI	11/0.415KV	300	11KV Zaria Road	1	Dec-22
CONOIL 2	11/0.415KV	300	11KV Zaria Road	1	Dec-22
Barakallahu GRA 1	11/0.415KV	300	11KV Zaria Road	1	Dec-22
Barakallahu GRA 2	11/0.415KV	300	11KV Zaria Road	1	Dec-22
SARKIN FULANI	11/0.415KV	500	11KV Zaria Road	1	Dec-22
M.D YUSUF	11/0.415KV	300	11KV Zaria Road	1	Dec-22
NEW DEVELOPMENT AREA 3	11/0.415KV	300	11KV Zaria Road	1	Dec-22
DEVELOPMENT AREA 3	11/0.415KV	500	11KV Zaria Road	1	Dec-22
NEW DEVELOPMENT	11/0.415KV	300	11KV Zaria Road	1	Dec-22
BARAKALLAHU GRA 3	11/0.415KV	300	11KV Zaria Road	1	Dec-22
RIMI ROAD	11/0.415KV	300	11KV Zaria Road	1	Dec-22
AGRIC QUARTERS	11/0.415KV	300	11KV NAFBASE	1	Dec-22
Station	11/0.415KV	500	11KV NAFBASE	1	Dec-22
OMO Oirs	11/0.415KV	300	11KV NAFBASE	1	Dec-22
Station-2/workshop	11/0.415KV	500	11KV NAFBASE	1	Dec-22
Old Happy Valley	11/0.415KV	300	11KV NAFBASE	1	Dec-22
New Happy Valley	11/0.415KV	500	11KV NAFBASE	1	Dec-22



E:Blocks	11/0.415KV	500	11KV NAFBASE	1	Dec-22
JD Qtrs	11/0.415KV	500	11KV NAFBASE	1	Dec-22
Bhw JD Qtrs & 2nd Ofce Transit	11/0.415KV	300	11KV NAFBASE	1	Dec-22
CARDET QUARTERS	11/0.415KV	500	11KV NAFBASE	1	Dec-22
PROTESTANT CHURCH	11/0.415KV	300	11KV NAFBASE	1	Dec-22
HAPPYER YAU QTR	11/0.415KV	300	11KV NAFBASE	1	Dec-22
AIR MAN TRASIT CAMP	11/0.415KV	500	11KV NAFBASE	1	Dec-22
Doka Matlamu'a	11/0.415KV	300	11KV MALALI	1	Dec-22
Halliru Dan Toro	11/0.415KV	300	11KV MALALI	1	Dec-22
KEKE VILLAGE	11/0.415KV	300	11KV MALALI	1	Dec-22
Jafaru Israh Close	11/0.415KV	500	11KV MALALI	1	Dec-22
Lesbora	11/0.415KV	300	11KV MALALI	1	Dec-22
Likita Road	11/0.415KV	300	11KV MALALI	1	Dec-22
SabanGero	11/0.415KV	300	11KV MALALI	1	Dec-22
Anguwar Shekero layoul	11/0.415KV	300	11KV MALALI	1	Dec-22
Bola	11/0.415KV	300	11KV MALALI	1	Dec-22
Dakoché	11/0.415KV	500	11KV MALALI	1	Dec-22
EI -Natohy Close	11/0.415KV	500	11KV MALALI	1	Dec-22
F.G.C. Malali	11/0.415KV	300	11KV MALALI	1	Dec-22
FRCN Qtrs	11/0.415KV	300	11KV MALALI	1	Dec-22
FRCN	11/0.415KV	500	11KV MALALI	1	Dec-22
Kenya road	11/0.415KV	300	11KV MALALI	1	Dec-22
LEA Primary School	11/0.415KV	300	11KV MALALI	1	Dec-22
Moi Anguwar Isahaya	11/0.415KV	500	11KV MALALI	1	Dec-22
Sani Sami	11/0.415KV	500	11KV MALALI	1	Dec-22
Sewage road	11/0.415KV	500	11KV MALALI	1	Dec-22
St. Monica Church	11/0.415KV	500	11KV MALALI	1	Dec-22
Umaru Mohammed	11/0.415KV	300	11KV MALALI	1	Dec-22
Water Board Quarters	11/0.415KV	300	11KV MALALI	1	Dec-22
Zambia/Gambia road	11/0.415KV	500	11KV MALALI	1	Dec-22
Mamman Vaisa	11/0.415KV	300	11KV MALALI	1	Dec-22
Keke 1	11/0.415KV	300	11KV MALALI	1	Dec-22

KEKE PRIMARY	11/0.415KV	300	11KV MALALI	1	Dec-22
DAUDA DAJIN	11/0.415KV	300	11KV MALALI	1	Dec-22
NEW LAYOUT	11/0.415KV	300	11KV MALALI	1	Dec-22
ANGUWMAN SHEKARA 2	11/0.415KV	500	11KV MALALI	1	Dec-22
Bannu Gade Sub-Station	33/0.415KV	300	33KV JEGA	1	Dec-22
Boloro Gadi Sub-Station	33/0.415KV	300	33KV JEGA	1	Dec-22
Dangamaji Sub-Station	33/0.415KV	300	33KV JEGA	1	Dec-22
Gamjeji Sub-Station	33/0.415KV	300	33KV JEGA	1	Dec-22
Giwa Tazo Sub-Station 1	33/0.415KV	300	33KV JEGA	1	Dec-22
Giwa Tazo Sub-Station 2	33/0.415KV	300	33KV JEGA	1	Dec-22
Gumbin Kure Sub-Station	33/0.415KV	300	33KV JEGA	1	Dec-22
Mayalo Sub-Station	33/0.415KV	500	33KV JEGA	1	Dec-22
Mungadi Sub-Station	33/0.415KV	300	33KV JEGA	1	Dec-22
Runfa Sub-Station	33/0.415KV	300	33KV JEGA	1	Dec-22
Sambawa Sub-Station	33/0.415KV	300	33KV JEGA	1	Dec-22
Unguwar Abu/Auta Sub-Station	33/0.415KV	300	33KV JEGA	1	Dec-22
Unguwar Shuabau Sub-Station	33/0.415KV	300	33KV JEGA	1	Dec-22
Aida	33/0.415KV	300	33KV JEGA	1	Dec-22
ALHAI BELLO ZAKI	33/0.415KV	300	33KV JEGA	1	Dec-22
BAGUDU MIRDI	33/0.415KV	500	33KV JEGA	1	Dec-22
BASAURA 1	33/0.415KV	500	33KV JEGA	1	Dec-22
BASAURA 2	33/0.415KV	300	33KV JEGA	1	Dec-22
Danwo	33/0.415KV	300	33KV JEGA	1	Dec-22
GANDU	33/0.415KV	300	33KV JEGA	1	Dec-22
HARASAWA	33/0.415KV	300	33KV JEGA	1	Dec-22
HIRISHII	33/0.415KV	300	33KV JEGA	1	Dec-22
HUDA SUSTATION	33/0.415KV	300	33KV JEGA	1	Dec-22
JANBAKI	33/0.415KV	500	33KV JEGA	1	Dec-22
KARDI 1	33/0.415KV	300	33KV JEGA	1	Dec-22
KARDI 2	33/0.415KV	300	33KV JEGA	1	Dec-22
KARDI 3	33/0.415KV	500	33KV JEGA	1	Dec-22
KARDI NARBA	33/0.415KV	300	33KV JEGA	1	Dec-22



KARDI	33/0.415KV	500	33KV JEGA	1	Dec-22
Kwailfo	33/0.415KV	500	33KV JEGA	1	Dec-22
LANGIDO	33/0.415KV	300	33KV JEGA	1	Dec-22
MAGARE (PROPOSE)	33/0.415KV	500	33KV JEGA	1	Dec-22
MALAM ALTINE KALGO	33/0.415KV	500	33KV JEGA	1	Dec-22
MATAN KARI	33/0.415KV	300	33KV JEGA	1	Dec-22
MAZA GOMA	33/0.415KV	300	33KV JEGA	1	Dec-22
N.TA	33/0.415KV	300	33KV JEGA	1	Dec-22
NIJAWA	33/0.415KV	500	33KV JEGA	1	Dec-22
Sagaworoda	33/0.415KV	300	33KV JEGA	1	Dec-22
SARKI	33/0.415KV	300	33KV JEGA	1	Dec-22
TASHAN KALGO	33/0.415KV	300	33KV JEGA	1	Dec-22
UNGUWAN DIKKO	33/0.415KV	300	33KV JEGA	1	Dec-22
UNGUWAN NA HUDA	33/0.415KV	300	33KV JEGA	1	Dec-22
UNGUWAR LELE	33/0.415KV	300	33KV JEGA	1	Dec-22
UNIVERSITY SCHOOL	33/0.415KV	500	33KV JEGA	1	Dec-22
UNIVERSITY STAFF QUARTERS	33/0.415KV	500	33KV JEGA	1	Dec-22
YA MAMA	33/0.415KV	300	33KV JEGA	1	Dec-22
YAR KANGWA	33/0.415KV	300	33KV JEGA	1	Dec-22
Achikarolu	33/0.415KV	300	33KV JEGA	1	Dec-22
Akalawa	33/0.415KV	300	33KV JEGA	1	Dec-22
Akwoda	33/0.415KV	300	33KV JEGA	1	Dec-22
Alelu	33/0.415KV	500	33KV JEGA	1	Dec-22
Andarai 1	33/0.415KV	500	33KV JEGA	1	Dec-22
Andarai 2	33/0.415KV	500	33KV JEGA	1	Dec-22
Bimbin Madi	33/0.415KV	300	33KV JEGA	1	Dec-22
Dogon Daji	33/0.415KV	300	33KV JEGA	1	Dec-22
Dudduke	33/0.415KV	500	33KV JEGA	1	Dec-22
Duhuwa	33/0.415KV	300	33KV JEGA	1	Dec-22
Fogoda	33/0.415KV	300	33KV JEGA	1	Dec-22
G.G.S. School Suru	33/0.415KV	300	33KV JEGA	1	Dec-22
Genero Hospital Suru	33/0.415KV	300	33KV JEGA	1	Dec-22

GIDAN COMMISSIONER	33/0.415KV	500	33KV JEGA	1	Dec-22
Gidigo	33/0.415KV	300	33KV JEGA	1	Dec-22
Gindi	33/0.415KV	300	33KV JEGA	1	Dec-22
Gindi Tasho	33/0.415KV	300	33KV JEGA	1	Dec-22
Giro	33/0.415KV	300	33KV JEGA	1	Dec-22
Giwatozo 1	33/0.415KV	300	33KV JEGA	1	Dec-22
Giwatozo 2	33/0.415KV	300	33KV JEGA	1	Dec-22
Gwahwadi	33/0.415KV	300	33KV JEGA	1	Dec-22
Hoire	33/0.415KV	500	33KV JEGA	1	Dec-22
Ingarje	33/0.415KV	300	33KV JEGA	1	Dec-22
Jondutsi	33/0.415KV	500	33KV JEGA	1	Dec-22
Jondutsi	33/0.415KV	300	33KV JEGA	1	Dec-22
Kankarwai	33/0.415KV	300	33KV JEGA	1	Dec-22
Karoye 1	33/0.415KV	500	33KV JEGA	1	Dec-22
Karoye 2	33/0.415KV	300	33KV JEGA	1	Dec-22
Katanga	33/0.415KV	300	33KV JEGA	1	Dec-22
Kaworo	33/0.415KV	500	33KV JEGA	1	Dec-22
Kaworo Mai Ruwa	33/0.415KV	300	33KV JEGA	1	Dec-22
Kimba 1	33/0.415KV	300	33KV JEGA	1	Dec-22
Kimba 2	33/0.415KV	300	33KV JEGA	1	Dec-22
Kuchi Kasuwo	33/0.415KV	300	33KV JEGA	1	Dec-22
Kuchi Tasho	33/0.415KV	300	33KV JEGA	1	Dec-22
Kulone	33/0.415KV	300	33KV JEGA	1	Dec-22
Kurun Kudi	33/0.415KV	300	33KV JEGA	1	Dec-22
Lafiya	33/0.415KV	300	33KV JEGA	1	Dec-22
Liba	33/0.415KV	300	33KV JEGA	1	Dec-22
Lugu	33/0.415KV	300	33KV JEGA	1	Dec-22
MaiTawoye	33/0.415KV	300	33KV JEGA	1	Dec-22
Maiyama Local Government	33/0.415KV	300	33KV JEGA	1	Dec-22
Maiyama Sabongari	33/0.415KV	300	33KV JEGA	1	Dec-22
Maiyama Tschuwar Tasho	33/0.415KV	300	33KV JEGA	1	Dec-22
Rafin Guzuma	33/0.415KV	500	33KV JEGA	1	Dec-22



Bumare	33/0.415KV	300	33KV JEGA	1	Dec-22
Ruwon Fili	33/0.415KV	300	33KV JEGA	1	Dec-22
Saban Sara	33/0.415KV	300	33KV JEGA	1	Dec-22
Sabongari	33/0.415KV	300	33KV JEGA	1	Dec-22
Saran Dosa	33/0.415KV	300	33KV JEGA	1	Dec-22
Suru 1	33/0.415KV	300	33KV JEGA	1	Dec-22
Suru 2	33/0.415KV	300	33KV JEGA	1	Dec-22
Suru 3	33/0.415KV	500	33KV JEGA	1	Dec-22
Suru Town	33/0.415KV	300	33KV JEGA	1	Dec-22
Tulaye	33/0.415KV	300	33KV JEGA	1	Dec-22
Tunga	33/0.415KV	300	33KV JEGA	1	Dec-22
Ungwar Kurya	33/0.415KV	300	33KV JEGA	1	Dec-22
Zaro 1	33/0.415KV	300	33KV JEGA	1	Dec-22
Zaro 2	33/0.415KV	300	33KV JEGA	1	Dec-22
Ungwar Bakari	33/0.415KV	300	33KV JEGA	1	Dec-22
Ungwar Madi	33/0.415KV	300	33KV JEGA	1	Dec-22
Ungwar Dakko	33/0.415KV	300	33KV JEGA	1	Dec-22
Tsalbi	33/0.415KV	300	33KV JEGA	1	Dec-22
Birin Malam	33/0.415KV	300	33KV JEGA	1	Dec-22
Rafin Nagindi	33/0.415KV	300	33KV JEGA	1	Dec-22
Dan Tawaye	33/0.415KV	300	33KV JEGA	1	Dec-22
Sonagi	33/0.415KV	300	33KV JEGA	1	Dec-22
Karba	33/0.415KV	300	33KV JEGA	1	Dec-22
Gubba	33/0.415KV	300	33KV JEGA	1	Dec-22
Ungwar Roziku	33/0.415KV	300	33KV JEGA	1	Dec-22
Aisha Bukari Hospital	33/0.415KV	300	33KV JEGA	1	Dec-22
Tsiriri	33/0.415KV	300	33KV JEGA	1	Dec-22
KANGIWA	33/0.415KV	300	33KV JEGA	1	Dec-22
UNGUWAR LARABA	33/0.415KV	300	33KV JEGA	1	Dec-22
UNGUWAR TUDU	33/0.415KV	300	33KV JEGA	1	Dec-22
KWARIKWASA	33/0.415KV	300	33KV JEGA	1	Dec-22
ANDARAI	33/0.415KV	300	33KV JEGA	1	Dec-22

MAI KUNFAN GIDA	33/0.415KV	300	33KV JEGA	1	Dec-22
DADIN KOWA	33/0.415KV	300	33KV JEGA	1	Dec-22
BIRI	33/0.415KV	300	33KV JEGA	1	Dec-22
MUNGADI II	33/0.415KV	300	33KV JEGA	1	Dec-22
MUNGADI III	33/0.415KV	300	33KV JEGA	1	Dec-22
GIRAWA OIL & GAS	33/0.415KV	300	33KV JEGA	1	Dec-22
GINDI 2	33/0.415KV	300	33KV JEGA	1	Dec-22
NIKI	33/0.415KV	300	33KV JEGA	1	Dec-22
Chiko	11/0.415KV	300	11KV GRA JEGA	1	Dec-22
Lawalli Dan Aggo	11/0.415KV	500	11KV GRA JEGA	1	Dec-22
Raudah	11/0.415KV	300	11KV GRA JEGA	1	Dec-22
Audu Soda	11/0.415KV	300	11KV GRA JEGA	1	Dec-22
Boyan Asibiti	11/0.415KV	300	11KV GRA JEGA	1	Dec-22
BLB	11/0.415KV	500	11KV GRA JEGA	1	Dec-22
Business Unit	11/0.415KV	500	11KV GRA JEGA	1	Dec-22
Dan Majalisa	11/0.415KV	300	11KV GRA JEGA	1	Dec-22
G.R.A 1	11/0.415KV	500	11KV GRA JEGA	1	Dec-22
G.R.A 2	11/0.415KV	500	11KV GRA JEGA	1	Dec-22
Garba Kirki	11/0.415KV	500	11KV GRA JEGA	1	Dec-22
Garke Soriki	11/0.415KV	500	11KV GRA JEGA	1	Dec-22
Gidan Ruwa	11/0.415KV	500	11KV GRA JEGA	1	Dec-22
Gingo	11/0.415KV	300	11KV GRA JEGA	1	Dec-22
Hajiya Hauwa	11/0.415KV	300	11KV GRA JEGA	1	Dec-22
Health Technology	11/0.415KV	500	11KV GRA JEGA	1	Dec-22
Kanwa	11/0.415KV	500	11KV GRA JEGA	1	Dec-22
Kara	11/0.415KV	500	11KV GRA JEGA	1	Dec-22
Labbo gehuru	11/0.415KV	500	11KV GRA JEGA	1	Dec-22
Lowal Buhari	11/0.415KV	300	11KV GRA JEGA	1	Dec-22
N.Y.S.C	11/0.415KV	500	11KV GRA JEGA	1	Dec-22
Nassarawa	11/0.415KV	500	11KV GRA JEGA	1	Dec-22
New Water Board	11/0.415KV	500	11KV GRA JEGA	1	Dec-22
NITEL	11/0.415KV	300	11KV GRA JEGA	1	Dec-22



Rini	11/0.415KV	500	11KV GRA JEGA	1	Dec-22
Samusi Namodina	11/0.415KV	500	11KV GRA JEGA	1	Dec-22
Speaker	11/0.415KV	300	11KV GRA JEGA	1	Dec-22
Street light	11/0.415KV	300	11KV GRA JEGA	1	Dec-22
Tarbuda	11/0.415KV	300	11KV GRA JEGA	1	Dec-22
Turahi	11/0.415KV	300	11KV GRA JEGA	1	Dec-22
Yankifi	11/0.415KV	300	11KV GRA JEGA	1	Dec-22
T.E	11/0.415KV	500	11KV GRA JEGA	1	Dec-22
Dean Lami Mai ruwa	11/0.415KV	500	11KV GRA JEGA	1	Dec-22
Bonus	11/0.415KV	500	11KV GRA JEGA	1	Dec-22
Makabarta	11/0.415KV	500	11KV GRA JEGA	1	Dec-22
Adan Iliya	11/0.415KV	500	11KV GRA JEGA	1	Dec-22
Kwanawa	11/0.415KV	500	11KV GRA JEGA	1	Dec-22
Kaura	11/0.415KV	500	11KV GRA JEGA	1	Dec-22
Gingo	11/0.415KV	300	11KV GRA JEGA	1	Dec-22
BAKA	11/0.415KV	300	11KV UNGUWAN YELWA	1	Dec-22
BUSA	11/0.415KV	500	11KV UNGUWAN YELWA	1	Dec-22
CHIROMA	11/0.415KV	500	11KV UNGUWAN YELWA	1	Dec-22
HALIMA	11/0.415KV	300	11KV UNGUWAN YELWA	1	Dec-22
MAKARANTA	11/0.415KV	300	11KV UNGUWAN YELWA	1	Dec-22
SAMARI	11/0.415KV	500	11KV UNGUWAN YELWA	1	Dec-22
SHAMAKI 1	11/0.415KV	500	11KV UNGUWAN YELWA	1	Dec-22
SHAMAKI 2	11/0.415KV	500	11KV UNGUWAN YELWA	1	Dec-22
TELEVISION GRA	11/0.415KV	300	11KV UNGUWAN YELWA	1	Dec-22
TELEVISION MARKET	11/0.415KV	500	11KV UNGUWAN YELWA	1	Dec-22
UNGUWAR SUNDAY 1	11/0.415KV	500	11KV UNGUWAN YELWA	1	Dec-22
UNGUWAR SUNDAY 2	11/0.415KV	500	11KV UNGUWAN YELWA	1	Dec-22
UNGUWAR SUNDAY 3	11/0.415KV	500	11KV UNGUWAN YELWA	1	Dec-22
WILSON	11/0.415KV	500	11KV UNGUWAN YELWA	1	Dec-22
ECWA	11/0.415KV	500	11KV UNGUWAN YELWA	1	Dec-22
NAMSO	11/0.415KV	500	11KV UNGUWAN YELWA	1	Dec-22
Makoronto 2	11/0.415KV	300	11KV UNGUWAN YELWA	1	Dec-22

AGYEITA	11/0.415KV	300	11KV FEDERAL HOUSING	1	Dec-22
UNGUWAR TANKO 1	11/0.415KV	500	11KV FEDERAL HOUSING	1	Dec-22
UNGUWAR TANKO 2	11/0.415KV	300	11KV FEDERAL HOUSING	1	Dec-22
UNGUWAN WAZIRI 1	11/0.415KV	500	11KV FEDERAL HOUSING	1	Dec-22
UNGUWAN WAZIRI 2	11/0.415KV	300	11KV FEDERAL HOUSING	1	Dec-22
BENKAY	11/0.415KV	300	11KV FEDERAL HOUSING	1	Dec-22
CHURCH ROAD (KARATUDU 1)	11/0.415KV	300	11KV FEDERAL HOUSING	1	Dec-22
DYNAMIC	11/0.415KV	300	11KV FEDERAL HOUSING	1	Dec-22
FEDERAL HOUSING 1	11/0.415KV	500	11KV FEDERAL HOUSING	1	Dec-22
GONIN GORA MARKET	11/0.415KV	500	11KV FEDERAL HOUSING	1	Dec-22
DURUMI NEW EXTENSION 2	11/0.415KV	500	11KV FEDERAL HOUSING	1	Dec-22
HAYIN KATAFAWA	11/0.415KV	500	11KV FEDERAL HOUSING	1	Dec-22
JAMA'A ROAD	11/0.415KV	500	11KV FEDERAL HOUSING	1	Dec-22
KARATUDU MARKET 1	11/0.415KV	300	11KV FEDERAL HOUSING	1	Dec-22
KININKO	11/0.415KV	300	11KV FEDERAL HOUSING	1	Dec-22
ROMI NEW EXTENSION 1	11/0.415KV	500	11KV FEDERAL HOUSING	1	Dec-22
ROMI NEW EXTENSION 2	11/0.415KV	300	11KV FEDERAL HOUSING	1	Dec-22
NICON WATER	11/0.415KV	500	11KV FEDERAL HOUSING	1	Dec-22
AGWAN TANKO 4	11/0.415KV	300	11KV FEDERAL HOUSING	1	Dec-22
ANGUWAR SAURI	11/0.415KV	500	11KV FEDERAL HOUSING	1	Dec-22
NEW FEDERAL HOUSING ESTATE	11/0.415KV	500	11KV FEDERAL HOUSING	1	Dec-22
AGETA RELIEF	11/0.415KV	300	11KV FEDERAL HOUSING	1	Dec-22
ANGUWAR SAURI 2	11/0.415KV	500	11KV FEDERAL HOUSING	1	Dec-22
DIC	11/0.415KV	300	11KV BARNAWA MKR	1	Dec-22
GIDAN ZAKI 1	11/0.415KV	500	11KV BARNAWA MKR	1	Dec-22
GIDAN ZAKI 2	11/0.415KV	300	11KV BARNAWA MKR	1	Dec-22
GONGOLA	11/0.415KV	500	11KV BARNAWA MKR	1	Dec-22
K. T. 1 QUARTERS	11/0.415KV	500	11KV BARNAWA MKR	1	Dec-22
KUBANI	11/0.415KV	300	11KV BARNAWA MKR	1	Dec-22
NEW BARNAWA	11/0.415KV	500	11KV BARNAWA MKR	1	Dec-22
OLD BARNAWA	11/0.415KV	500	11KV BARNAWA MKR	1	Dec-22
THOMAS WATTS	11/0.415KV	300	11KV BARNAWA MKR	1	Dec-22



CHIROMA	11/0.415KV	500	11KV BARNAWA MKR	1	Dec-22
BABANDODO ROAD	11/0.415KV	500	11KV KAKURI	1	Dec-22
BAMED 1	11/0.415KV	300	11KV KAKURI	1	Dec-22
BAMED 2	11/0.415KV	300	11KV KAKURI	1	Dec-22
COURT ROAD	11/0.415KV	300	11KV KAKURI	1	Dec-22
DADIN KOWA	11/0.415KV	300	11KV KAKURI	1	Dec-22
DANDALI	11/0.415KV	500	11KV KAKURI	1	Dec-22
FASKARE STREET	11/0.415KV	500	11KV KAKURI	1	Dec-22
GALADIMAWA 1	11/0.415KV	500	11KV KAKURI	1	Dec-22
GALADIMAWA 2	11/0.415KV	500	11KV KAKURI	1	Dec-22
GALADIMAWA 3	11/0.415KV	300	11KV KAKURI	1	Dec-22
GAMBARAWA	11/0.415KV	500	11KV KAKURI	1	Dec-22
GENERAL HOSPITAL 1	11/0.415KV	300	11KV KAKURI	1	Dec-22
GRA 1	11/0.415KV	500	11KV KAKURI	1	Dec-22
GRA 2	11/0.415KV	500	11KV KAKURI	1	Dec-22
HAKIMI	11/0.415KV	500	11KV KAKURI	1	Dec-22
KAKURI BUSTOP	11/0.415KV	500	11KV KAKURI	1	Dec-22
KURMIN GWARI 1	11/0.415KV	500	11KV KAKURI	1	Dec-22
KURMIN GWARI 2	11/0.415KV	300	11KV KAKURI	1	Dec-22
LAFIA ROAD	11/0.415KV	300	11KV KAKURI	1	Dec-22
MANI ROAD	11/0.415KV	300	11KV KAKURI	1	Dec-22
PAWA ROAD	11/0.415KV	500	11KV KAKURI	1	Dec-22
SOKOTO ROAD 1	11/0.415KV	500	11KV KAKURI	1	Dec-22
SOKOTO ROAD 2	11/0.415KV	300	11KV KAKURI	1	Dec-22
UNGUWAR MISSION	11/0.415KV	500	11KV KAKURI	1	Dec-22
WAKILI	11/0.415KV	500	11KV KAKURI	1	Dec-22
WAZOBIA	11/0.415KV	500	11KV KAKURI	1	Dec-22
GMP 1	11/0.415KV	500	11KV NORTEX	1	Dec-22
KADUNA ELECTRIC AREA OFFICE	11/0.415KV	300	11KV NORTEX	1	Dec-22
KURMIN GWARI AFAKA	11/0.415KV	500	11KV NORTEX	1	Dec-22
STRIKE FORCE	11/0.415KV	500	11KV NORTEX	1	Dec-22
ZICORIKO 1	11/0.415KV	300	11KV SUNGLASS	1	Dec-22



ZICRIKO 2	11/0.415KV	300	11KV SUNGLASS	1	Dec-22
UNGUWAN RAMI	11/0.415KV	500	11KV AREWA BOTTLERS	1	Dec-22
HAUSAWA	11/0.415KV	500	11KV AREWA BOTTLERS	1	Dec-22
CHRISTIAN PILGRIM WELFARE BOARD	11/0.415KV	300	11KV AREWA BOTTLERS	1	Dec-22
CHURCH ROAD	11/0.415KV	500	11KV AREWA BOTTLERS	1	Dec-22
COMMITTEE	11/0.415KV	500	11KV AREWA BOTTLERS	1	Dec-22
FULANI	11/0.415KV	500	11KV AREWA BOTTLERS	1	Dec-22
GBAGYI VILLA 1	11/0.415KV	500	11KV AREWA BOTTLERS	1	Dec-22
GBAGYI VILLA 2	11/0.415KV	500	11KV AREWA BOTTLERS	1	Dec-22
MANYA	11/0.415KV	300	11KV AREWA BOTTLERS	1	Dec-22
MASSALLACI 1	11/0.415KV	500	11KV AREWA BOTTLERS	1	Dec-22
MASSALLACI 2	11/0.415KV	500	11KV AREWA BOTTLERS	1	Dec-22
PHCN	11/0.415KV	500	11KV AREWA BOTTLERS	1	Dec-22
POLY QUATERS 1	11/0.415KV	300	11KV AREWA BOTTLERS	1	Dec-22
ROMI BUSTOP	11/0.415KV	500	11KV AREWA BOTTLERS	1	Dec-22
ROMI NEW EXTENSION 3	11/0.415KV	500	11KV AREWA BOTTLERS	1	Dec-22
SAGBAGI 1	11/0.415KV	500	11KV AREWA BOTTLERS	1	Dec-22
SAGBAGI 2	11/0.415KV	300	11KV AREWA BOTTLERS	1	Dec-22
SAGBAGI 3	11/0.415KV	500	11KV AREWA BOTTLERS	1	Dec-22
LOCAL GVT	11/0.415KV	300	11KV AREWA BOTTLERS	1	Dec-22
MARIGOLD	11/0.415KV	500	11KV AREWA BOTTLERS	1	Dec-22
COMMISSIONER	11/0.415KV	500	11KV AREWA BOTTLERS	1	Dec-22
TIMBER GLOSE 1	11/0.415KV	300	11KV AREWA BOTTLERS	1	Dec-22
NAGARTA FEEDS	33/0.415KV	300	33KV PAN	1	Dec-22
NAGARTA 2	33/0.415KV	300	33KV PAN	1	Dec-22
NAGARTA 3	33/0.415KV	500	33KV PAN	1	Dec-22
Aldifa No 1	11/0.415KV	300	11KV NTA SOK	1	Dec-22
Aldifa No 2	11/0.415KV	500	11KV NTA SOK	1	Dec-22
Aliku	11/0.415KV	300	11KV NTA SOK	1	Dec-22
Aliku No 2	11/0.415KV	500	11KV NTA SOK	1	Dec-22
Base Road No 1	11/0.415KV	500	11KV NTA SOK	1	Dec-22



Base Road No 2	11/0.415KV	500	11KV NTA SOK	1	Dec-22
Danko Road	11/0.415KV	300	11KV NTA SOK	1	Dec-22
Double 7	11/0.415KV	300	11KV NTA SOK	1	Dec-22
First Bank Fodio Road	11/0.415KV	300	11KV NTA SOK	1	Dec-22
FIRST BANK	11/0.415KV	300	11KV NTA SOK	1	Dec-22
GANDU RELIEF	11/0.415KV	300	11KV NTA SOK	1	Dec-22
Gidan kuka 1	11/0.415KV	300	11KV NTA SOK	1	Dec-22
Gidan kuka 2	11/0.415KV	300	11KV NTA SOK	1	Dec-22
Goster	11/0.415KV	300	11KV NTA SOK	1	Dec-22
Ibro Hotel	11/0.415KV	300	11KV NTA SOK	1	Dec-22
Incubation Centre	11/0.415KV	300	11KV NTA SOK	1	Dec-22
Kangiwa Road No 2	11/0.415KV	500	11KV NTA SOK	1	Dec-22
Kangiwa Road No 1	11/0.415KV	300	11KV NTA SOK	1	Dec-22
Kato Bakwai	11/0.415KV	500	11KV NTA SOK	1	Dec-22
Makwashe	11/0.415KV	300	11KV NTA SOK	1	Dec-22
Meat & Vegetable Mkt	11/0.415KV	300	11KV NTA SOK	1	Dec-22
Muntari Maligona	11/0.415KV	500	11KV NTA SOK	1	Dec-22
N . T . A .	11/0.415KV	300	11KV NTA SOK	1	Dec-22
PHCN	11/0.415KV	500	11KV NTA SOK	1	Dec-22
Police Barrack	11/0.415KV	300	11KV NTA SOK	1	Dec-22
R E B STORE SOKOTO	11/0.415KV	300	11KV NTA SOK	1	Dec-22
Raro	11/0.415KV	500	11KV NTA SOK	1	Dec-22
Shara	11/0.415KV	300	11KV NTA SOK	1	Dec-22
State Medical store	11/0.415KV	300	11KV NTA SOK	1	Dec-22
Surejo Kure Market	11/0.415KV	300	11KV NTA SOK	1	Dec-22
TECHNICAL COLLEGE	11/0.415KV	300	11KV NTA SOK	1	Dec-22
Tudun Paiko 1	11/0.415KV	300	11KV NTA SOK	1	Dec-22
Tudun Paiko 2	11/0.415KV	300	11KV NTA SOK	1	Dec-22
University Girs	11/0.415KV	500	11KV NTA SOK	1	Dec-22
Yam Boko	11/0.415KV	300	11KV NTA SOK	1	Dec-22
POLICE BARRACK 2	11/0.415KV	500	11KV NTA SOK	1	Dec-22
TUDUN FALLA	11/0.415KV	500	11KV NTA SOK	1	Dec-22

KANGIWA ROAD 3	11/0.415KV	500	11KV NTA SOK	1	Dec-22
MAKWASHE 2	11/0.415KV	300	11KV NTA SOK	1	Dec-22
MAKABARTA RUMJIN SAMBO	11/0.415KV	300	11KV NTA SOK	1	Dec-22
Ungwar Dankali	11/0.415KV	300	11KV NNPC ZAR	1	Dec-22
Dammogaji MKT	11/0.415KV	500	11KV NNPC ZAR	1	Dec-22
Gabari Koroma	11/0.415KV	300	11KV NNPC ZAR	1	Dec-22
Hanwa Low Cost	11/0.415KV	300	11KV NNPC ZAR	1	Dec-22
Hanwa Road	11/0.415KV	500	11KV NNPC ZAR	1	Dec-22
Hanwa village	11/0.415KV	500	11KV NNPC ZAR	1	Dec-22
Hanwa Water Tank 1	11/0.415KV	500	11KV NNPC ZAR	1	Dec-22
Hanwa Water Tank 2	11/0.415KV	300	11KV NNPC ZAR	1	Dec-22
Hanwa Water Tank 3	11/0.415KV	300	11KV NNPC ZAR	1	Dec-22
Jim Harrison	11/0.415KV	500	11KV NNPC ZAR	1	Dec-22
Kuleno College	11/0.415KV	300	11KV NNPC ZAR	1	Dec-22
Kulenan Modaki	11/0.415KV	300	11KV NNPC ZAR	1	Dec-22
Kulenan Sarki	11/0.415KV	300	11KV NNPC ZAR	1	Dec-22
Kuregu	11/0.415KV	300	11KV NNPC ZAR	1	Dec-22
Rock Road	11/0.415KV	300	11KV NNPC ZAR	1	Dec-22
Sodaki Street	11/0.415KV	300	11KV NNPC ZAR	1	Dec-22
ST. Lukes Hospital	11/0.415KV	500	11KV NNPC ZAR	1	Dec-22
Tukur-Tukur 2	11/0.415KV	500	11KV NNPC ZAR	1	Dec-22
GONMAN GANYE	11/0.415KV	500	11KV NNPC ZAR	1	Dec-22
KWARIN AYUBA	11/0.415KV	300	11KV NNPC ZAR	1	Dec-22
TUKUR TUKUR REUEF	11/0.415KV	300	11KV NNPC ZAR	1	Dec-22
JIM HARRISON 2	11/0.415KV	500	11KV NNPC ZAR	1	Dec-22
ANGUWAR DANKALI	11/0.415KV	300	11KV NNPC ZAR	1	Dec-22
Jushin Waje	11/0.415KV	500	11KV SABON GARIN ZAR	1	Dec-22
Bakin Dogo	11/0.415KV	500	11KV Samaru	1	Dec-22
Biye Village	11/0.415KV	300	11KV Samaru	1	Dec-22
Damraka 1	11/0.415KV	500	11KV Samaru	1	Dec-22
Damraka 3	11/0.415KV	500	11KV Samaru	1	Dec-22
Damraka 2	11/0.415KV	500	11KV Samaru	1	Dec-22



FMW&H	11/0.415KV	300	11KV Samaru	1	Dec-22
Hoyin Damyaro	11/0.415KV	300	11KV Samaru	1	Dec-22
Hoyin Dogo 1	11/0.415KV	500	11KV Samaru	1	Dec-22
Hoyin Dogo 2	11/0.415KV	500	11KV Samaru	1	Dec-22
Hoyin Dogo 3	11/0.415KV	500	11KV Samaru	1	Dec-22
Hoyin Dogo 4	11/0.415KV	300	11KV Samaru	1	Dec-22
Hoyin Dogo 5	11/0.415KV	500	11KV Samaru	1	Dec-22
Hoyin Dogo 6	11/0.415KV	500	11KV Samaru	1	Dec-22
Layin Tsamiya Hoyin Dogo	11/0.415KV	500	11KV Samaru	1	Dec-22
IDC	11/0.415KV	300	11KV Samaru	1	Dec-22
Maimuna 1	11/0.415KV	500	11KV Samaru	1	Dec-22
Maimuna 2	11/0.415KV	500	11KV Samaru	1	Dec-22
New Extension	11/0.415KV	300	11KV Samaru	1	Dec-22
Sa'idu Primary	11/0.415KV	500	11KV Samaru	1	Dec-22
Sardouna Samaru	11/0.415KV	300	11KV Samaru	1	Dec-22
LAYIN BABURAWA	11/0.415KV	300	11KV Samaru	1	Dec-22
BABA KADUNA	11/0.415KV	300	11KV GASKIYA	1	Dec-22
BAKO ZUNTU	11/0.415KV	500	11KV GASKIYA	1	Dec-22
BAREWA COLLEGE	11/0.415KV	300	11KV GASKIYA	1	Dec-22
GASKIYA LAY OUT 1	11/0.415KV	300	11KV GASKIYA	1	Dec-22
IDRIS ABDUL	11/0.415KV	300	11KV GASKIYA	1	Dec-22
MAGUME 1	11/0.415KV	500	11KV GASKIYA	1	Dec-22
MAGUME 2	11/0.415KV	300	11KV GASKIYA	1	Dec-22
T/JUKUN 1	11/0.415KV	500	11KV GASKIYA	1	Dec-22
T/JUKUN 2	11/0.415KV	500	11KV GASKIYA	1	Dec-22
T/JUKUN 3	11/0.415KV	500	11KV GASKIYA	1	Dec-22
T/JUKUN 4	11/0.415KV	300	11KV GASKIYA	1	Dec-22
T/JUKUN 5	11/0.415KV	300	11KV GASKIYA	1	Dec-22
T/TUKUR JUNC	11/0.415KV	500	11KV GASKIYA	1	Dec-22
TUKUR TUKUR	11/0.415KV	300	11KV GASKIYA	1	Dec-22
ZAMFARA ROAD.	11/0.415KV	500	11KV GASKIYA	1	Dec-22
EMIR ROAD	11/0.415KV	300	11KV GASKIYA	1	Dec-22

MAGUME 3	11/0.415KV	300	11KV GASKIYA	1	Dec-22
GASKIYA LAY OUT 2	11/0.415KV	500	11KV GASKIYA	1	Dec-22
GASKIYA 3 (DANRAKA)	11/0.415KV	300	11KV GASKIYA	1	Dec-22
ADWAN	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
HOSPITAL	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
TM	11/0.415KV	300	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
BAUCHI 1	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
BAUCHI 2	11/0.415KV	300	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
KANO	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
ECWA	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
TAKAU /UNGUWAR MUSA	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
GGSS	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
TAKAU	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
REHAB	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
GDSS ROAD	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
UNIVERSITY RD	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
EMIR GATE	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
AREA COURT	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
ZARIA ST.	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
OLD MARKET	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
NITEL	11/0.415KV	300	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
TAKAU 2	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
TUDUN WADA	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
AMBAM	11/0.415KV	300	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
GOSKA	11/0.415KV	300	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
DANGOMA	11/0.415KV	300	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
BAKIN KOGI KANINKON	11/0.415KV	300	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
RAFIN DADI	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
SHOCK	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
UNGUWAR FARI	11/0.415KV	300	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
UNGUWAR BAKI 2	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
UNGUWAR BAKI 1	11/0.415KV	300	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22








BINZOM	11/0.415KV	300	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
UNGUWAR V I O	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
UNGUWAR JOGAI	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
DANNAGAJI	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
P J	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
BAKIN KOGI BAJIU	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
KASHAM	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
UNGUWAR YASHIN	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
ABUJA ST.	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
BAYAN LOCO 2	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
BAYAN LOCO 1	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
LOCO	11/0.415KV	300	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
SOKOTO STREET	11/0.415KV	300	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
LIVING FAITH	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
UNGUWAR LUKA	11/0.415KV	500	11KV KAFANCHAN (TOWNSHIP)	1	Dec-22
OFFICE	11/0.415KV	300	11KV BANK KAFANCHAN	1	Dec-22
11KV MAHUTA	11/0.415KV	500	11KV MAHUTA	3	
11KV PAMA	11/0.415KV	500	11KV PAMA	3	
11KV SABON TASHA	11/0.415KV	500	11KV SABON TASHA	3	
11KV VILLAGE	11/0.415KV	500	11KV VILLAGE	3	
11KV COSTAIN	11/0.415KV	500	11KV COSTAIN	3	
11KV KAWO	11/0.415KV	500	11KV KAWO	3	
11KV KURMIN MASHI	11/0.415KV	500	11KV KURMIN MASHI	3	
11KV MALAI	11/0.415KV	500	11KV MALAI	3	
11KV NAFBASE	11/0.415KV	500	11KV NAFBASE	3	
11KV NASFAT	11/0.415KV	500	11KV NASFAT	3	
11KV NDA	11/0.415KV	500	11KV NDA	3	
11KV NTA (DEDICATED)	11/0.415KV	500	11KV NTA (DEDICATED)	3	
11KV RABAH ROAD	11/0.415KV	500	11KV RABAH ROAD	3	
11KV RAFIN GUZA	11/0.415KV	500	11KV RAFIN GUZA	3	
11KV STATEHOUSE	11/0.415KV	500	11KV STATEHOUSE	3	
11KV ZARIA ROAD	11/0.415KV	500	11KV ZARIA ROAD	3	

11KV KARA	11/0.415KV	500	11KV KARA	3	
11KV NASSARAWA KBI	11/0.415KV	500	11KV NASSARAWA KBI	3	
11KV TUDUN WADA KBI	11/0.415KV	500	11KV TUDUN WADA KBI	3	
11KV AREWA BOTTLERS	11/0.415KV	500	11KV AREWA BOTTLERS	3	
11KV BARNAWA MKR	11/0.415KV	500	11KV BARNAWA MKR	3	
11KV CHEICO	11/0.415KV	500	11KV CHEICO	3	
11KV FEDERAL HOUSING	11/0.415KV	500	11KV FEDERAL HOUSING	3	
11KV KAKURI	11/0.415KV	500	11KV KAKURI	3	
11KV NOCACO	11/0.415KV	500	11KV NOCACO	3	
11KV NORTEX	11/0.415KV	500	11KV NORTEX	3	
11KV SUNGLASS	11/0.415KV	500	11KV SUNGLASS	3	
11KV UNGUWAN YELWA	11/0.415KV	500	11KV UNGUWAN YELWA	3	
11KV ASIKOLAYE	11/0.415KV	500	11KV ASIKOLAYE	3	
11KV HAYIN RIGASA	11/0.415KV	500	11KV HAYIN RIGASA	3	
11KV MAKARFI ROAD	11/0.415KV	500	11KV MAKARFI ROAD	3	
11KV MANDO ROAD	11/0.415KV	500	11KV MANDO ROAD	3	
11KV SABON GARIN RIG	11/0.415KV	500	11KV SABON GARIN RIG	3	
11KV TUDUN WADA RIG	11/0.415KV	500	11KV TUDUN WADA RIG	3	
11KV UNGUWAN MUAZU	11/0.415KV	500	11KV UNGUWAN MUAZU	3	
11KV WATER RESOURCES (DEDICATED)	11/0.415KV	500	11KV WATER RESOURCES (DEDICATED)	3	
11KV ARMY BARRACK	11/0.415KV	500	11KV ARMY BARRACK	3	
11KV DIORI HAMMANI	11/0.415KV	500	11KV DIORI HAMMANI	3	
11KV DURBAWA	11/0.415KV	500	11KV DURBAWA	3	
11KV FARFARU	11/0.415KV	500	11KV FARFARU	3	
11KV INDUSTRIAL SOK	11/0.415KV	500	11KV INDUSTRIAL SOK	3	
11KV KUEPPERS	11/0.415KV	500	11KV KUEPPERS	3	
11KV MABERA	11/0.415KV	500	11KV MABERA	3	
11KV NTA SOK	11/0.415KV	500	11KV NTA SOK	3	
11KV SULTAN PALACE	11/0.415KV	500	11KV SULTAN PALACE	3	
11KV TOWN	11/0.415KV	500	11KV TOWN	3	
11KV WATERWORKS SOK	11/0.415KV	500	11KV WATERWORKS SOK	3	

Handwritten signature in blue ink.



11KV DAMBA	11/0.415KV	500	11KV DAMBA	3	
11KV FGGC	11/0.415KV	500	11KV FGGC	3	
11KV GADA BIYU	11/0.415KV	500	11KV GADA BIYU	3	
11KV GRA ZAM	11/0.415KV	500	11KV GRA ZAM	3	
11KV INDUSTRIAL ZAM	11/0.415KV	500	11KV INDUSTRIAL ZAM	3	
11KV POLY GATE	11/0.415KV	500	11KV POLY GATE	3	
11KV SABON GARIN ZAM	11/0.415KV	500	11KV SABON GARIN ZAM	3	
11KV TUDUN WADA ZAM	11/0.415KV	500	11KV TUDUN WADA ZAM	3	
11KV WATER BOARD	11/0.415KV	500	11KV WATER BOARD	3	
11KV ZAMTEX	11/0.415KV	500	11KV ZAMTEX	3	
11KV DAM	11/0.415KV	500	11KV DAM	3	
11KV KOFAN KIBO	11/0.415KV	500	11KV KOFAN KIBO	3	
11KV NNPC ZAR	11/0.415KV	500	11KV NNPC ZAR	3	
11KV RIV/NTC	11/0.415KV	500	11KV RIV/NTC	3	
11KV SABON GARI ZAR	11/0.415KV	500	11KV SABON GARI ZAR	3	
11KV SAMARU	11/0.415KV	500	11KV SAMARU	3	
11KV TEACHING HOSPITAL ZAR	11/0.415KV	500	11KV TEACHING HOSPITAL ZAR	3	
11KV WUSASA	11/0.415KV	500	11KV WUSASA	3	
11KV ZARIA CITY	11/0.415KV	500	11KV ZARIA CITY	3	

Network: Injection Substations (33/11KV)

Project Type: Construction, Reinforcement and Standardisation of Injection Substation

#	Name of Substation	Location	N ^o of units	Rating - MVA	Project Completion Date (MM -YY)
1	NARAYI	Koduna	1	15	Feb-22
2	U/BORO	BARNAWA	1	15	Feb-22
3	POWER HOUSE	Sokoto	1	7.5	Apr-22
4	KAKURI	Rigasa	1	15	Apr-22
5	BOSTAL	Makera	2	15	Jun-22
6	KINKINAU	Zamfara	2	15	Jun-22

7	RUNJIN SAMBO	Sokoto	1	15	Aug-22	
8	ILELA ROAD	Sokoto	1	15	Aug-22	
9	GUSAU ROAD	Makera	1	7.5	Oct-22	
10	GAGI	Sokoto	1	15	Oct-22	
11	POWER STATION	Sokoto	1	7.5	Dec-22	
12	TOWNSHIP	Sokoto	1	15	Dec-22	
13	AVATION	Zaria	1	15	Dec-22	
14	ZARIA TS	Zaria	1	7.5	Oct-22	
15	HANWA	Zaria	1	15	Dec-22	
16	KOFAR DOKA	Zaria	1	15	Dec-22	
17	MAIN OFFICE	Zaria	1	15	Aug-22	

Network: Standardisation of Existing Injection Substations (33/11kV)

Project Type: Replacement of Switch Gears, Control Panel and Protection Equipment

#	Name of Substation	Description	Location	Quantity	Project Completion Date (MM - YY)
1	33KV JEGA	33kV indoor Control Panel		2	Dec-22
2	33KV NEW INJECTION	33kV indoor Control Panel	SOKOTO	1	Dec-22
3	33KV RIGASA	11kV indoor Control Panel	RIGASA	1	Dec-22
4	33KV JEGA	11kV indoor Control Panel	KEBBI	1	Dec-22
5	33KV RIGASA	33kV Voltage Transformer		1	Dec-22
6	33KV JEGA	33kV Voltage Transformer		1	Dec-22
7	33KV JEGA	110V Tripping Unit		1	Dec-22

AT&C Loss Reduction Plan

#	Name	Description	Quantity	Project Completion Date (MM - YY)



1	Normalization of customer connection point	Replacement of service cables, load balancing	30 customers	Nov-22
---	--	---	--------------	--------

Customer Service Improvement Plan

#	Name	Description	Quantity	Project Completion Date (MM - YY)
1	Customer relationship management system (CRM)		1	Nov-22

IT Investments (GIS)

#	Name	Description	Project Completion Date (MM - YY)
1	Geographical Information System (GIS) Phase 2	Deployment	Dec-22

IT Investments (ERP)

#	Name	Description	Project Completion Date (MM - YY)
1	Enterprise Resource Planning (Inventory, Procurement and Expense requisition)	Deployment	Dec-22

IT Investments (AMI)

#	Name	Description	Project Completion Date (MM - YY)
1	Revenue Protection Project (RPP) supported by Advanced Metering Infrastructure (AMI)-Phase 2	Deployment	Dec-22

Handwritten signature and initials in blue ink, located at the bottom right of the page.

Network Metering (Smart Meters)			
#	Project Description	Description	Quantity
1	DI Metering	DI Metering	1,800

IT Investments (SCADA)			
#	Name	Description	Project Completion Date (MM - YY)
	Works Management System (Field Force Automation)-Phase 2	Works Management System (Field Force Automation)-Phase 2	Dec-22
	Fibre Optics Internet Connectivity	Fibre optics connection for some priority injection substations	Dec-22

